


**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT ☐**APPLICATION FOR PERMIT TO DRILL**

<b>2. TYPE OF WORK</b> DRILL NEW WELL <input checked="" type="checkbox"/> REENTER P&A WELL <input type="checkbox"/> DEEPEN WELL <input type="checkbox"/>				<b>1. WELL NAME and NUMBER</b> NBU 922-31J2S		
<b>4. TYPE OF WELL</b> Gas Well Coalbed Methane Well: NO				<b>3. FIELD OR WILDCAT</b> NATURAL BUTTES		
<b>6. NAME OF OPERATOR</b> KERR-MCGEE OIL & GAS ONSHORE, L.P.				<b>5. UNIT or COMMUNITIZATION AGREEMENT NAME</b> NATURAL BUTTES		
<b>8. ADDRESS OF OPERATOR</b> P.O. Box 173779, Denver, CO, 80217				<b>7. OPERATOR PHONE</b> 720 929-6587		
<b>10. MINERAL LEASE NUMBER (FEDERAL, INDIAN, OR STATE)</b> UO 1207A		<b>11. MINERAL OWNERSHIP</b> FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input checked="" type="checkbox"/> FEE <input type="checkbox"/>		<b>9. OPERATOR E-MAIL</b> mary.mondragon@anadarko.com		
<b>13. NAME OF SURFACE OWNER (if box 12 = 'fee')</b>				<b>12. SURFACE OWNERSHIP</b> FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input checked="" type="checkbox"/> FEE <input type="checkbox"/>		
<b>15. ADDRESS OF SURFACE OWNER (if box 12 = 'fee')</b>				<b>14. SURFACE OWNER PHONE (if box 12 = 'fee')</b>		
<b>17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN')</b>		<b>18. INTEND TO COMMINGLE PRODUCTION FROM MULTIPLE FORMATIONS</b> YES <input checked="" type="checkbox"/> (Submit Commingling Application) NO <input type="checkbox"/>		<b>16. SURFACE OWNER E-MAIL (if box 12 = 'fee')</b>		
<b>20. LOCATION OF WELL</b>		<b>FOOTAGES</b>	<b>QTR-QTR</b>	<b>SECTION</b>	<b>TOWNSHIP</b>	<b>RANGE</b>
<b>LOCATION AT SURFACE</b>		2552 FSL 1420 FWL	NESW	31	9.0 S	22.0 E
<b>Top of Uppermost Producing Zone</b>		2611 FSL 1837 FEL	NWSE	31	9.0 S	22.0 E
<b>At Total Depth</b>		2611 FSL 1837 FEL	NWSE	31	9.0 S	22.0 E
<b>21. COUNTY</b> UINTAH		<b>22. DISTANCE TO NEAREST LEASE LINE (Feet)</b> 1837		<b>23. NUMBER OF ACRES IN DRILLING UNIT</b> 203		
		<b>25. DISTANCE TO NEAREST WELL IN SAME POOL (Applied For Drilling or Completed)</b> 1500		<b>26. PROPOSED DEPTH</b> MD: 9556 TVD: 9170		
<b>27. ELEVATION - GROUND LEVEL</b> 4841		<b>28. BOND NUMBER</b>		<b>29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE</b> Permit #43-8496		


**ATTACHMENTS****VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES**

<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER	<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN
<input type="checkbox"/> AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE)	<input type="checkbox"/> FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER
<input checked="" type="checkbox"/> DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED)	<input checked="" type="checkbox"/> TOPOGRAPHICAL MAP
<b>NAME</b> Danielle Piernot	<b>TITLE</b> Regulatory Analyst
<b>SIGNATURE</b>	<b>PHONE</b> 720 929-6156
	<b>EMAIL</b> danielle.piernot@anadarko.com
<b>API NUMBER ASSIGNED</b> 43047504170000	<b>APPROVAL</b>  Permit Manager

Proposed Hole, Casing, and Cement						
String	Hole Size	Casing Size	Top (MD)	Bottom (MD)		
Prod	7.875	4.5	0	9556		
Pipe	Grade	Length	Weight			
	Grade I-80 LT&C	9556	11.6			

Proposed Hole, Casing, and Cement						
String	Hole Size	Casing Size	Top (MD)	Bottom (MD)		
Surf	12.25	9.625	0	2135		
Pipe	Grade	Length	Weight			
	Grade J-55 LT&C	2135	36.0			

'APIWellNo:43047504170000'



**LEGEND:**

- └─ = 90° SYMBOL
- = PROPOSED WELL HEAD.
- ▲ = SECTION CORNERS LOCATED.
- △ = SECTION CORNERS RE-ESTABLISHED. (Not Set on Ground)

NAD 83 (TARGET BOTTOM HOLE)	NAD 83 (SURFACE LOCATION)
LATITUDE = 39°59'32.74" (39.992428)	LATITUDE = 39°59'32.19" (39.992275)
LONGITUDE = 109°28'47.40" (109.479833)	LONGITUDE = 109°29'08.14" (109.485594)
NAD 27 (TARGET BOTTOM HOLE)	NAD 27 (SURFACE LOCATION)
LATITUDE = 39°59'32.87" (39.992464)	LATITUDE = 39°59'32.32" (39.992311)
LONGITUDE = 109°28'44.93" (109.479147)	LONGITUDE = 109°29'05.67" (109.484908)

**Kerr-McGee Oil & Gas Onshore LP**


Well location, NBU #922-31J2S, located as shown in the NE 1/4 SW 1/4 of Section 31, T9S, R22E, S.L.B.&M., Uintah County, Utah.

**BASIS OF ELEVATION**

TWO WATER TRIANGULATION STATION LOCATED IN THE NW 1/4 OF SECTION 1, T10S, R21E, S.L.B.&M. TAKEN FROM THE BIG PACK MTN NE QUADRANGLE, UTAH, UTAH COUNTY, 7.5 MINUTE SERIES (TOPOGRAPHICAL MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 5238 FEET.

**BASIS OF BEARINGS**

BASIS OF BEARINGS IS A G.P.S. OBSERVATION.



**CERTIFICATE**

THIS IS TO CERTIFY THAT THE ABOVE PLAN WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

**REGISTERED LAND SURVEYOR**  
**REGISTRATION NO. 161319**  
**STATE OF UTAH**




**UINTAH ENGINEERING & LAND SURVEYING**  
**85 SOUTH 200 EAST - VERNAL, UTAH 84078**  
**(435) 789-1017**

SCALE 1" = 1000'	DATE SURVEYED: 11-19-08	DATE DRAWN: 12-05-08
PARTY L.K. C.K. D.P.	REFERENCES G.L.O. PLAT	
WEATHER COOL	FILE Kerr-McGee Oil & Gas Onshore LP	





Well Name: P\_NBU 922-31J2S  
 Surface Location: UINTAH\_NBU 922-31K PAD  
 NAD 1927 (NADCON CONUS) Universal Transverse Mercator (US Survey Feet)  
 UTAH - UTM (feet), NAD27, Zone 12N  
 Ground Elevation: 4841.0  
 Northing 14526851.04 Easting 2064787.06 Latitude 39.992311°N Longitude 109.484908°W



#### SECTION DETAILS

Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	DLeg	TFace	VSec
1	0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.0
2	2150.0	0.00	0.00	2150.0	0.0	0.0	0.00	0.00	0.0
3	3150.0	30.00	88.02	3104.9	8.8	255.7	3.00	88.02	255.9
4	5356.3	30.00	88.02	5015.6	46.9	1358.2	0.00	0.00	1359.0
5	6356.3	0.00	0.00	5970.6	55.8	1613.9	3.00	180.00	1614.9
6	9555.7	0.00	0.00	9170.0	55.8	1613.9	0.00	0.00	1614.9



Azimuths to True North  
 Magnetic North: 11.33°

Magnetic Field  
 Strength: 52570.4snT  
 Dip Angle: 65.93°  
 Date: 4/15/2009  
 Model: IGRF200510

# **ROCKIES - PLANNING**

**UTAH - UTM (feet), NAD27, Zone 12N**

**UINTAH\_NBU 922-31K PAD**

**P\_NBU 922-31J2S**

**P\_NBU 922-31J2S**

**Plan: Plan #1 04-15-09 ZJRA6**

## **Standard Planning Report - Geographic**

**15 April, 2009**

# APC

## Planning Report - Geographic

<b>Database:</b>	apc_edmp	<b>Local Co-ordinate Reference:</b>	Well P_NBU 922-31J2S
<b>Company:</b>	ROCKIES - PLANNING	<b>TVD Reference:</b>	WELL @ 4841.0ft (Original Well Elev)
<b>Project:</b>	UTAH - UTM (feet), NAD27, Zone 12N	<b>MD Reference:</b>	WELL @ 4841.0ft (Original Well Elev)
<b>Site:</b>	UINTAH_NBU 922-31K PAD	<b>North Reference:</b>	True
<b>Well:</b>	P_NBU 922-31J2S	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	P_NBU 922-31J2S		
<b>Design:</b>	Plan #1 04-15-09 ZJRA6		

<b>Project</b>	UTAH - UTM (feet), NAD27, Zone 12N		
<b>Map System:</b>	Universal Transverse Mercator (US Survey Fee	<b>System Datum:</b>	Mean Sea Level
<b>Geo Datum:</b>	NAD 1927 (NADCON CONUS)		
<b>Map Zone:</b>	Zone 12N (114 W to 108 W)		

Site		UINTAH_NBU 922-31K PAD			
Site Position:		Northing:	14,526,925.45ft	Latitude:	39.992514°N
From:	Lat/Long	Easting:	2,064,816.83ft	Longitude:	109.484797°W
Position Uncertainty:		Slot Radius:	"	Grid Convergence:	0.97 °

Well	P_NBU 922-31J2S					
Well Position	+N-S	0.0 ft	Northing:	14,526,851.04 ft	Latitude:	39.992311°N
	+E-W	0.0 ft	Easting:	2,064,787.06 ft	Longitude:	109.484908°W
Position Uncertainty		0.0 ft	Wellhead Elevation:	ft	Ground Level:	4,841.0 ft

<b>Wellbore</b>	P_NBU 922-31J2S				
<b>Magnetics</b>	<b>Model Name</b>	<b>Sample Date</b>	<b>Declination (°)</b>	<b>Dip Angle (°)</b>	<b>Field Strength (nT)</b>
	IGRF200510	4/15/2009	11.33	65.93	52,570

<b>Design</b>	Plan #1 04-15-09 ZJRA6			
<b>Audit Notes:</b>				
<b>Version:</b>	<b>Phase:</b>	PLAN	<b>Tie On Depth:</b>	0.0
<b>Vertical Section:</b>	<b>Depth From (TVD) (ft)</b>	<b>+N/-S (ft)</b>	<b>+E/-W (ft)</b>	<b>Direction (°)</b>
	9,170.0	0.0	0.0	88.02

<b>Plan Sections</b>										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	TFO (°)	Target
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00	0.00	
2,150.0	0.00	0.00	2,150.0	0.0	0.0	0.00	0.00	0.00	0.00	
3,150.0	30.00	88.02	3,104.9	8.8	255.7	3.00	3.00	0.00	88.02	
5,356.3	30.00	88.02	5,015.6	46.9	1,358.2	0.00	0.00	0.00	0.00	
6,356.3	0.00	0.00	5,970.6	55.8	1,613.9	3.00	-3.00	0.00	180.00	
9,555.7	0.00	0.00	9,170.0	55.8	1,613.9	0.00	0.00	0.00	0.00	PBHL_NBU 922-31

# APC

## Planning Report - Geographic

<b>Database:</b>	apc_edmp	<b>Local Co-ordinate Reference:</b>	Well P_NBU 922-31J2S
<b>Company:</b>	ROCKIES - PLANNING	<b>TVD Reference:</b>	WELL @ 4841.0ft (Original Well Elev)
<b>Project:</b>	UTAH - UTM (feet), NAD27, Zone 12N	<b>MD Reference:</b>	WELL @ 4841.0ft (Original Well Elev)
<b>Site:</b>	UINTAH_NBU 922-31K PAD	<b>North Reference:</b>	True
<b>Well:</b>	P_NBU 922-31J2S	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	P_NBU 922-31J2S		
<b>Design:</b>	Plan #1 04-15-09 ZJRA6		

Planned Survey										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (ft)	Map Easting (ft)	Latitude	Longitude	
0.0	0.00	0.00	0.0	0.0	0.0	14,526,851.04	2,064,787.06	39.992311°N	109.484908°W	
1,135.0	0.00	0.00	1,135.0	0.0	0.0	14,526,851.04	2,064,787.06	39.992311°N	109.484908°W	
Green River										
2,000.0	0.00	0.00	2,000.0	0.0	0.0	14,526,851.04	2,064,787.06	39.992311°N	109.484908°W	
Surface Casing										
2,150.0	0.00	0.00	2,150.0	0.0	0.0	14,526,851.04	2,064,787.06	39.992311°N	109.484908°W	
3,150.0	30.00	88.02	3,104.9	8.8	255.7	14,526,864.22	2,065,042.59	39.992335°N	109.483995°W	
4,631.6	30.00	88.02	4,388.0	34.4	996.1	14,526,902.39	2,065,782.39	39.992405°N	109.481353°W	
Wasatch										
5,356.3	30.00	88.02	5,015.6	46.9	1,358.2	14,526,921.06	2,066,144.27	39.992440°N	109.480060°W	
6,356.3	0.00	0.00	5,970.6	55.8	1,613.9	14,526,934.24	2,066,399.81	39.992464°N	109.479147°W	
8,946.7	0.00	0.00	8,561.0	55.8	1,613.9	14,526,934.24	2,066,399.81	39.992464°N	109.479147°W	
Mesaverde										
9,555.7	0.00	0.00	9,170.0	55.8	1,613.9	14,526,934.24	2,066,399.81	39.992464°N	109.479147°W	

Targets										
Target Name	- hit/miss target	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (ft)	Easting (ft)	Latitude	Longitude
PBHL_NBU 922-31J2	- plan hits target center	0.00	0.00	9,170.0	55.8	1,613.9	14,526,934.24	2,066,399.81	39.992464°N	109.479147°W
	- Point									

Casing Points					
Measured Depth (ft)	Vertical Depth (ft)	Name	Casing Diameter (")	Hole Diameter (")	
2,000.0	2,000.0	Surface Casing	9-5/8	12-1/4	

Formations						
Measured Depth (ft)	Vertical Depth (ft)	Name	Lithology	Dip (°)	Dip Direction (°)	
4,631.6	4,388.0	Wasatch		0.00		
8,946.7	8,561.0	Mesaverde		0.00		
1,135.0	1,135.0	Green River		0.00		

**NBU 922-31J2S**

Pad: NBU 922-31K

Surface: 2,552' FSL, 1,420' FWL (NE/4SW/4)

BHL: 2,611' FSL 1,837' FEL (NW/4SE/4)

Sec. 31 T9S R22E

Uintah, Utah

Mineral Lease: UO1207A

**ONSHORE ORDER NO. 1**

***DRILLING PROGRAM***

1. – 2. **Estimated Tops of Important Geologic Markers:**  
**Estimated Depths of Anticipated Water, Oil, Gas, or Mineral Formations:**

<u>Formation</u>	<u>Depth</u>	<u>Resource</u>
Uinta	0 – Surface	
Green River	1,129'	
Birds Nest	1,450'	Water
Mahogany	1,934'	Water
Wasatch	4,374'	Gas
Mesaverde	6,955'	Gas
MVU2	7,932'	Gas
MVL1	8,478'	Gas
TVD	9,170'	
TD	9,556'	

3. **Pressure Control Equipment** (Schematic Attached)

*Please refer to the attached Drilling Program.*

4. **Proposed Casing & Cementing Program:**

*Please refer to the attached Drilling Program.*

5. **Drilling Fluids Program:**

*Please refer to the attached Drilling Program.*

6. **Evaluation Program:**

*Please refer to the attached Drilling Program.*

7. **Abnormal Conditions:**

Maximum anticipated bottomhole pressure calculated at 9,556' TD, approximately equals 5,427 psi (calculated at 0.59 psi/foot).

Maximum anticipated surface pressure equals approximately 3,410 psi (bottomhole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot).

**8. Anticipated Starting Dates:**

*Drilling is planned to commence immediately upon approval of this application.*

**9. Variances:**

*Please refer to the attached Drilling Program.*

*Onshore Order #2 – Air Drilling Variance*

*Kerr-McGee Oil & Gas Onshore LP (KMG) respectfully requests a variance to several requirements associated with air drilling outlined in Onshore Order 2*

- *Blowout Prevention Equipment (BOPE) requirements;*
- *Mud program requirements; and*
- *Special drilling operation (surface equipment placement) requirements associated with air drilling.*

*This Standard Operating Practices addendum provides supporting information as to why KMG current air drilling practices for constructing the surface casing hole should be granted a variance to Onshore Order 2 air drilling requirements.*

*The reader should note that the air rig is used only to construct a stable surface casing hole through a historically difficult lost circulation zone. A conventional rotary rig follows the air rig, and is used to drill and construct the majority of the wellbore.*

*More notable, KMG has used the air rig layout and procedures outlined below to drill the surface casing hole in approximately 675 wells without incident of blow out or loss of life.*

***Background***

*In a typical well, KMG utilizes an air rig for drilling the surface casing hole, an interval from the surface to surface casing depths, which varies in depth from 1,700 to 2,800 feet. The air rig drilling operation does not drill through productive or over pressured formations in KMG field, but does penetrate the Uinta and Green River Formations. The purpose of the air drilling operation is to overcome the severe loss circulation zone in the Green River known as the Bird's Nest while creating a stable hole for the surface casing. The surface casing hole is generally drilled to approximately 500 feet below the Bird's Nest.*

*Before the surface air rig is mobilized, a rathole rig is utilized to set and cement conductor pipe through a competent surface formation. Generally, the conductor is set at 40 feet. In some cases, conductor may be set deeper in areas that the surface formation is not found competent. This rig also drills the rat and mouse holes in preparation for the surface casing and production string drilling operations.*

*The air rig is then mobilized to drill the surface casing hole by drilling a 12-1/4 inch hole to just above the Bird's Nest interval with an air hammer. The hammer is then tripped and replaced with a 12-1/4 inch tri-cone bit. The tri-cone bit is used to drill to the surface casing point, approximately 500 feet below the loss circulation zone (Bird's Nest). The 9-5/8 inch surface casing is then run and cemented in place, thereby isolating the lost circulation zone.*

*KMG fully appreciates Onshore Order 2 well control and safety requirements associated with a typical air drilling operations. However, the requirements of Onshore Order 2 are excessive with respect to the air rig layout and drilling operation procedures that are currently in practice to drill and control the surface casing hole in KMG Fields.*

***Variance for BOPE Requirements***

*The air rig operation utilizes a properly lubricated and maintained air bowl diverter system which diverts the drilling returns to a six-inch blooie line. The air bowl is the only piece of BOPE equipment which is installed during drilling operations and is sufficient to contain the air returns associated with this drilling operation. As was discussed earlier, the drilling of the surface hole does not encounter any over pressured or productive zones, and as a result standard BOPE equipment should not be required. In addition, standard drilling practices do not support the use of BOPE on 40 feet of conductor pipe.*

***Variance for Mud Material Requirements***

*Onshore Order 2 also states that sufficient quantities of mud materials shall be maintained or readily accessible for the purpose of assuring adequate well control. Once again, the surface hole drilling operations does not encounter over pressured or productive intervals, and as a result there is not a need to control pressure in the surface hole with a mud system. Instead of mud, the air rigs utilize water from the reserve pit for well control, if necessary. A skid pump which is located near the reserve pit (see attachment) will supply the water to the well bore.*

***Variance for Special Drilling Operation (surface equipment placement) Requirements***

*Onshore Order 2 requires specific safety distances or setbacks for the placement of associated standard air drilling equipment, wellbore, and reserve pits. The air rigs used to drill the surface holes are not typical of an air rig used to drill a producing hole in other parts of the US. These are smaller in nature and designed to fit a KMG location. The typical air rig layout for drilling surface hole in the field is attached.*

*Typically the blooie line discharge point is required to be 100 feet from the well bore. In the case of a KMG well, the reserve pit is only 45 feet from the rig and is used for the drill cuttings. The blooie line, which transports the drill cuttings from the well to the reserve pit, subsequently discharges only 45 feet from the well bore.*

*Typically the air rig compressors are required to be located in the opposite direction from the blooie line and a minimum of 100 feet from the well bore. At the KMG locations, the air rig compressors are approximately 40 feet from the well bore and approximately 60 feet from the blooie line discharge due to the unique air rig design. The air compressors (see attachment) are located on the rig (1250 cfm) and on a standby trailer (1170 cfm). A booster sits between the two compressors and boosts the output from 350 psi to 2000 psi. The design does put the booster and standby compressor opposite from the blooie line.*

*Lastly, Onshore Order 2 addresses the need for an automatic igniter or continuous pilot light on the blooie line. The air rig does not utilize an igniter as the surface hole drilling operation does not encounter productive formations.*

***Conclusion***


*The air rig operating procedures and the attached air rig layout have effectively maintained well control while drilling the surface holes in KMG Fields. KMG respectfully requests a variance from Onshore Order 2 with respect to air drilling well control requirements as discussed above.*

**10. Other Information:**

*Please refer to the attached Drilling Program.*



COMPANY NAME	KERR-McGEE OIL & GAS ONSHORE LP				DATE	May 11, 2009		
WELL NAME	<b>NBU 922-31J2S</b>				TD	9,170'	TVD	9,556' MD
FIELD	Natural Buttes		COUNTY	Uintah	STATE	Utah	ELEVATION	4,841' GL KB 4,856'
SURFACE LOCATION	NE/4 SW/4	2,552' FSL	1,420' FWL	Sec 31	T 9S	R 22E		
	Latitude:	39.992311	Longitude:	-109.484908		NAD 27		
BTM HOLE LOCATION	NW/4 SE/4	2,611' FSL	1,837' FEL	Sec 31	T 9S	R 22E		
	Latitude:	39.992464	Longitude:	-109.479147		NAD 27		
OBJECTIVE ZONE(S)	Wasatch/Mesaverde							
ADDITIONAL INFO	Regulatory Agencies: SITLA (Minerals), UDOGM (Surface), Tri-County Health Dept.							





# KERR-McGEE OIL & GAS ONSHORE LP

## DRILLING PROGRAM

### CASING PROGRAM

	SIZE	INTERVAL	WT.	GR.	CPLG.	DESIGN FACTORS		
						BURST	COLLAPSE	TENSION
CONDUCTOR	14"	0-40'						
						3520	2020	453000
SURFACE	9-5/8"	0 to 2,135	36.00	J-55	LTC	0.96	2.02	7.50
						7,780	6,350	201,000
PRODUCTION	4-1/2"	0 to 9,556	11.60	I-80	LTC	2.21	1.15	2.08

1) Max Anticipated Surf. Press.(MASP) (Surface Casing) = (Pore Pressure at next csg point-(0.22 psi/ft-partial evac gradient x TVD of next csg point))

2) MASP (Prod Casing) = Pore Pressure at TD - (0.22 psi/ft-partial evac gradient x TD)

(Burst Assumptions: TD = 11.6 ppg)

0.22 psi/ft = gradient for partially evac wellbore

(Collapse Assumption: Fully Evacuated Casing, Max MW)

(Tension Assumptions: Air Weight of Casing\*Buoy.Fact. of water)

**MASP 3,410 psi**

3) Maximum Anticipated Bottom Hole Pressure (MABHP) = Pore Pressure at TD

(Burst Assumptions: TD = 11.6 ppg)

0.59 psi/ft = bottomhole gradient

(Collapse Assumption: Fully Evacuated Casing, Max MW)

(Tension Assumptions: Air Weight of Casing\*Buoy.Fact. of water)

**MABHP 5,427 psi**

### CEMENT PROGRAM

		FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT	YIELD
SURFACE	LEAD	500	Premium cmt + 2% CaCl	215	60%	15.60	1.18
Option 1			+ 0.25 pps flocele				
	TOP OUT CMT (1)	200	20 gals sodium silicate + Premium cmt	50		15.60	1.18
			+ 2% CaCl + 0.25 pps flocele				
	TOP OUT CMT (2)	as required	Premium cmt + 2% CaCl	as req.		15.60	1.18
SURFACE		<b>NOTE: If well will circulate water to surface, option 2 will be utilized</b>					
Option 2	LEAD	1500	65/35 Poz + 6% Gel + 10 pps gilsonite	360	35%	12.60	1.81
			+ .25 pps Flocele + 3% salt BWOW				
	TAIL	500	Premium cmt + 2% CaCl	180	35%	15.60	1.18
			+ 0.25 pps flocele				
	TOP OUT CMT	as required	Premium cmt + 2% CaCl	as req.		15.60	1.18
PRODUCTION	LEAD	3,866'	Premium Lite II + 3% KCl + 0.25 pps celloflake + 5 pps gilsonite + 10% gel	370	40%	11.00	3.38
			+ 0.5% extender				
	TAIL	5,690'	50/50 Poz/G + 10% salt + 2% gel	1390	40%	14.30	1.31
			+ .1% R-3				

\*Substitute caliper hole volume plus 0% excess for LEAD if accurate caliper is obtained

\*Substitute caliper hole volume plus 10% excess for TAIL if accurate caliper is obtained

### FLOAT EQUIPMENT & CENTRALIZERS

SURFACE	Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe
PRODUCTION	Float shoe, 1 jt, float collar. No centralizers will be used.

### ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.

BOPE: 11" 5M with one annular and 2 rams. The BOPE will be installed before the production hole is drilled and tested to 5,000 psi (annular to 2,500 psi) prior to drilling out the surface casing shoe. Record on chart recorder and tour sheet. Function test rams on each trip. Maintain safety valve and inside BOP on rig floor at all times. Most rigs have top drives; however, if used, the Kelly is to be equipped with upper and lower kelly valves.

Surveys will be taken at 1,000' minimum intervals.

Most rigs have PVT System for mud monitoring. If no PVT is available, visual monitoring will be utilized.

DRILLING ENGINEER:

John Huycke / Grant Schluender


DATE:

DRILLING SUPERINTENDENT:


John Merkel / Lovel Young

DATE:

EXHIBIT A  
NBU 922-31J2S



SCHEMATIC DIAGRAM OF 5,000 PSI BOP STACK



# Kerr-McGee Oil & Gas Onshore LP

FIGURE #2

## TYPICAL CROSS SECTIONS FOR


NBU #922-31F3S, #922-31F2S & #922-31J2S

SECTION 31, T9S, R22E, S.L.B.&M.

NE 1/4 SW 1/4


1" = 20'  
X-Section  
Scale  
1" = 100'

DATE: 12-05-08  
DRAWN BY: D.P.



### NOTE:

Topsoil should not be Stripped Below Finished Grade on Substructure Area.



### APPROXIMATE ACREAGES

EXISTING WELL SITE DISTURBANCE =  $\pm 1.505$  ACRES  
NEW CONSTRUCTION WELL SITE DISTURBANCE =  $\pm 2.205$  ACRES  
TOTAL =  $\pm 3.710$  ACRES

\* NOTE:  
FILL QUANTITY INCLUDES  
5% FOR COMPACTION

### APPROXIMATE YARDAGES


CUT  
(6") Topsoil Stripping = 1,170 Cu. Yds.  
(New Construction Only)  
Remaining Location = 6,450 Cu. Yds.  
TOTAL CUT = 7,620 CU.YDS.  
FILL = 4,430 CU.YDS.

EXCESS MATERIAL = 3,190 Cu. Yds.  
Topsoil & Pit Backfill = 3,070 Cu. Yds.  
(1/2 Pit Vol.)  
EXCESS UNBALANCE = 120 Cu. Yds.  
(After Interim Rehabilitation)

UINTAH ENGINEERING & LAND SURVEYING  
85 So. 200 East \* Vernal, Utah 84078 \* (435) 789-1017







**LEGEND:**

**● PROPOSED LOCATION**

**Kerr-McGee Oil & Gas Onshore LP**

**NBU #922-31F3S, #922-31F2S & #922-31J2S**

**SECTION 31, T9S, R22E, S.L.B.&M.**

**NE 1/4 SW 1/4**



**Uintah Engineering & Land Surveying**  
 85 South 200 East Vernal, Utah 84078  
 (435) 789-1017 \* FAX (435) 789-1813




**TOPOGRAPHIC**  
**MAP**

**12 05 08**  
 MONTH DAY YEAR

**SCALE: 1:100,000** **DRAWN BY: D.P.** **REVISED: 00-00-00**







**LEGEND:**

— EXISTING ROAD



**Kerr-McGee Oil & Gas Onshore LP**

**NBU #922-31F3S, #922-31F2S & #922-31J2S**

**SECTION 31, T9S, R22E, S.L.B.&M.**

**NE 1/4 SW 1/4**



**Utah Engineering & Land Surveying**  
85 South 200 East Vernal, Utah 84078  
(435) 789-1017 \* FAX (435) 789-1813

**TOPOGRAPHIC**  
**MAP**

**12 05 08**  
MONTH DAY YEAR

SCALE: 1" = 2000' DRAWN BY: D.P. REVISED: 00-00-00







**C**  
**TOPO**

SCALE: 1" = 2000'	DRAWN BY: D.P.	REVISED: 00-00-00
-------------------	----------------	-------------------



**Kerr-McGee Oil & Gas Onshore LP**  
**NBU #922-31F3S, #922-31F2S, & #922-31J2S**  
**LOCATED IN UINTAH COUNTY, UTAH**  
**SECTION 31, T9S, R22E, S.L.B.&M.**




PHOTO: VIEW FROM CORNER #5 TO LOCATION STAKES

CAMERA ANGLE: NORTHWESTERLY



PHOTO: VIEW OF EXISTING ACCESS

CAMERA ANGLE: SOUTHEASTERLY



- Since 1964 -

**UELS** Uintah Engineering & Land Surveying  
85 South 200 East Vernal, Utah 84078  
(435) 789-1017 \* FAX (435) 789-1813

**LOCATION PHOTOS**

**12 05 08**  
MONTH DAY YEAR

**PHOTO**

TAKEN BY: D.K.

DRAWN BY: D.P.

REVISED: 00-00-00

**Kerr-McGee Oil & Gas Onshore LP**  
**NBU #922-31F3S, #922-31F2S & #922-31J2S**  
**SECTION 31, T9S, R22E, S.L.B.&M.**

PROCEED IN A WESTERLY DIRECTION FROM VERNAL, UTAH ALONG U.S. HIGHWAY 40 APPROXIMATELY 14.0 MILES TO THE JUNCTION OF STATE HIGHWAY 88; EXIT LEFT AND PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 17.0 MILES TO OURAY, UTAH; PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 6.9 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHEAST; TURN LEFT AND PROCEED IN A SOUTHEASTERLY, THEN EASTERLY DIRECTION APPROXIMATELY 5.0 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE NORTHWEST; TURN LEFT AND PROCEED IN A NORTHWESTERLY DIRECTION APPROXIMATELY 0.3 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE NORTHEAST; TURN RIGHT AND PROCEED IN A NORTHEASTERLY DIRECTION APPROXIMATELY 3.8 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE NORTHEAST; PROCEED IN A NORTHEASTERLY DIRECTION APPROXIMATELY 0.9 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHWEST; TURN RIGHT AND PROCEED IN A SOUTHWESTERLY, THEN SOUTHEASTERLY DIRECTION APPROXIMATELY 2.9 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHEAST; TURN LEFT AND PROCEED IN A SOUTHEASTERLY DIRECTION APPROXIMATELY 400' TO THE PROPOSED LOCATION.

TOTAL DISTANCE FROM VERNAL, UTAH TO THE PROPOSED WELL LOCATION IS APPROXIMATELY 50.8 MILES.

***Kerr-McGee Oil & Gas Onshore LP***

**NBU 922-31F2S**

Surface: 2,626' FSL, 1,451' FWL (NE/4SW/4)  
BHL: 1,737' FNL 1,258' FWL (SE/4NW/4)  
Mineral Lease: ML23607

**NBU 922-31F3S**

Surface: 2,607' FSL, 1,443' FWL (NE/4SW/4)  
BHL: 2,215' FNL 1,258' FWL (SE/4NW/4)  
Mineral Lease: ML23607

**NBU 922-31J2S**

Surface: 2,552' FSL, 1,420' FWL (NE/4SW/4)  
BHL: 2,611' FSL 1,837' FEL (NW/4SE/4)  
Mineral Lease: UO1207A

Section 31 Township 9 South Range 22 East  
Pad: NBU 922-31K  
Uintah, Utah  
Surface: State

**ONSHORE ORDER NO. 1**

***MULTI-POINT SURFACE USE & OPERATIONS PLAN***

**Directional Drilling:**

In accordance with Oil & Gas Conservation Rule R649-3-11 pertaining to Directional Drilling, this well will be directionally drilled in order to access portions of our lease which are otherwise inaccessible due to topography.

**1. Existing Roads:**

Refer to Topo Map A for directions to the location.

Refer to Topo Maps A and B for location of access roads within a 2-mile radius.

Refer to Topo Maps A and B for location of access roads within a 2-mile radius.

All existing roads will be maintained and kept in good repair during all drilling and completion operations associated with this well.

**Kerr-McGee Oil & Gas Onshore LP**  
NBU 922-31F2S/ 31F3S/ 31J2S

Page 2  
Surface Use and Operations Plan

**2. Planned Access Roads:**

Approximately  $\pm 0.0$  mi. ( $\pm 0'$ ) of new access road is proposed. Please refer to the attached Topo Map B.

The upgraded and new portions of the access road will be crowned and ditched with a running surface of 18 feet and a maximum disturbed width of 30 feet. Appropriate water control will be installed to control erosion.

*Existence of pipelines; maximum grade; turnouts; major cut and fills, culverts, or bridges; gates, cattle guards, fence cuts, or modifications to existing facilities were determined at the on-site.*

The access road was centerline flagged during time of staking.

Surfacing material may be necessary, depending upon weather conditions.

Surface disturbance and vehicular traffic will be limited to the approved location and approved access route. Any additional area needed will be approved in advance.

**3. Location of Existing Wells Within a 1-Mile Radius:**

Please refer to Topo Map C.

**4. Location of Existing & Proposed Facilities:**

*The following guidelines will apply if the well is productive.*

All production facilities will be located on the disturbed portion of the well pad and at a minimum of 25 feet from the toe of the back slope or the top of the fill slope.

A dike will be constructed completely around those production facilities which contain fluids (i.e., production tanks, produced water tanks, and/or heater/treater). These dikes will be constructed of compacted subsoil, be impervious, hold 100% of the capacity of the largest tank, and be independent of the back cut.

All permanent (on-site six months or longer) above the ground structures constructed or installed, including pumping units, will be painted a flat, non-reflective, earthtone color to match one of the standard environmental colors, as determined by the five state Rocky Mountain Inter-Agency Committee.

All facilities will be painted within six months of installation. Facilities required to comply with the Occupational Safety and Health Act (OSHA) will be excluded. The required color is Shadow Gray, a non-reflective earthtone.

Any necessary pits will be properly fenced to protect livestock and prevent wildlife entry.

**Kerr-McGee Oil & Gas Onshore LP**  
NBU 922-31F2S/ 31F3S/ 31J2S

Page 3  
Surface Use and Operations Plan

**5. Location and Type of Water Supply:**

Water for drilling purposes will be obtained from Dalbo Inc.'s underground well located in Ouray, Utah, Sec. 32 T4S R3E, Water User Claim #43-8496, Application #53617.

Water will be hauled to location over the roads marked on Maps A and B.

No water well is to be drilled on this lease.

**6. Source of Construction Materials:**

Surface and subsoil materials in the immediate area will be utilized.

Any gravel will be obtained from a commercial source.

**7. Methods of Handling Waste Materials:**

Drill cuttings will be contained and buried in the reserve pit.

Drilling fluids, including salts and chemicals, will be contained in the reserve pit. Upon termination of drilling and completion operations, the liquid contents of the reserve pit will be removed and disposed of at an approved waste disposal facility within 120 days after drilling is terminated.

The reserve pit will be constructed on the location and will not be located within natural drainage, where a flood hazard exists or surface runoff will destroy or damage the pit walls. The reserve pit will be constructed so that it will not leak, break, or allow discharge of liquids.

A plastic reinforced liner and felt will be used; it will be a minimum of 20 mil thick, with sufficient bedding used to cover any rocks. The liner will overlap the pit walls and be covered with dirt and/or rocks to hold it in place. No trash or scrap that could puncture the liner will be disposed of in the pit. Any spills of oil, gas, salt water, or other noxious fluids will be immediately cleaned up and removed to an approved disposal site.

A chemical porta-toilet will be furnished with the drilling rig.

Garbage, trash, and other waste materials will be collected in a portable, self-contained, fully enclosed trash cage during operations. No trash will be burned on location.

All debris and other waste material not contained in the trash cage will be cleaned up and removed from the location immediately after removal of the drilling rig.

Any open pits will be fenced during the operations. The fencing will be maintained until such time as the pits are backfilled.

**Kerr-McGee Oil & Gas Onshore LP**  
NBU 922-31F2S/ 31F3S/ 31J2S

Page 4  
Surface Use and Operations Plan

No chemicals subject to reporting under SARA Title III (hazardous materials) in an amount greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling of this well.

Any produced water from the proposed well will be contained in a water tank and will then be hauled By truck to one of the pre-approved disposal sites: RNI in Sec. 5 T9S R22E, NBU #159 in Sec. 35 T9S R21E, Ace Oilfield in Sec. 2 T6S R20E, MC&MC in Sec. 12 T6S R19E, Pipeline Facility in Sec. 36 T9S R20E, Goat Pasture Evaporation Pond in SW/4 Sec. 16 T10S R22E, Bonanza Evaporation Pond in Sec. 2 T10S R23E.

**8. Ancillary Facilities:**

None are anticipated.

**9. Well Site Layout:** (See Location Layout Diagram)

The attached Location Layout Diagram describes drill pad cross-sections, cuts and fills, and locations of the mud tanks, reserve pit, flare pit, pipe racks, trailer parking, spoil dirt stockpile(s), and surface material stockpile(s).

Please see the attached diagram to describe rig orientation, parking areas, and access roads.

The reserve pit will be lined, and when the reserve pit is closed, the pit liner will be buried below plow depth.

All pits will be fenced according to the following minimum standards:

39 inch net wire will be used with at least one strand of barbed wire on top of the net wire. Barbed wire is not necessary if pipe or some type of reinforcement rod is attached to the top of the entire fence.

The net wire shall be no more than two inches above the ground. The barbed wire shall be three inches over the net wire. Total height of the fence shall be at least 42 inches.

Corner posts shall be cemented and/or braced in such a manner to keep the fence tight at all times.

Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distance between any 2 fence posts shall be no greater than 16 feet.

All wire shall be stretched, by using a stretching device, before it is attached to corner posts.

The reserve pit fencing will be on three sides during drilling operations, and on the fourth side when the rig moves off location. Pits will be fenced and maintained until cleanup.

Location size may change prior to the drilling of the well due to current rig availability. If the proposed location is not large enough to accommodate the drilling rig the location will be re-surveyed and a Form 9 shall be submitted.

**10. Plans for Reclamation of the Surface:**

*Producing Location:*

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, materials, trash, and debris not required for production.

Immediately upon well completion, any hydrocarbons in the pit shall be removed in accordance with 43 CFR 3162.7-1.

A plastic, nylon reinforced liner will be used, it shall be torn and perforated before backfilling of the reserve pit.

Before any dirt work associated with location restoration takes place, the reserve pit shall be as dry as possible. All debris in it will be removed. Other waste and spoil materials will be disposed of immediately upon completion of operations.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximate natural contours. The reserve pit will be reclaimed within 90 days from the date of well completion, weather permitting.

To prevent surface water(s) from standing (ponding) on the reclaimed reserve pit area, final reclamation of the reserve pit will consist of "mounding" the surface three feet above surrounding ground surface to allow the reclaimed pit area to drain effectively.

Upon completion of backfilling, leveling, and recontouring, the stockpiled topsoil will be spread evenly over the reclaimed area(s).

*Dry Hole/Abandoned Location:*

Abandoned well sites, roads, and other disturbed areas will be restored as near as practical to their original condition. Where applicable, these conditions include the re-establishment of irrigation systems, the re-establishment of appropriate soil conditions, and re-establishment of vegetation as specified.

All disturbed surfaces will be recontoured to the approximate natural contours, with reclamation of the well pad and access road to be performed as soon as practical after final abandonment. Reseeding operations will be performed after completion of other reclamation operations.



**Kerr-McGee Oil & Gas Onshore LP**  
NBU 922-31F2S/ 31F3S/ 31J2S

Page 6  
Surface Use and Operations Plan

**11. Surface/Mineral Ownership:**

SITLA  
675 East 500 South, Suite 500  
Salt Lake City, UT 84102

**12. Other Information:**

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, the approved Plan of Operations, and any applicable Notice of Lessees. The Operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished to the field representative to ensure compliance.

The Operator will control noxious weeds along Rights-Of-Way for roads, pipelines, well sites, or other applicable facilities.

A Class III archaeological survey report and paleontological survey report is attached.

**13. Lessee's or Operators' Representative & Certification:**

Kathy Schneebeck Dulnoan  
Staff Regulatory Analyst  
Kerr-McGee Oil & Gas Onshore LP  
PO Box 173779  
Denver, CO 80217-3779  
(720) 929-6226

Tommy Thompson  
General Manager, Drilling  
Kerr-McGee Oil & Gas Onshore LP  
PO Box 173779  
Denver, CO 80217-3779  
(720) 929-6724

Certification: All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved Plan of Operations, and any applicable Notice to Lessees.

The Operator will be fully responsible for the actions of its subcontractors. A complete copy of the approved "Application for Permit to Drill" will be furnished to the field representative(s) to ensure compliance and shall be on location during all construction and drilling operations.

Kerr-McGee Oil & Gas Onshore LP is considered to be the operator of the subject well. Kerr-McGee Oil & Gas Onshore LP agrees to be responsible under terms and conditions of the lease for the operations conducted upon leased lands.

Bond coverage pursuant to 43 CFR 3104 for lease activities is being provided by State Surety Bond 22013542.

I hereby certify that I, or persons under my supervision, have inspected the proposed drill site and access route, that I am familiar with the conditions that currently exist; that I have full knowledge of the State and Federal laws applicable to this operation; that the statements made in this plan are, to the best of my knowledge, true and correct; and the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.

  
Kathy Schneebeck Dulnoan

May 7, 2009  
Date



# Kerr-McGee Oil & Gas Onshore LP

1099 18th Street, Suite 1800  
Denver, CO 80202-1918  
P.O. Box 173779  
Denver, CO 80217-3779  
720-929-6000

May 5, 2009

Mrs. Diana Mason  
Division of Oil, Gas and Mining  
P.O. Box 145801  
Salt Lake City, UT 84114-6100

Re: Directional Drilling R649-3-11  
NBU 922-31J2S  
T9S-R22E  
Section 31: NWSE  
Surface: 2552' FSL, 1420' FWL  
Bottom Hole: 2611' FSL, 1837' FEL  
Uintah County, Utah

Dear Mrs. Mason:

Pursuant to the filing of Kerr-McGee Oil & Gas Onshore LP's (Kerr-McGee) Application for Permit to Drill regarding the above referenced well, we are hereby submitting this letter in accordance with Oil & Gas Conservation Rule R649-3-11 pertaining to the Exception to Location and Siting of Wells.


- Kerr-McGee's NBU 922-31J2S located within the Natural Buttes Unit area.
- Kerr-McGee is permitting this well as a directional well in order to minimize surface disturbance. Locating the well at the surface location and directionally drilling from this location, Kerr-McGee will be able to utilize the existing road and pipelines in the area.
- Furthermore, Kerr-McGee certifies that it is the sole working interest owner within 460 feet of the entire directional well bore.

Therefore, based on the above stated information Kerr-McGee Oil & Gas Onshore LP requests the permit be granted pursuant to R649-3-11.

Sincerely,

KERR-MCGEE OIL & GAS ONSHORE LP

Jason K. Rayburn  
Landman

A handwritten signature in blue ink, appearing to read 'Jason K. Rayburn', is written over the printed name and extends upwards into the company name line.

CLASS I REVIEW OF KERR-MCGEE OIL AND GAS  
ONSHORE LP'S 46 PROPOSED WELL LOCATIONS  
(T9S, R22E, SEC. 29, 30, 31, 32, 33, 34; T10S, R22E, SEC. 4)  
UINTAH COUNTY, UTAH

CLASS I REVIEW OF KERR-MCGEE OIL AND GAS  
ONSHORE LP'S 46 PROPOSED WELL LOCATIONS  
(T9S, R22E, SEC. 29, 30, 31, 32, 33, 34; T10S, R22E, SEC. 4)  
UINTAH COUNTY, UTAH

By:

Nicole Shelnut

Prepared For:

Bureau of Land Management  
Vernal Field Office  
and  
State of Utah  
School & Institutional Trust Lands Administration

Prepared Under Contract With:

Kerr-McGee Oil and Gas Onshore LP  
1368 South 1200 East  
Vernal, Utah 84078

Prepared By:

Montgomery Archaeological Consultants, Inc.  
P.O. Box 219  
Moab, Utah 84532

MOAC Report No. 08-356

February 26, 2009

United States Department of Interior (FLPMA)  
Permit No. 08-UT-60122

Public Lands Policy Coordination Office  
Archaeological Survey Permit No. 117

## INTRODUCTION

A Class I literature review was completed by Montgomery Archaeological Consultants, Inc. (MOAC) in February 2009 of Kerr-McGee Onshore's 46 proposed NBU well locations in Township 9S, Range 22E Sections 29, 30, 31, 32, 33, 34; Township 10S, Range 22E, Section 4. The project area is situated west of the White River in the Bitter Creek Gas Field, Uintah County, Utah. The wells are designated NBU 922-29P Directional Pad, NBU 920-29P, NBU 922-29P2DS, NBU 922-29I3DS, NBU 922-29P3AS, NBU 922-29M Directional Pad, NBU 922-29M2CS, NBU 922-29M3CS, NBU 922-29M4DS, NBU 184 (NBU 922-30N) Directional Pad, NBU 922-30N2S, NBU 280, NBU 922-31K-2TX Directional Pad, NBU 922-31F2S, NBU 922-31F3S, NBU 922-31J2S, (NBU 921-31I) Directional Pad, NBU 922-31J3AS, NBU 922-31O1AS, NBU 922-31I3CS, NBU 922-31I4AS, CIGE 106D (NBU 922-32D) Directional Pad, NBU 922-32F3T, NBU 922-32L1S, NBU 922-32K1S, NBU 922-32F2S, NBU 922-32J3 Directional Pad, NBU 922-32J4CS, NBU 922-32IT, NBU 282 Directional Pad, NBU 922-32P1BS, (NBU 922-33D) Directional Pad, NBU 922-33E2DS, NBU 922-33E3AS, NBU 922-33E3DS, NBU 922-33F3DS, NBU 922-33K2, (NBU 1022-4B) Directional Pad, NBU 922-33P2S, NBU 922-33O4S, NBU 922-33N4S, NBU 922-33P3S, (NBU 922-34E) Directional Pad, NBU 922-34C3BS, NBU 922-34D2CS, NBU 922-34D3BS, and (NBU 922-34O) Directional Pad, NBU 922-34P3CS. This document was implemented at the request of Ms. Raleen White, Kerr-McGee Onshore LP, Denver, Colorado.

The purpose of this Class I review is to identify, classify, and evaluate the previously conducted cultural resource inventories and archaeological sites in the project area in order to comply with Section 106 of 36 CFR 800, the National Historic Preservation Act of 1966 (as amended). Also, the inventory was implemented to attain compliance with a number of federal and state mandates, including the National Environmental Policy Act of 1969, the Archaeological and Historic Conservation Act of 1972, the Archaeological Resources Protection Act of 1979, the American Indian Religious Freedom Act of 1978, and the Utah State Antiquities Act of 1973 (amended 1990).

The project area in which Kerr-McGee Onshore's 46 proposed NBU well locations occur was previously inventoried by MOAC in 2007 for the Class III inventory of Township 9 South, Range 22 East (Montgomery and Dunn 2008) and the Class III inventory of Township 10 South, Range 22 East (Montgomery 2008). A file search was completed by consulting MOAC's Class I existing data review of 459 square miles (293,805 acres) covering the Greater NBU study area between Bonanza and Ouray in Uintah County, northeastern Utah (Patterson et al. 2008). Kerr-McGee Oil & Gas Onshore LP proposes to explore and develop oil and natural gas resources throughout the area. Record searches were performed for this Class I project by Marty Thomas at the Utah State Historic Preservation Office (SHPO) on various dates between June 14, 2006 and January 27, 2007. The results of this Class I data review and Class III inventory indicated that no previously recorded sites occur in the current project area.

## DESCRIPTION OF THE PROJECT AREA

The project area is situated west of the White River on both sides of Sand Wash in the Uinta Basin. The legal description is Township 9S, Range 22E, Sections 29, 30, 31, 32, 33, 34; Township 10S, Range 22E, Sections 3 and 4 (Figure 1, Table 1). Land status is public land administered by the Bureau of Land Management (BLM) Vernal Field Office and State of Utah School & Institutional Trust Lands Administration (SITLA).






Figure 1. Kerr-McGee Oil and Gas Onshore LP's Proposed NBU Well Locations in Uintah County, Utah.



Table 1. Kerr-McGee Onshore's 46 NBU Well Locations.

Well Designation	Legal Description	Access/Pipeline Corridor	Cultural Resources
NBU 922-29P Directional Pad NBU 922-29P NBU 922-29P2DS, NBU 922-29I3DS, NBU 922-29P3AS	SE/SE Sec. 29, T9S, R22E	Access: 368 Pipeline: 577	None
NBU 922-29M Directional Pad NBU 922-29M2CS, NBU 922-29M3CS, NBU 922-29M4DS	SW/SW Sec. 29, T9S, R22E	Pipeline: 2296	None
NBU 922-30N Directional Pad NBU 922-30N2S	SE/SW Sec. 30, T9S, R22E	None	None
NBU 280, NBU 922-31K-2TX Directional Pad NBU 922-31F2S, NBU 922-31F3S, NBU 922-31J2S	NE/SW Sec. 31, T9S, R22E	Access: 690 Pipeline: 277	None
(NBU 921-31I) Directional Pad NBU 922-31J3AS, NBU 922-31O1AS, NBU 922-31I3CS, NBU 922-31I4AS	NE/SE Sec. 31, T9S, R22E	Access: 550 ft Pipeline: 815 ft	None
CIGE 106D (NBU 922-32D) Directional Pad NBU 922-32F3T, NBU 922-32L1S, NBU 922-32K1S, NBU 922-32F2S	SE/NW Sec. 32, T9S, R22E	None	None
NBU 922-32J3 Directional Pad NBU 922-32J4CS	NW/SE Sec. 32, T9S, R22E	None	None
NBU 922-32IT, NBU 282 Directional Pad NBU 922-32P1BS	NE/SE Sec.32, T9S, R22E	None	None
(NBU 922-33D) Directional Pad NBU 922-33E2DS, NBU 922-33E3AS, NBU 922-33E3DS, NBU 922-33F3DS	CT/NW Sec. 33, T9S, R22E	Pipeline: 2009 ft	None
NBU 922-33K2	NE/SW Sec. 33, T9S, R22E	Access: 690 Pipeline: 277	None
(NBU 922-34E) Directional Pad NBU 922-34C3BS, NBU 922-34D2CS, NBU 922-34D3BS	SW/NW Sec. 34, T9S, R22E	Access: 537 ft Pipeline: 1356 ft	None
(NBU 922-34O) Directional Pad NBU 922-34P3CS	SW/SE Sec. 34, T9S, R22E	Access: 263 ft Pipeline: 1120 ft	None



Well Designation	Legal Description	Access/Pipeline Corridor	Cultural Resources
(NBU 1022-4B) Directional Pad NBU 922-33P2S, NBU 922-33O4S, NBU 922-33N4S, NBU 922-33P3S	NW/NE Sec. 4, 10S, R22E	Access: 67 ft Pipeline: 196 ft	None

The study area lies within the Uinta Basin physiographic unit, a distinctly bowl-shaped geologic structure (Stokes 1986:231). The Uinta Basin ecosystem is within the Green River drainage, considered to be the northernmost extension of the Colorado Plateau. The geology is comprised of Tertiary age deposits, which include Paleocene age deposits and Eocene age fluvial and lacustrine sedimentary rocks. The Uinta Formation, which is predominate in the project area, occurs as eroded outcrops (formed by fluvial deposited, stream laid interbedded sandstone and mudstone), and is known for its prolific paleontological localities. Specifically, the inventory area is situated west of the White River on both sides of Sand Wash in Uintah County, Utah. Elevation ranges from 4900 to 5040 ft asl. The project occurs within the Upper Sonoran Desert Shrub Association which includes sagebrush, shadscale, greasewood, mat saltbush, snakeweed, rabbitbrush, and prickly pear cactus. Modern disturbances include livestock grazing, roads, and oil/gas development.

#### CLASS I RESULTS AND RECOMMENDATIONS

The Class I literature review of Kerr-McGee Onshore's 46 proposed well locations and associated pipeline corridors in Township 9S, Range 22E and Township 10S, Range 22E resulted in the location of no cultural resources. Based on the findings, a determination of "no adverse impact" is recommended for the undertaking pursuant to Section 106, CFR 800.

#### REFERENCES CITED

- Montgomery, J. A.  
2008 Cultural Resource Management Report for Kerr-McGee Oil and Gas Onshore LP's Greater NBU Blocks in Township 10 South Range 22 East Uintah County, Utah. Montgomery Archaeological Consultants, Moab, Utah. Report No. U-07-MQ-1438b.
- Montgomery, J. A., and J. Dunn  
2008 Cultural Resource Management Report for Kerr-McGee Oil and Gas Onshore LP's Greater NBU Blocks in Township 9 South, Range 22 East, Uintah County, Utah. Montgomery Archaeological Consultants, Moab, Utah. Report No. U-07-MQ-0461.
- Patterson, J. J., J. Fritz, K. Lower-Eskelson, R. Stash and A. Thomas  
2008 NBU Class I Existing Data Review for Kerr-McGee Oil & Gas Onshore LP, Uintah County, Utah. Montgomery Archaeological Consultants, Moab, Utah.
- Stokes, W. L.  
1986 *Geology of Utah*. Utah Museum of Natural History and Utah Geological and Mineral Survey, Salt Lake City.

**Paleontological Assessment for  
Anadarko Petroleum Corp.  
NBU #922-31F3S, 31F2S, 31J2S**

Archy Bench Quadrangle  
Uintah County, Utah

Prepared for

Anadarko Petroleum Corp.  
and  
School and Institutional Trust Land  
Administration

Prepared by

SWCA Environmental Consultants

03/16/2009  
SWCA #UT09-14314-02

**Paleontological Assessment for Anadarko Petroleum Corp.  
NBU #922-31F3S, 31F2S, 31J2S Proposed Extension of Existing Well Pad**

Prepared for

**Anadarko Petroleum Corp.**

Granite Tower  
1099 18th St. #1200  
Denver, CO 80202

and

**State of Utah**

**School & Institutional Trust Lands Administration**

675 East 500 South, Suite 500  
Salt Lake City, UT 84102-2818

Prepared by:

**Benjamin John Burger, M.S., Justin J. Strauss, M.S., Paul C. Murphey, Ph.D.  
Utah State Permit 07-363**

SWCA Environmental Consultants

2028 West 500 North  
Vernal, UT 84078  
Phone: 435.789.9388  
Fax: 435.789.9385  
[www.swca.com](http://www.swca.com)

SWCA #UT09-14314-02

**03/16/09**

## TABLE OF CONTENTS

	<u>Page</u>
<b>1.0 PROJECT SUMMARY</b> .....	2
<b>2.0 INTRODUCTION</b> .....	3
<b>3.0 METHODS</b> .....	3
3.1 Personnel.....	3
3.2 Records Search Methods.....	3
3.3 Resource Assessment Methods.....	2
3.4 Field Methods .....	4
3.5 Distribution of Data .....	4
<b>4.0 GEOLOGY AND PALEONTOLOGY</b> .....	4
4.1 Uinta Formation .....	5
<b>5.0 RESULTS</b> .....	6
5.1 Previously Documented Localities .....	6
5.2 Paleontological Sensitivities .....	6
5.3 Field Survey .....	7
Well Pad Expansion .....	7
<b>6.0 REFERENCES</b> .....	10

## LIST OF TABLES

<u>Table</u>	<u>Page</u>
Table 1. Paleontological Sensitivities of Geologic Units Within the Project APE. ....	7

## LIST OF MAPS

<u>Map</u>	<u>Page</u>
Map 1. Location of Anadarko Petroleum Corp. Proposed 3 wells to be drilled NBU 922-31F3S, 31F2S, and 31 J2S (on existing well pad NBU#922-31K-2TX) .....	3

## LIST OF FIGURES

<u>Figure</u>	<u>Page</u>
Figure 1. View from center stake, facing north. ....	9
Figure 2. View from center stake facing east.. ....	9
Figure 3. View from center stake, facing south. ....	9
Figure 4. View from center stake, facing west. ....	9
Figure 5. View of ground at center stake. ....	9

## **1.0 PROJECT SUMMARY**

- Paleontological assessment conducted at the request of Anadarko Petroleum Corp. and the State of Utah School & Institutional Trust Lands Administration (SITLA). Performed by SWCA Environmental Consultants.
  - Utah State Permit 07-363
- Paleontological records search and field survey for the expansion of a pre-existing well pad to accommodate three new wells.
- Field survey of proposed well pad and access route completed on 03/03/09 within NE ¼ SW ¼ of Section 31, T9S, R22E in Uintah County, Utah (USGS 7.5 Minute Archy Bench quadrangle).
  - 100-foot survey buffer around well pad.
- Geology
  - Geologic Units (mapped and observed):
    - Lower unit of the Uinta Formation (PFYC Class 5)
- Paleontology
  - No previous localities known in APE.
  - No new fossil localities discovered in area.
- Recommendation
  - **Clearance without further mitigation for well pad.**
  - If any subsurface bones or other potential fossils are encountered during construction anywhere within the project area, work in the immediate vicinity should cease, the BLM should be notified, and a qualified and BLM-permitted paleontologist should inspect the location before work continues.
- Distribution of Survey Report
  - Hard copies sent SITLA and Anadarko Petroleum Corp. Hard copy and electronic copies on file at the SWCA Vernal office.

## 2.0 INTRODUCTION

At the request of Anadarko Petroleum Corp. and the Bureau of Land Management SWCA Environmental Consultants conducted a paleontological records search and field survey for the expansion of a preexisting well pad (NBU# 922-31K-2TX) to accommodate three new wells (NBU#922-31F3S, 31F2S, 31J2S).

The proposed well pad expansion is located in Section 31, T9S, R22E in Uintah County, Utah (USGS 7.5 Minute Archy Bench quadrangle; See Map 1).

### 2.1 Laws, Regulations and Standards

Various laws, regulations, and standards govern how fossils on public lands maybe collected and preserved for future generations. The School and Institutional Trust Lands Administration (Utah State Owned Property) requires a permit and repository agreement with Utah Museum of Natural History for the curation and storage of all “critical paleontological resources” found on Trust Lands (Utah Division of Administrative Rules 807). Furthermore, the state of Utah requires oil, gas and hydrocarbon lessees to provide a paleontological surveys, when requested, prior to project approval (Utah Division of Administrative Rules 850-21-700). A paleontological survey helps to ensure that proposed land use projects do not inadvertently damage or destroy “critical” paleontological resources on state trust lands. This report was prepared in order to describe the known paleontological resources in the area of potential effect for this project, and includes mitigation recommendations.

## 3.0 METHODS

The paleontological survey and evaluation procedures for this assessment were conducted according to State guidelines under Utah State Permit 07-363.

### 3.1 Personnel

Benjamin J.Burger and Justin Strauss completed the field survey, conducted the file search and prepared the final report. Dr. Paul Murphey Principal Investigator on the BLM permit under which this survey was conducted reviewed the final report.


### 3.2 Records Search Methods

Records searches were conducted in order to 1) determine whether any previously recorded fossil localities occur within the project areas; 2) assess the potential for disturbance of these localities during construction; and 3) evaluate the paleontological sensitivity within the area of potential effect (APE). Electronic paleontological records maintained by the Utah Geological Survey, Paleontology Department were searched in order to determine the presence of previously documented fossil localities within the project APE.

### 3.3 Resource Assessment Methods

Geological units are assigned a Potential Fossil Yield Classification System (PFYC) number by the BLM Regional Paleontologists based upon the known paleontology resources from the geological unit and the potential for future significant fossils to be discovered.





**Map 1. Location of Anadarko Petroleum Corp. Proposed 3 wells to be drilled NBU 922-31F3S, 31F2S, and 31 J2S (on existing well pad NBU#922-31K-2TX).**



### 3.4 Field Methods

The survey was designed to 1) determine the surface presence of previously unknown significant vertebrate fossils and/or noteworthy occurrences of invertebrate, plant, or trace fossils; 2) evaluate the condition of documented paleontological localities and the potential for disturbance of these localities during the proposed construction; and 3) evaluate potential adverse impacts to subsurface paleontological resources during construction.

The paleontological field survey consisted of the area within the staked expansion of the well pad plus a 100-foot-wide buffer around the well pad. The APE was inspected for 1) surface fossils; 2) exposures of potentially fossiliferous rocks; and 3) areas in which fossiliferous rocks will be exposed or otherwise impacted during construction. The survey was 100% pedestrian of outcrop.

A paleontological locality documents the location, identification and description of a scientifically significant fossil(s) along with its geologic context. In addition, however, we record the presence of highly weathered, fragmentary or otherwise unidentifiable fossils as non-significant fossil occurrences which typically consist of fragments of turtle shell, unidentifiable bone and tooth fragments, and unidentifiable plant fossils in order to communicate the presence of fossils in a manner that does not trigger mitigation measures. Typically, fossil locality forms and maps are provided only for significant fossil localities which are either collected at the time of discovery or recommended for avoidance and/or later mitigation.

### 3.5 Distribution of Data

Copies of this report will be submitted to BLM and Anadarko Petroleum Corp. Any newly recorded locality data will be submitted to the Utah Geological Survey, State Paleontologist. A hard-copy file will be retained at SWCA Environmental Consultants, Vernal office, along with relevant field notes, maps, and other data.

## 4.0 GEOLOGY AND PALEONTOLOGY

The East-West trending Uinta Mountains were uplifted during the Rocky Mountain-forming Laramide orogeny (Rasmussen et al. 1999) in the Paleocene Epoch (Stokes 1986), exposing the Paleozoic-age rocks in the core of the mountains and Mesozoic-age rocks along their flanks. In conjunction with the uplift, the southerly-adjacent synclinal Uinta Basin formed (Rasmussen et al. 1999). From the Paleocene to the middle Eocene, sediments from freshwater lakes and later from river channels, river deltas and floodplains filled the basin with sediments and accompanying fossils (Stokes 1986, Townsend 2004). From oldest to youngest, these rock units include the Wasatch, Green River, Uinta and Duchesne River formations. Collectively, these units represent the primary source of middle Eocene-aged vertebrate, invertebrate and plant fossils from Utah and Colorado, and are thus of great scientific importance. Locally, Pleistocene- and Holocene-aged sediments deposited by rivers, streams, gravity, and wind overlie the bedrock geologic units.

The project APE contains one mapped geologic unit (Rowley et al 1995): Eocene-age lower Uinta Formation.

## 4.1 Uinta Formation

The middle Eocene Uinta Formation preserves a rich fossil record extending from about 46.5 to 40 million years ago (Prothero 1996). During this period, Earth's climate slowly cooled from the previously intense warm period of the early Eocene (Zachos et al. 2001). Many fossil mammals from the Uinta Formation represent a mix of modern and ancient forms (Scott and Osborn 1890; Peterson 1919; Robinson et al. 2004; Townsend 2004).

Fossil mammals known from the Uinta Formation include the carnivorous mammals *Mesonyx* and *Harpagolestes*, members of the Mesonychidae, an extinct family of mammals distantly related to whales and even-toed hoofed mammals. Mesonychids exhibit large sharp teeth and claws with the superficial appearance of modern wolves (Scott 1888; Peterson 1931). The Uinta Formation also produces remains of large six horned, saber toothed beasts call *Uintatheres*. As a member of the long extinct mammalian order Dinocerata, *Uintathere* fossils are featured in many museum exhibits (Wheeler 1961). Another large but uncommon mammal fossil known from the Uinta Formation is the early chalicothere *Eomorphus*. Long extinct, chalicotheres are a group of perissodactyl (odd toed ungulate) mammals that featured long forelegs equipped with claws used to strip vegetation for food, yet retained a horse like skull. A small fossil mammal known from the Uinta Formation is *Apatemys*, an arboreal animal with long anterior incisors adapted to feed on bark grubs and other insects. The Uinta Formation also preserves some of the last remaining early primates in North America (Townsend, 2004), including the omomyid primates *Macrotarsius*, *Ourayia*, *Trogolemur* and the more recently described *Chipetaia* (Rasmussen 1996). Primates would eventually vanish from North America as the climate continued to cool into the Oligocene Epoch (about 35 million years ago; Townsend 2004). The small bodied hyaenodontid creodonts, a sister group to modern carnivores co-occur with early ancestors of modern cats and dogs including *Procynodictis*, *Tapocyon* and *Prodaphaenus* in the Uinta Formation (Flynn and Galiano 1982, Townsend 2004). Other fossil mammals known from the Uinta Formation include a great diversity of rodents, representing six families (Robinson et al. 2004), and the earliest North American rabbit *Mytonolagus* (Dawson 1970). The Uinta Formation also preserves an excellent record of the early diversification of Artiodactyls (even toed ungulates) including the early camel *Poebrodon* and the deer-like *Leptotragulus* (Gazin 1955). Remains of Perissodactyls are equally diverse, including the early rhino *Amyrnodon*, the tapiriod *Colodon*, early horse *Epihippus* (Granger 1908), as well numerous large brontotheres (Riggs 1912; Osborn 1929).

More common than mammal fossils, reptile remains from the Uinta Formation include a rich record of turtles including *Baena*, *Echmatemys* and *Trionyx*. Fossil teeth, bones and osteoderms of ancient crocodiles are common throughout the formation.

Because of its diverse and locally abundant mammalian fossils, the Uinta Formation was designated as the stratotype for the Uintan North American Land Mammal Age (Wood et al. 1940). Subsequently, Uintan aged strata have been documented at other locations in North America using the exceptional fossil record of the Uinta Formation in the Uinta Basin for comparison (Flynn 1986, Walsh 1996; Townsend 2004; Murphey and Evanoff 2007).

The following museums have fossils from the Uinta Formation in their collections:

American Museum of Natural History, New York, New York.  
Carnegie Museum of Natural History, Pittsburgh, Pennsylvania.  
Smithsonian National Museum of Natural History, Washington, D.C.  
Vernal Field House of Natural History, Vernal, Utah.  
Yale Peabody Museum, New Haven, Connecticut.

Smaller collections are known from:

Brigham Young University Earth Science Museum, Provo, Utah.  
Utah Museum of Natural History, Salt Lake City, Utah.  
Museum of Comparative Zoology, Harvard University, Cambridge, Massachusetts.  
Field Museum of Natural History, Chicago, Illinois.  
University of Colorado Museum of Natural History, Boulder, Colorado.

Lithologically, the Uinta Formation consists of greenish-gray, reddish-brown, yellow, grayish-orange, and purple fluvial and lacustrine shale marlstone, siltstone, and sandstone beds which are locally tuffaceous (Cashion 1973; Dane 1954; Rowley et al. 1985). In general terms, the Uinta Formation conformably overlies and interfingers with the Green River Formation in the Uinta and Piceance Creek Basins, and is overlain by the Duchesne River Formation in the Uinta Basin. Despite its historical and scientific importance to vertebrate paleontology, the detailed stratigraphy of the Uinta Formation is complex and not yet fully understood.

Named by Marsh (1871), geologists have subdivided the Uintan Formation from stratigraphically lowest to highest into three horizons A, B, and C. The A and B horizons represents the Wagonhound Member of the Uinta Formation, and the C horizon represents the Myton Member. The mudstone and claystone-dominated horizons (Uinta B and C) contain many well preserved fossil remains, while fossils recovered from the sandstone dominated horizon (Uinta A) are less well preserved and rare. The specific location of these subunit boundaries has shifted slightly with almost each successive publication on the stratigraphy of the area, resulting in a well-understood broad picture for which the stratigraphic details are hazy and the biostratigraphy unresolved (Walsh 1996). The most recent stratigraphic and paleontologic work in the Uinta Formation has included important efforts to better characterize and document the lithostratigraphy, biostratigraphy paleoecology, and paleoenvironments of the Uinta Formation and time-equivalent strata (see Rasmussen et al. 1999; Townsend 2004; Walsh 1996; Townsend et al. 2006). Documentation of where fossils are recovered within the Uinta Formation remains essential for understanding how life and the environment changed during this long interval of time.

## 5.0 RESULTS

The following section presents the results of the records search and field survey conducted for the Anadarko Petroleum Corp. for the expansion of a preexisting well pad.

### 5.1 Previously Documented Localities

The nearest important fossil locality is located 0.38 miles toward the north-west direction from the proposed pad extension. This locality yielded remains of the agriochoerid artiodactyl *Protoreodon*, brontothere postcranial elements, and abundant turtle bone and shell fragments. Twelve previously recorded fossil localities are reported within a 1-mile radius of the proposed well pad extension, most of which are located above the Sand Wash Creek where the well is located. None of these previously recorded fossil localities are located within the APE.

### 5.2 Paleontological Sensitivities

The paleontological sensitivity of the one mapped geologic unit (Rowley et al 1995) in the project APE has been classified according to the PFYC by the BLM and is summarized in Table 1.

**Table 1. Paleontological Sensitivities of Geologic Units Within the Project APE.**

Geologic Unit	Map Symbol*	Age	Typical Fossils	PFYC
Uinta Formation, lower part	Tul	Eocene	Locally abundant plants (leaves, seeds, wood); invertebrates (insects, mollusks); and a highly diverse and scientifically important vertebrate fauna (reptiles, mammals)	Class 5

\* Rowley et al 1995



### 5.3 Field Survey

<b>922-31F3S, 31F2S, 31J2S</b>	<b>Well pad extension on preexisting well pad</b>		
<b>Location:</b>	NE ¼ SW ¼ Section 31, T9S, R22E		
<b>Surveyed on:</b>	3/3/2009	<b>By:</b>	Ben Burger and Justin Strauss
<b>Survey Remarks:</b>	100% pedestrian survey of existing well pad with proposed 3 new wells and new pit.		
<b>Photos:</b>	Figures 1-5		
<b>Geologic Formation(s):</b>	Uinta Fm, lower Mbr	Eocene	PFYC Class 5
<b>Reference:</b>	Rowley et al 1995		
<b>Topography:</b>	Located within Sand Wash, against the eastern wall.		
<b>Bedrock Exposure Status:</b>	Extensive bedrock exposure along eastern side of pad forming a large cliff.		
<b>Geologic Description:</b>	Coarsed grained fluvial sandstone, lag deposits up to 1 cm diameter, dark brown to black clasts, interbedded with gray-green and red-brown mudstones and claystones.		
<b>Fossil Status:</b>	None		
<b>Fossil Description:</b>	N/A		
<b>Recommendation:</b>	<p>Immediate paleontological clearance.</p> <p>However, if any subsurface bones or other potential fossils are encountered during construction anywhere within the project area, work in the immediate vicinity should cease, the BLM should be notified, and a qualified and BLM-permitted paleontologist should inspect the location <i>before</i> work continues.</p>		



**Figure 1. View from center stake, facing north.**



**Figure 2. View from center stake facing east. Note extensive badlands exposures forming large cliff against well pad's eastern edge.**



**Figure 3. View from center stake, facing south.**



**Figure 4. View from center stake, facing west.**



**Figure 5. View of ground at center stake.**

## 6.0 REFERENCES

- Bureau of Land Management (BLM). 2007. Instructional Memorandum 2008-009, Potential Fossil Resource Classification System.
- Cashion, W. B. 1973. Geologic and structure map of the Grand Junction quadrangle, Colorado and Utah: U.S. Geological Survey, Miscellaneous Geologic Investigations Map I-736 (1:250,000).
- Dane, C. H. 1954. Stratigraphic and facies relationships of upper part of Green River Formation and lower part of Uinta Formation in Duchesne, Uintah, Wasatch Counties, Utah: American Association of Petroleum Geologists Bulletin, 38(2): 405-425.
- Dawson, M. 1970. Paleontology and geology of the Badwater Creek area, central Wyoming. Part 6. The leporid *Mytonolagus* (Mammalia, Lagomorpha). Annals of Carnegie Museum 7:215-230.
- Flynn, J. J. 1986. Correlation and geochronology of Middle Eocene strata from the western United States. Palaeogeography, Palaeoclimatology, Palaeoecology 55:335-406.
- Flynn, J. J. and Galiano, H. 1982. Phylogeny of early Tertiary Carnivora, with a description of a new species of *Protictis* from the Middle Eocene of northwestern Wyoming. American Museum Novitates 2725:1-64.
- Gazin, C. L. 1955. A review of the upper Eocene Artiodactyla of North America. Smithsonian Miscellaneous Collections 128(8):1-96.
- Granger, W. 1908. A revision of the American Eocene horses. Bulletin of the American Museum of Natural History 14:221-264.
- Marsh, O.C. 1871. Notice of some new fossil reptiles from the Cretaceous and Tertiary formations. American Journal of Science and Arts 4:122-28,202-24.
- Murphey, P.C., and Evanoff, E. 2007. Stratigraphy, fossil distribution and depositional environments of the upper Bridger Formation (middle Eocene), southwestern Wyoming: Wyoming State Geological Survey Report of Investigation 57, 107 p, (1 map, scale 1:100,000; 10 maps, scale 1:24,000).
- Osborn, H. F. 1895. Fossil mammals of the Uinta Basin, Expedition of 1894. Bulletin of the American Museum of Natural History 7:71-105.
- Osborn, H. F., 1929. The titanotheres of ancient Wyoming, Dakota, and Nebraska. U.S. Geologic Survey Monograph 1:1-701.

- Peterson, O. A. 1919. Report upon the material discovered in the Upper Eocene of the Uinta Basin by Earl Douglas in the years 1908-1909, and by O. A. Peterson in 1912. *Annals of Carnegie Museum* 12(2):40-168.
- Peterson, O. A. 1931. New mesonychids from the Uinta. *Annals of the Carnegie Museum*.16:333-339.
- Prothero, D. R., 1996. Magnetic Stratigraphy and Biostratigraphy of the Middle Eocene Uinta Formation, Uinta Basin, Utah. *In*: D. R. Prothero and R. J. Emry (eds.): *The Terrestrial Eocene-Oligocene Transition in North America*. Cambridge University Press, pp. 75-119.
- Rasmussen, D. T. 1996. A new Middle Eocene omomyine primate from the Uinta Basin, Utah. *Journal of Human Evolution* 31:75-87.
- Rasmussen, D. T., G. C. Conroy, A. R. Friscia, K. E. Townsend, and M. D. Kinkel. 1999. Mammals of the middle Eocene Uinta Formation. *In*: Gillette, D.E. (ed.). *Vertebrate Paleontology in Utah: Utah Geological Survey Miscellaneous Publication*, 99-1: 401-420.
- Riggs, E. S., 1912. New or little known titanotheres from the Lower Uintah Formations. *Field Museum of Natural History Geological Series* 159:17-41.
- Robinson, P., Gunnell, G. F., Walsh, S. L., Clyde, W. C., Storer, J. E., Stucky, R. K., Froehlich, D. J., Ferrusquia-Villafranca, I., McKenna, M. C. 2004. Wasatchian through Duchesnean Biochronology. *In*: Woodburne, M. O. (ed.): *Late Cretaceous and Cenozoic Mammals of North America; Biostratigraphy and geochronology*, pp. 106-155.
- Rowley, P. D., W. R. Hansen, O. Tweto, and P. E. Carrara. 1985. Geologic map of the Vernal 1° X 2° Quadrangle, Colorado, Utah and Wyoming: U.S. Geological Survey Miscellaneous Investigations Map I-1526 (scale 1:250,000).
- Scott, W. B. 1888. On some new and little known creodonts. *Journal of the Academy of Natural Sciences Philadelphia* 9:155-185.
- Scott, W. B. and Osborn, H. F., 1890. The Mammalia of the Uinta Formation. *Transactions of the American Philosophical Society* 1887:255-264.
- Stokes, W. L. 1986. *Geology of Utah: Utah Museum of Natural History, University of Utah and Utah Geological and Mineral Survey, Department of Natural Resources.*
- Stucky, R. K. 1992. Mammalian faunas in North America of Bridgerian to Arikareean "ages" (Eocene and Oligocene): *In*: D. R. Prothero and W. A. Berggren (eds.): *Eocene-Oligocene Climatic and Biotic Evolution*. Princeton, N.J.: Princeton University Press, pp. 463-93.



- Townsend, K. E. 2004. Stratigraphy, paleoecology, and habitat change in the middle Eocene of North America: Unpublished dissertation, Washington University, 418 pp.
- Townsend, K. E., Friscia, A. R., Rasmussen, D. T. 2006. Stratigraphic Distribution of Upper Middle Eocene Fossil Vertebrate Localities in the Eastern Uinta Basin, Utah, with comments on Uintan Biostratigraphy. *The Mountain Geologist* 43(2):115-134.
- Walsh, S. L. 1996. Middle Eocene mammalian faunas of San Diego County, California. *In*: D. R. Prothero and R. J. Emry (eds.): *The Terrestrial Eocene-Oligocene Transition in North America*. Cambridge: Cambridge University Press, p. 75-119.
- Wheeler, W.H. 1961. Revision of the Uintatheres. *Bulletin of the Peabody Museum of Natural History*, p. 93.
- Wood, H. E., R. W. Chaney, J. Clark, E. H. Colbert, G. L. Jepsen, J. B. Reeside, Jr., and C. Stock. 1941. Nomenclature and correlation of the North American continental Tertiary. *Bulletin of the Geological Society of America*, 52:1-48.
- Utah Division of Administrative Rules (<http://www.rules.utah.gov/>) accessed 3/6/2009.
- Zachos, J., Pagani, M., Sloan, L., Thomas, E. and Billips, K. 2001. Trends, rhythms, and aberrations in global climate 65 Ma to present. *Science* 292:686-693.

Location Map

Box Elder Cache Rich  
Hemp Morgan  
Dove Summit Disposit  
Salt Lake  
Tooele Utah Duchesne Uintah  
Juab Carbon  
Sanpete  
Millard Emery Grand  
Sevier  
Beaver Piute Wayne  
Iron Garfield San Juan  
Washington Kane

**From:** Jim Davis  
**To:** Bonner, Ed; Mason, Diana  
**Date:** 6/1/2009 8:12 AM  
**Subject:** Well approvals. 3 for Anadarko.

**CC:** Garrison, LaVonne  
The following wells have been approved by SITLA including arch and paleo clearance.

NBU 922-31F2S (4304750415)  
NBU 922-31J2S (4304750417)  
NBU 922-31f3S (4304750419)

-Jim

Jim Davis  
Utah Trust Lands Administration  
jimdavis1@utah.gov  
Phone: (801) 538-5156

# United States Department of the Interior

## BUREAU OF LAND MANAGEMENT

Utah State Office  
P.O. Box 45155  
Salt Lake City, Utah 84145-0155

### IN REPLY REFER TO:

3160  
(UT-922)

June 5, 2009

### Memorandum

To: Assistant District Manager Minerals, Vernal District

From: Michael Coulthard, Petroleum Engineer

Subject: 2009 Plan of Development Natural Buttes Unit Uintah  
County, Utah.

Pursuant to email between Diana Whitney, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management, the following wells are planned for calendar year 2009 within the Natural Buttes Unit, Uintah County, Utah.

API #	WELL NAME	LOCATION
(Proposed PZ WASATCH-MESA VERDE)		
43-047-50415	NBU 922-31F2S Sec 31 T09S R22E 2626 FSL 1451 FWL BHL Sec 31 T09S R22E 1737 FNL 1258 FWL	
43-047-50417	NBU 922-31J2S Sec 31 T09S R22E 2552 FSL 1420 FWL BHL Sec 31 T09S R22E 2611 FSL 1837 FEL	
43-047-50419	NBU 922-31F3S Sec 31 T09S R22E 2607 FSL 1443 FWL BHL Sec 31 T09S R22E 2215 FNL 1258 FWL	
43-047-50428	NBU 1022-18I4BS Sec 18 T10S R22E 0213 FSL 0292 FEL BHL Sec 18 T10S R22E 1690 FSL 0580 FEL	
43-047-50429	NBU 1022-18O1AS Sec 18 T10S R22E 0231 FSL 0301 FEL BHL Sec 18 T10S R22E 1115 FSL 1400 FEL	
43-047-50430	NBU 1022-18P1DS Sec 18 T10S R22E 0196 FSL 0283 FEL BHL Sec 18 T10S R22E 0855 FSL 0050 FEL	
43-047-50431	NBU 1022-18P4AS Sec 18 T10S R22E 0178 FSL 0274 FEL BHL Sec 18 T10S R22E 0505 FSL 0050 FEL	
43-047-50446	NBU 922-32J4CS Sec 32 T09S R22E 1453 FSL 2398 FEL BHL Sec 32 T09S R22E 1463 FSL 1902 FEL	
43-047-50461	NBU 1022-24O2S Sec 24 T10S R22E 0684 FSL 2016 FEL	



BHL Sec 24 T10S R22E 1060 FSL 2080 FEL

This office has no objection to permitting the wells at this time.

/s/ Michael L. Coulthard

bcc: File – Natural Buttes Unit  
Division of Oil Gas and Mining  
Central Files  
Agr. Sec. Chron  
Fluid Chron

MCoulthard:mc:6-5-09

Well Name	KERR-MCGEE OIL & GAS ONSHORE, L.P. NBU 922-31J2S 43047504170000			
String	Surf	Prod		
Casing Size(in)	9.625	4.500		
Setting Depth (TVD)	2135	9170		
Previous Shoe Setting Depth (TVD)	20	2135		
Max Mud Weight (ppg)	8.3	11.6		
BOPE Proposed (psi)	500	5000		
Casing Internal Yield (psi)	3250	7780		
Operators Max Anticipated Pressure (psi)	5427	11.4		

Calculations	Surf String	9.625	"
Max BPH (psi)	.052*Setting Depth*MW=	925	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	669	NO
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	455	YES OK
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	460	NO Reasonable depth in area
Required Casing/BOPE Test Pressure=		2135	psi
*Max Pressure Allowed @ Previous Casing Shoe=		20	psi *Assumes 1psi/ft frac gradient


Calculations	Prod String	4.500	"
Max BPH (psi)	.052*Setting Depth*MW=	5531	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	4431	YES
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	3514	YES OK
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	3983	NO Reasonable, note max allowed pressure
Required Casing/BOPE Test Pressure=		5000	psi
*Max Pressure Allowed @ Previous Casing Shoe=		2135	psi *Assumes 1psi/ft frac gradient

Calculations	String		"
Max BPH (psi)	.052*Setting Depth*MW=		
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=		NO
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=		NO
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=		NO
Required Casing/BOPE Test Pressure=			psi
*Max Pressure Allowed @ Previous Casing Shoe=			psi *Assumes 1psi/ft frac gradient

Calculations	String		"
Max BPH (psi)	.052*Setting Depth*MW=		
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=		NO
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=		NO
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=		NO
Required Casing/BOPE Test Pressure=			psi
*Max Pressure Allowed @ Previous Casing Shoe=			psi *Assumes 1psi/ft frac gradient

43047504170000 NBU 922-31J2S

Casing Schematic



Well name:	<b>43047504170000 NBU 922-31J2S</b>	
Operator:	<b>KERR-MCGEE OIL &amp; GAS ONSHORE, L.P.</b>	
String type:	Surface	Project ID: 43-047-50417
Location:	UINTAH COUNTY	

**Design parameters:**

**Collapse**

Mud weight: 8.330 ppg  
Design is based on evacuated pipe.

**Minimum design factors:**

**Collapse:**

Design factor 1.125

**Burst:**

Design factor 1.00

**Environment:**

H2S considered? No  
Surface temperature: 74 °F  
Bottom hole temperature: 104 °F  
Temperature gradient: 1.40 °F/100ft  
Minimum section length: 100 ft

Cement top: 1,593 ft

**Burst**

Max anticipated surface pressure: 1,879 psi  
Internal gradient: 0.120 psi/ft  
Calculated BHP 2,135 psi

No backup mud specified.

**Tension:**

8 Round STC: 1.80 (J)  
8 Round LTC: 1.70 (J)  
Buttress: 1.60 (J)  
Premium: 1.50 (J)  
Body yield: 1.50 (B)

Tension is based on air weight.  
Neutral point: 1,872 ft

**Non-directional string.**

**Re subsequent strings:**

Next setting depth: 9,170 ft  
Next mud weight: 11.600 ppg  
Next setting BHP: 5,526 psi  
Fracture mud wt: 19.250 ppg  
Fracture depth: 2,135 ft  
Injection pressure: 2,135 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	2135	9.625	36.00	J-55	LT&C	2135	2135	8.796	17459

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	924	2020	2.186	2135	3520	1.65	76.9	453	5.89 J

Prepared by: Helen Sadik-Macdonald  
Div of Oil, Gas & Mining

Phone: 801 538-5357  
FAX: 801-359-3940

Date: June 18, 2009  
Salt Lake City, Utah

**Remarks:**

Collapse is based on a vertical depth of 2135 ft, a mud weight of 8.33 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Well name: <b>43047504170000 NBU 922-31J2S</b>	
Operator: <b>KERR-MCGEE OIL &amp; GAS ONSHORE, L.P.</b>	Project ID: <b>43-047-50417</b>
String type: <b>Production</b>	
Location: <b>UINTAH COUNTY</b>	

**Design parameters:**

**Collapse**

Mud weight: 11.600 ppg  
Design is based on evacuated pipe.

**Minimum design factors:**

**Collapse:**

Design factor 1.125

**Burst:**

Design factor 1.00

**Environment:**

H2S considered? No  
Surface temperature: 74 °F  
Bottom hole temperature: 202 °F  
Temperature gradient: 1.40 °F/100ft  
Minimum section length: 100 ft

Cement top: Surface

**Burst**

Max anticipated surface pressure: 3,508 psi  
Internal gradient: 0.220 psi/ft  
Calculated BHP 5,526 psi

No backup mud specified.

**Tension:**

8 Round STC: 1.80 (J)  
8 Round LTC: 1.80 (J)  
Buttress: 1.60 (J)  
Premium: 1.50 (J)  
Body yield: 1.60 (B)

Tension is based on air weight.  
Neutral point: 7,966 ft

**Directional Info - Build & Drop**

Kick-off point 2150 ft  
Departure at shoe: 1615 ft  
Maximum dogleg: 3 °/100ft  
Inclination at shoe: 0 °

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	9556	4.5	11.60	I-80	LT&C	9170	9556	3.875	126139

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	5526	6360	1.151	5526	7780	1.41	106.4	212	1.99 J

Prepared by: Helen Sadik-Macdonald  
Div of Oil, Gas & Mining

Phone: 801 538-5357  
FAX: 801-359-3940

Date: June 18, 2009  
Salt Lake City, Utah

**Remarks:**

Collapse is based on a vertical depth of 9170 ft, a mud weight of 11.6 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Collapse strength is (biaxially) derated for doglegs in directional wells by multiplying the tensile stress by the cross section area to calculate a

*Engineering responsibility for use of this design will be that of the purchaser.*



**ON-SITE PREDRILL EVALUATION****Utah Division of Oil, Gas and Mining**

**Operator** KERR-MCGEE OIL & GAS ONSHORE, L.P.  
**Well Name** NBU 922-31J2S  
**API Number** 43047504170000 **APD No** 1535 **Field/Unit** NATURAL BUTTES  
**Location: 1/4,1/4** NESW **Sec** 31 **Tw** 9.0S **Rng** 22.0E 2552 FSL 1420 FWL  
**GPS Coord (UTM)** **Surface Owner**

**Participants**

Floyd Bartlett (DOGM), Jim Davis (SITLA), Raleen White, Griz Oleen, Clay Einerson, Charles Chase and Tony Kzneck (Kerr McGee), Ben Williams (UDWR) and Kolby Kay (Timberline Engineering and Land Surveying).

**Regional/Local Setting & Topography**

The general area is the Natural Buttes Unit in the lower portion of the Sand Wash Drainage of Uintah, County, approximately 35 air miles and 51 road miles south of Vernal, Utah. Access is by State of Utah Highways, Uintah County and existing oilfield development roads to the site. Topography of the Sand Wash area is characterized by broad open flats dissected by numerous sub-drainages, which often become steep with ridges and draws with exposed sandstone layers. No perennial streams occur in the drainage. Individual draws or washes are ephemeral with spring runoff or flows from sometimes-intense summer rainstorms. No springs exist in the area. An occasional constructed pond occurs furnishing water for antelope or livestock.

The existing pad of the producing NBU 280 well will be extended on 3 sides to provide more width and length. Three additional directional wells will be drilled on the enlarged pad. They are the NBU 922-31F3S, NBU 922-31F2S and NBU 922-31J2S. The site is in the bottom of a canyon that runs to the north. It is surrounded on the east and west by hills with sandstone ledges. The defined drainage of the canyon is to the west beyond the location and contains tamarix vegetation. The surface of the existing location will be lowered 0.3 feet to obtain fill for enlarging the pad. The reserve pit will be cut into a slope on the northeast side of the location which has had significant previously excavation. A surface drainage ditch is needed on the east side of the pit extending north around the pit. The White River is approximately 3 miles down drainage.

Both the surface and minerals are owned by SITLA. Jim Davis represented SITLA at the pre-site investigation. Mr. Davis had no concerns pertaining to this location. The selected location appears to be a suitable site for drilling and operating additional wells.

**Surface Use Plan****Current Surface Use**

Grazing  
 Recreational  
 Wildlife Habitat  
 Existing Well Pad

<b>New Road Miles</b>	<b>Well Pad</b>	<b>Src Const Material</b>	<b>Surface Formation</b>
0	<b>Width</b> 305 <b>Length</b> 450	Onsite	UNTA

**Ancillary Facilities** N

**Waste Management Plan Adequate?****Environmental Parameters**

**Affected Floodplains and/or Wetlands** N

**Flora / Fauna**

Vegetation is a poor desert shrub type, which includes sagebrush, greasewood, cheatgrass, Russian thistle, tamarix, halogeton and spring annuals.

Antelope, sheep during the winter, rabbits, coyotes, and small mammals, birds and raptors.

**Soil Type and Characteristics**

Deep sandy loam.

**Erosion Issues N**

**Sedimentation Issues Y**

A surface drainage ditch is needed on the east side of the pit extending north around the pit.

**Site Stability Issues**

**Drainage Diversion Required? Y**

A surface drainage ditch is needed on the east side of the pit extending north around the pit.

**Berm Required? N**

**Erosion Sedimentation Control Required? Y**

**Paleo Survey Run? Y Paleo Potential Observed? N Cultural Survey Run? Y Cultural Resources?**

**Reserve Pit**

**Site-Specific Factors**

**Site Ranking**

<b>Distance to Groundwater (feet)</b>	>200	0
<b>Distance to Surface Water (feet)</b>	>1000	0
<b>Dist. Nearest Municipal Well (ft)</b>	>5280	0
<b>Distance to Other Wells (feet)</b>		20
<b>Native Soil Type</b>	Mod permeability	10
<b>Fluid Type</b>	Fresh Water	5
<b>Drill Cuttings</b>	Normal Rock	0
<b>Annual Precipitation (inches)</b>		0
<b>Affected Populations</b>		
<b>Presence Nearby Utility Conduits</b>	Not Present	0
<b>Final Score</b>		35

1 Sensitivity Level

**Characteristics / Requirements**

The proposed reserve pit is 70' x 220' x 10' deep located in a cut on the northeast corner of the location. Kerr McGee plans a 30-mil liner with a double felt sub-liner.

**Closed Loop Mud Required? N Liner Required? Y Liner Thickness 30 Pit Underlayment Required? Y**

**Other Observations / Comments**

Floyd Bartlett

5/20/2009

**Evaluator**

**Date / Time**

# Application for Permit to Drill

## Statement of Basis

7/15/2009

Utah Division of Oil, Gas and Mining

Page 1

<b>APD No</b>	<b>API WellNo</b>	<b>Status</b>	<b>Well Type</b>	<b>Surf Owner</b>	<b>CBM</b>
1535	43047504170000	LOCKED	GW	S	No
<b>Operator</b>	KERR-MCGEE OIL & GAS ONSHORE, L.P.		<b>Surface Owner-APD</b>		
<b>Well Name</b>	NBU 922-31J2S		<b>Unit</b>	NATURAL BUTTES	
<b>Field</b>	NATURAL BUTTES		<b>Type of Work</b>	DRILL	
<b>Location</b>	NESW 31 9S 22E S 2552 FSL 1420 FWL GPS Coord (UTM) 629360E 4427797N				

### Geologic Statement of Basis

Kerr McGee proposes to set 2,135' of surface casing at this location. The depth to the base of the moderately saline water at this location is estimated to be at a depth of 2,900'. A search of Division of Water Rights records shows no water wells within a 10,000 foot radius of the center of section 31. The surface formation at this site is the Uinta Formation. The Uinta Formation is made up of interbedded shales and sandstones. The sandstones are mostly lenticular and discontinuous and should not be a significant source of useable ground water. Production casing cement should be brought to above the base of the moderately saline groundwater in order to isolate it from fresher waters uphole.

Brad Hill  
APD Evaluator

6/3/2009  
Date / Time

### Surface Statement of Basis

The general area is the Natural Buttes Unit in the lower portion of the Sand Wash Drainage of Uintah, County, approximately 35 air miles and 51 road miles south of Vernal, Utah. Access is by State of Utah Highways, Uintah County and existing oilfield development roads to the site. Topography of the Sand Wash area is characterized by broad open flats dissected by numerous sub-drainages, which often become steep with ridges and draws with exposed sandstone layers. No perennial streams occur in the drainage. Individual draws or washes are ephemeral with spring runoff or flows from sometimes-intense summer rainstorms. No springs exist in the area. An occasional constructed pond occurs furnishing water for antelope or livestock.

The existing pad of the producing NBU 280 well will be extended on 3 sides to provide more width and length. Three additional directional wells will be drilled on the enlarged pad. They are the NBU 922-31F3S, NBU 922-31F2S and NBU 922-31J2S. The site is in the bottom of a canyon that runs to the north. It is surrounded on the east and west by hills with sandstone ledges. The defined drainage of the canyon is to the west beyond the location and contains tamarix vegetation. The surface of the existing location will be lowered 0.3 feet to obtain fill for enlarging the pad. The reserve pit will be cut into a slope on the northeast side of the location which has had significant previously excavation. A surface drainage ditch is needed on the east side of the pit extending north around the pit. The White River is approximately 3 miles down drainage.

Both the surface and minerals are owned by SITLA. Jim Davis represented SITLA at the pre-site investigation. Mr. Davis had no concerns pertaining to this location. The selected location appears to be a suitable site for drilling and operating additional wells.

Ben Williams of the Utah Division of Wildlife Resources also attended the pre-site. Mr. Williams stated no wildlife values would be significantly affected by drilling and operating the wells at this location.

T

Floyd Bartlett  
Onsite Evaluator

5/20/2009  
Date / Time

---

# Application for Permit to Drill

## Statement of Basis

7/15/2009

Utah Division of Oil, Gas and Mining

---

Page 2

### Conditions of Approval / Application for Permit to Drill

Category	Condition
Pits	A synthetic liner with a minimum thickness of 30mils with a felt subliner shall be properly installed and maintained in the reserve pit.
Surface	Drainages adjacent to the proposed pad shall be diverted around the location.
Surface	The reserve pit shall be fenced upon completion of drilling operations.



# WORKSHEET

## APPLICATION FOR PERMIT TO DRILL

**APD RECEIVED:** 5/11/2009

**API NO. ASSIGNED:** 43047504170000

**WELL NAME:** NBU 922-31J2S

**OPERATOR:** KERR-MCGEE OIL & GAS ONSHORE, L.P. (N2995)

**PHONE NUMBER:** 720 929-6156

**CONTACT:** Danielle Piernot

**PROPOSED LOCATION:** NESW 31 090S 220E

**Permit Tech Review:** ☒

**SURFACE:** 2552 FSL 1420 FWL

**Engineering Review:** ☒

**BOTTOM:** 2611 FSL 1837 FEL

**Geology Review:** ☒

**COUNTY:** UINTAH

**LATITUDE:** 39.99234

**LONGITUDE:** -109.48477

**UTM SURF EASTINGS:** 629360.00

**NORTHINGS:** 4427797.00

**FIELD NAME:** NATURAL BUTTES

**LEASE TYPE:** 3 - State

**LEASE NUMBER:** UO 1207A

**PROPOSED PRODUCING FORMATION(S):** WASATCH-MESA VERDE

**SURFACE OWNER:** 3 - State

**COALBED METHANE:** NO

### RECEIVED AND/OR REVIEWED:

☒ **PLAT**

☒ **Bond:** STATE/FEE - 22013542

☐ **Potash**

☒ **Oil Shale 190-5**

☐ **Oil Shale 190-3**

☐ **Oil Shale 190-13**

☒ **Water Permit:** Permit #43-8496

☐ **RDCC Review:**

☐ **Fee Surface Agreement**

☒ **Intent to Commingle**

**Commingle Approved**

### LOCATION AND SITING:

☐ **R649-2-3.**

**Unit:** NATURAL BUTTES

☐ **R649-3-2. General**

☐ **R649-3-3. Exception**

☒ **Drilling Unit**

**Board Cause No:** Cause 173-14

**Effective Date:** 12/2/1999

**Siting:** 460' fr u bdry & uncomm. tract

☒ **R649-3-11. Directional Drill**

**Comments:** Presite Completed

**Stipulations:**  
3 - Commingle - ddoucet  
5 - Statement of Basis - bhill  
15 - Directional - dmason  
17 - Oil Shale 190-5(b) - dmason  
25 - Surface Casing - hmacdonald



JON M. HUNTSMAN, JR.  
*Governor*

GARY R. HERBERT  
*Lieutenant Governor*

## State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER  
*Executive Director*

Division of Oil, Gas and Mining

JOHN R. BAZA  
*Division Director*

### Permit To Drill

\*\*\*\*\*

**Well Name:** NBU 922-31J2S  
**API Well Number:** 43047504170000  
**Lease Number:** UO 1207A  
**Surface Owner:** STATE  
**Approval Date:** 8/5/2009

**Issued to:**

KERR-MCGEE OIL & GAS ONSHORE, L.P., P.O. Box 173779, Denver, CO 80217

**Authority:**

Pursuant to Utah Code Ann. §40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of Cause 173-14. The expected producing formation or pool is the WASATCH-MESA VERDE Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

**Duration:**

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

**Commingling:**

In accordance with Board Cause No. 173-14 commingling the production from the Wasatch formation and the Mesaverde formation in this well is allowed.

**General:**

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

**Conditions of Approval:**

In accordance with Utah Admin. R. 649-3-11, Directional Drilling, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.

In accordance with the Order in Cause No. 190-5(b) dated October 28, 1982, the operator shall comply with the requirements of Rules R649-3-31 and R649-3-27 pertaining to Designated Oil Shale Areas. Additionally, the operators shall ensure that the surface and or production casing is properly cemented over the entire oil shale section as defined by Rule R649-3-31. The Operator shall report the actual depth the oil shale is encountered to the division.

Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis (copy attached).

Surface casing shall be cemented to the surface.

**Additional Approvals:**

The operator is required to obtain approval from the Division of Oil, Gas and mining before performing any of the following actions during the drilling of this well:

- Any changes to the approved drilling plan – contact Dustin Doucet
- Significant plug back of the well – contact Dustin Doucet
- Plug and abandonment of the well – contact Dustin Doucet

**Notification Requirements:**

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- Within 24 hours following the spudding of the well – contact Carol Daniels  
OR  
submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website at <http://oilgas.ogm.utah.gov>
- 24 hours prior to testing blowout prevention equipment - contact Dan Jarvis
- 24 hours prior to cementing or testing casing – contact Dan Jarvis
- Within 24 hours of making any emergency changes to the approved drilling program – contact Dustin Doucet
- 24 hours prior to commencing operations to plug and abandon the well – contact Dan Jarvis

**Contact Information:**

The following are Division of Oil, Gas and Mining contacts and their telephone numbers (please leave a voicemail message if the person is not available to take the call):

- Carol Daniels 801-538-5284 - office
- Dustin Doucet 801-538-5281 - office  
801-733-0983 - after office hours
- Dan Jarvis 801-538-5338 - office  
801-942-0871 - after office hours

**Reporting Requirements:**

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) – due within 5 days of spudding the well
- Monthly Status Report (Form 9) – due by 5th day of the following calendar month
- Requests to Change Plans (Form 9) – due prior to implementation
- Written Notice of Emergency Changes (Form 9) – due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) – due prior to implementation
- Report of Water Encountered (Form 7) – due within 30 days after completion
- Well Completion Report (Form 8) – due within 30 days after completion or plugging

**Approved By:**



Gil Hunt  
Associate Director, Oil & Gas

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> UO 1207A
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> KERR-MCGEE OIL & GAS ONSHORE, L.P.		<b>7. UNIT or CA AGREEMENT NAME:</b> NATURAL BUTTES
<b>3. ADDRESS OF OPERATOR:</b> P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		<b>8. WELL NAME and NUMBER:</b> NBU 922-31J2S
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 2552 FSL 1420 FWL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NESW Section: 31 Township: 09.0S Range: 22.0E Meridian: S		<b>9. API NUMBER:</b> 43047504170000
<b>PHONE NUMBER:</b> 720 929-6007 Ext		<b>9. FIELD and POOL or WILDCAT:</b> NATURAL BUTTES
<b>COUNTY:</b> UINTAH		<b>STATE:</b> UTAH

**11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA**

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER:
<input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:			
<input checked="" type="checkbox"/> <b>SPUD REPORT</b> Date of Spud: 10/7/2009			
<input type="checkbox"/> <b>DRILLING REPORT</b> Report Date:			

**12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.**  
 MIRU PETE MARTIN BUCKET RIG. DRILLED 20" CONDUCTOR HOLE TO 40'.  
 RAN 14" 36.7# SCHEDULE 10 PIPE. CMT W/28 SX READY MIX. SPUD WELL LOCATION ON 10/07/2009 AT 13:30 HRS.

Accepted by the

Utah Division of

Oil, Gas and Mining

FOR RECORD ONLY

October 12, 2009

<b>NAME (PLEASE PRINT)</b> Andy Lytle	<b>PHONE NUMBER</b> 720 929-6100	<b>TITLE</b> Regulatory Analyst
<b>SIGNATURE</b> N/A	<b>DATE</b> 10/8/2009	

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> UO 1207A
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> KERR-MCGEE OIL & GAS ONSHORE, L.P.		<b>7. UNIT or CA AGREEMENT NAME:</b> NATURAL BUTTES
<b>3. ADDRESS OF OPERATOR:</b> P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		<b>8. WELL NAME and NUMBER:</b> NBU 922-31J2S
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 2552 FSL 1420 FWL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NESW Section: 31 Township: 09.0S Range: 22.0E Meridian: S		<b>9. API NUMBER:</b> 43047504170000
<b>PHONE NUMBER:</b> 720 929-6007 Ext		<b>9. FIELD and POOL or WILDCAT:</b> NATURAL BUTTES
<b>COUNTY:</b> UTAH		<b>STATE:</b> UTAH
<b>11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</b>		
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>	
<input type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start:	<input type="checkbox"/> <b>ACIDIZE</b>	
<input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:	<input type="checkbox"/> <b>ALTER CASING</b>	
<input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:	<input type="checkbox"/> <b>CASING REPAIR</b>	
<input checked="" type="checkbox"/> <b>DRILLING REPORT</b> Report Date: 10/17/2009	<input type="checkbox"/> <b>CHANGE TO PREVIOUS PLANS</b>	
	<input type="checkbox"/> <b>CHANGE TUBING</b>	
	<input type="checkbox"/> <b>CHANGE WELL STATUS</b>	
	<input type="checkbox"/> <b>COMMINGLE PRODUCING FORMATIONS</b>	
	<input type="checkbox"/> <b>DEEPEN</b>	
	<input type="checkbox"/> <b>FRACTURE TREAT</b>	
	<input type="checkbox"/> <b>OPERATOR CHANGE</b>	
	<input type="checkbox"/> <b>PLUG AND ABANDON</b>	
	<input type="checkbox"/> <b>PRODUCTION START OR RESUME</b>	
	<input type="checkbox"/> <b>RECLAMATION OF WELL SITE</b>	
	<input type="checkbox"/> <b>REPERFORATE CURRENT FORMATION</b>	
	<input type="checkbox"/> <b>SIDETRACK TO REPAIR WELL</b>	
	<input type="checkbox"/> <b>TUBING REPAIR</b>	
	<input type="checkbox"/> <b>VENT OR FLARE</b>	
	<input type="checkbox"/> <b>WATER SHUTOFF</b>	
	<input type="checkbox"/> <b>SI TA STATUS EXTENSION</b>	
	<input type="checkbox"/> <b>WILDCAT WELL DETERMINATION</b>	
	<input type="checkbox"/> <b>OTHER</b>	
	OTHER:	
<b>12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.</b> MIRU PROPETRO AIR RIG ON 10/16/2009. DRILLED 12-1/4" SURFACE HOLE TO 2,230'. RAN 9-5/8" 40# J-55 SURFACE CSG. PUMP 20 BBLS OF GEL WATER. LEAD CMT W/220 SX CLASS G HI FILL @ 11.0 PPG, 3.82 YIELD. CIRC THROUGHOUT. TAILED CMT W/200 SX CLASS G PREM LITE @ 15.8 PPG, 1.15 YIELD. DROP PLUG ON FLY, DISPLACE W/159.6 BBLS OF H2O. PRESSURE 400, BUMP PLUG 1000 PSI. CHECK FLOAT. FLOAT HELD. 20 BBLS LEAD CMT TO PIT. CEMENT FELL. PUMP TOP OUT W/100 SX CLASS G PREM LITE @ 15.8 PPG, 1.15 YIELD DOWN 1" DISPLACE OUT LEAD CEMENT. CMT FELL. WAIT 2 HRS AND PUMP SECOND TOP OUT W/100 SX SAME CEMENT DOWN BACK SIDE. 2 BBLS OF CMT TO SURFACE AND STAYED. WORT.		
<b>NAME (PLEASE PRINT)</b> Andy Lytle	<b>PHONE NUMBER</b> 720 929-6100	<b>TITLE</b> Regulatory Analyst
<b>SIGNATURE</b> N/A		<b>DATE</b> 10/19/2009



<div>STATE OF UTAH</div> <div>DEPARTMENT OF NATURAL RESOURCES</div> <div>DIVISION OF OIL, GAS, AND MINING</div>		<div>FORM 9</div> <div>5.LEASE DESIGNATION AND SERIAL NUMBER: UO 1207A</div>	
<div>SUNDRY NOTICES AND REPORTS ON WELLS</div> <div>Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.</div>		<div>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</div> <div>7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES</div>	
<div>1. TYPE OF WELL</div> <div>Gas Well</div>		<div>8. WELL NAME and NUMBER:</div> <div>NBU 922-31J2S</div>	
<div>2. NAME OF OPERATOR:</div> <div>KERR-MCGEE OIL &amp; GAS ONSHORE, L.P.</div>		<div>9. API NUMBER:</div> <div>43047504170000</div>	
<div>3. ADDRESS OF OPERATOR:</div> <div>P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779</div>		<div>PHONE NUMBER:</div> <div>720 929-6007 Ext</div>	<div>9. FIELD and POOL or WILDCAT:</div> <div>NATURAL BUTTES</div>
<div>4. LOCATION OF WELL</div> <div>FOOTAGES AT SURFACE: 2552 FSL 1420 FWL</div> <div>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NESW Section: 31 Township: 09.0S Range: 22.0E Meridian: S</div>		<div>COUNTY:</div> <div>UINTAH</div>	
		<div>STATE:</div> <div>UTAH</div>	
<div>11.</div> <div>CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</div>			
<div>TYPE OF SUBMISSION</div>		<div>TYPE OF ACTION</div>	
<div><input type="checkbox"/> NOTICE OF INTENT</div> <div>Approximate date work will start:</div> <div><input type="checkbox"/> SUBSEQUENT REPORT</div> <div>Date of Work Completion:</div> <div><input type="checkbox"/> SPUD REPORT</div> <div>Date of Spud:</div> <div><input checked="" type="checkbox"/> DRILLING REPORT</div> <div>Report Date:</div> <div>12/5/2009</div>		<div><input type="checkbox"/> ACIDIZE</div> <div><input type="checkbox"/> CHANGE TO PREVIOUS PLANS</div> <div><input type="checkbox"/> CHANGE WELL STATUS</div> <div><input type="checkbox"/> DEEPEN</div> <div><input type="checkbox"/> OPERATOR CHANGE</div> <div><input type="checkbox"/> PRODUCTION START OR RESUME</div> <div><input type="checkbox"/> REPERFORATE CURRENT FORMATION</div> <div><input type="checkbox"/> TUBING REPAIR</div> <div><input type="checkbox"/> WATER SHUTOFF</div> <div><input type="checkbox"/> WILDCAT WELL DETERMINATION</div> <div><input type="checkbox"/> ALTER CASING</div> <div><input type="checkbox"/> CHANGE TUBING</div> <div><input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS</div> <div><input type="checkbox"/> FRACTURE TREAT</div> <div><input type="checkbox"/> PLUG AND ABANDON</div> <div><input type="checkbox"/> RECLAMATION OF WELL SITE</div> <div><input type="checkbox"/> SIDETRACK TO REPAIR WELL</div> <div><input type="checkbox"/> VENT OR FLARE</div> <div><input type="checkbox"/> SI TA STATUS EXTENSION</div> <div><input type="checkbox"/> OTHER</div> <div><input type="checkbox"/> CASING REPAIR</div> <div><input type="checkbox"/> CHANGE WELL NAME</div> <div><input type="checkbox"/> CONVERT WELL TYPE</div> <div><input type="checkbox"/> NEW CONSTRUCTION</div> <div><input type="checkbox"/> PLUG BACK</div> <div><input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION</div> <div><input type="checkbox"/> TEMPORARY ABANDON</div> <div><input type="checkbox"/> WATER DISPOSAL</div> <div><input type="checkbox"/> APD EXTENSION</div> <div>OTHER:</div>	
<div>12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.</div> <div> <div> <div>FINISHED DRILLING FROM 2230' TO 9421' ON 12/2/2009. RAN 4-1/2" 11.6# I-80 PRODUCTION CSG. RIG UP EQUIPMENT. TEST LINES 8000 PSI &amp; PUMP 35 BBL SPACER. LEAD CMT W/675 SX CLASS G PREM LITE @ 13.2 PPG, 1.6 YIELD. TAILED CMT W/1275 SX CLASS G 50/50 POZ MIX @ 14.3 PPG, 1.2 YIELD. DISPLACE W/144.5 BBLS WATER. BUMP PLUG, FLOATS HELD 1.5 BBLS BACK TO TRUCK, FINAL LIFT PSI 2600, 30 BBLS TO PIT. RELEASE ENSIGN 146 RIG ON 12/6/2009 AT 06:00 HRS.</div> <div> <div>Accepted by the</div> <div>Utah Division of</div> <div>Oil, Gas and Mining</div> <div>FOR RECORD ONLY</div> <div>December 07, 2009</div> </div> </div> </div>			
<div>NAME (PLEASE PRINT)</div> <div>Andy Lytle</div>		<div>PHONE NUMBER</div> <div>720 929-6100</div>	<div>TITLE</div> <div>Regulatory Analyst</div>
<div>SIGNATURE</div> <div>N/A</div>		<div>DATE</div> <div>12/7/2009</div>	

<div>STATE OF UTAH<div>DEPARTMENT OF NATURAL RESOURCES</div>DIVISION OF OIL, GAS, AND MINING</div>		<div>FORM 9</div> <div>5.LEASE DESIGNATION AND SERIAL NUMBER: UO 1207A</div>	
<div>SUNDRY NOTICES AND REPORTS ON WELLS</div> <div>Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.</div>		<div>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</div> <div>7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES</div>	
<div>1. TYPE OF WELL Gas Well</div>		<div>8. WELL NAME and NUMBER: NBU 922-31J2S</div>	
<div>2. NAME OF OPERATOR: KERR-MCGEE OIL &amp; GAS ONSHORE, L.P.</div>		<div>9. API NUMBER: 43047504170000</div>	
<div>3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779</div>		<div>PHONE NUMBER: 720 929-6007 Ext</div>	
<div>4. LOCATION OF WELL FOOTAGES AT SURFACE: 2552 FSL 1420 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NESW Section: 31 Township: 09.0S Range: 22.0E Meridian: S</div>		<div>9. FIELD and POOL or WILDCAT: NATURAL BUTTES</div> <div>COUNTY: UINTAH</div> <div>STATE: UTAH</div>	
<div>11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</div>			
<div>TYPE OF SUBMISSION</div>		<div>TYPE OF ACTION</div>	
<div><input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:</div> <div><input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:</div> <div><input type="checkbox"/> SPUD REPORT Date of Spud:</div> <div><input checked="" type="checkbox"/> DRILLING REPORT Report Date: 8/18/2010</div>		<div><input type="checkbox"/> ACIDIZE</div> <div><input type="checkbox"/> CHANGE TO PREVIOUS PLANS</div> <div><input type="checkbox"/> CHANGE WELL STATUS</div> <div><input type="checkbox"/> DEEPEN</div> <div><input type="checkbox"/> OPERATOR CHANGE</div> <div><input checked="" type="checkbox"/> PRODUCTION START OR RESUME</div> <div><input type="checkbox"/> REPERFORATE CURRENT FORMATION</div> <div><input type="checkbox"/> TUBING REPAIR</div> <div><input type="checkbox"/> WATER SHUTOFF</div> <div><input type="checkbox"/> WILDCAT WELL DETERMINATION</div> <div><input type="checkbox"/> ALTER CASING</div> <div><input type="checkbox"/> CHANGE TUBING</div> <div><input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS</div> <div><input type="checkbox"/> FRACTURE TREAT</div> <div><input type="checkbox"/> PLUG AND ABANDON</div> <div><input type="checkbox"/> RECLAMATION OF WELL SITE</div> <div><input type="checkbox"/> SIDETRACK TO REPAIR WELL</div> <div><input type="checkbox"/> VENT OR FLARE</div> <div><input type="checkbox"/> SI TA STATUS EXTENSION</div> <div><input type="checkbox"/> OTHER</div> <div><input type="checkbox"/> CASING REPAIR</div> <div><input type="checkbox"/> CHANGE WELL NAME</div> <div><input type="checkbox"/> CONVERT WELL TYPE</div> <div><input type="checkbox"/> NEW CONSTRUCTION</div> <div><input type="checkbox"/> PLUG BACK</div> <div><input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION</div> <div><input type="checkbox"/> TEMPORARY ABANDON</div> <div><input type="checkbox"/> WATER DISPOSAL</div> <div><input type="checkbox"/> APD EXTENSION</div> <div>OTHER: <input type="text"/></div>	
<div>12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.</div> <div>THE SUBJECT WELL WAS PLACED ON PRODUCTION ON AUGUST 18, 2010 AT 11:50 A.M. THE CHRONOLOGICAL WELL HISTORY WILL BE SUBMITTED WITH THE WELL COMPLETION REPORT.</div> <div>Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY August 19, 2010</div>			
<div>NAME (PLEASE PRINT) Gina Becker</div>		<div>PHONE NUMBER 720 929-6086</div>	
<div>SIGNATURE N/A</div>		<div>TITLE Regulatory Analyst II</div> <div>DATE 8/19/2010</div>	

**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

**COPY**

AMENDED REPORT ☐ FORM 8  
(highlight changes)

**WELL COMPLETION OR RECOMPLETION REPORT AND LOG**

1a. TYPE OF WELL: OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> DRY <input type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: <b>UO 1207A</b>
b. TYPE OF WORK: NEW WELL <input checked="" type="checkbox"/> HORIZ. LATS. <input type="checkbox"/> DEEP-EN <input type="checkbox"/> RE-ENTRY <input type="checkbox"/> DIFF. RESVR. <input type="checkbox"/> OTHER _____		6. IF INDIAN, ALLOTTEE OR TRIBE NAME _____
2. NAME OF OPERATOR: <b>KERR MCGEE OIL &amp; GAS ONSHORE, L.P.</b>		7. UNIT or CA AGREEMENT NAME <b>UTU63047A</b>
3. ADDRESS OF OPERATOR: <b>P.O.BOX 173779 CITY DENVER STATE CO ZIP 80217</b>		8. WELL NAME and NUMBER: <b>NBU 922-31J2S</b>
4. LOCATION OF WELL (FOOTAGES) AT SURFACE: <b>NESW 2552 FSL 1420 FWL S31,T9S,R22E</b> AT TOP PRODUCING INTERVAL REPORTED BELOW: <b>NWSE 1830 FSL 2247 FEL S31, T9S, R22E</b> AT TOTAL DEPTH: <b>NWSE 1806 FSL 2223 FEL S31, T9S, R22E</b>		9. API NUMBER: <b>4304750417</b>
10. FIELD AND POOL, OR WILDCAT <b>NATURAL BUTTES</b>		11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: <b>NESW 31 9S 22E S</b>
12. COUNTY <b>UINTAH</b>		13. STATE <b>UTAH</b>

14. DATE SPURRED: <b>10/7/2009</b>	15. DATE T.D. REACHED: <b>12/2/2009</b>	16. DATE COMPLETED: <b>8/18/2010</b>	ABANDONED <input type="checkbox"/> READY TO PRODUCE <input checked="" type="checkbox"/>	17. ELEVATIONS (DF, RKB, RT, GL): <b>4840 GL</b>
18. TOTAL DEPTH: MD <b>9,421</b> TVD <b>9,182</b>	19. PLUG BACK T.D.: MD <b>9,389</b> TVD <b>9,149</b>	20. IF MULTIPLE COMPLETIONS, HOW MANY? *		21. DEPTH BRIDGE MD PLUG SET: TVD

22. TYPE ELECTRIC AND OTHER MECHANICAL LOGS RUN (Submit copy of each) <b>TRIPLE COMBO-GR/CBL</b>	23. WAS WELL CORED? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit analysis) WAS DST RUN? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit report) DIRECTIONAL SURVEY? NO <input type="checkbox"/> YES <input checked="" type="checkbox"/> (Submit copy)
---	---

**24. CASING AND LINER RECORD (Report all strings set in well)**

HOLE SIZE	SIZE/GRADE	WEIGHT (#/ft.)	TOP (MD)	BOTTOM (MD)	STAGE CEMENTER DEPTH	CEMENT TYPE & NO. OF SACKS	SLURRY VOLUME (BBL)	CEMENT TOP **	AMOUNT PULLED
20"	14" STL	36.7#		40		28			
12 1/4"	9 5/8" J-55	36#		2,206		620			
7 7/8"	4 1/2" I-80	11.6#		9,408		1,950			

**25. TUBING RECORD**

SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
2 3/8"	6,575							

26. PRODUCING INTERVALS					27. PERFORATION RECORD				
FORMATION NAME	TOP (MD)	BOTTOM (MD)	TOP (TVD)	BOTTOM (TVD)	INTERVAL (Top/Bot - MD)	SIZE	NO. HOLES	PERFORATION STATUS	
(A) WASATCH	6,768	6,890			6,768 6,890	0.36	21	Open <input checked="" type="checkbox"/>	Squeezed <input type="checkbox"/>
(B) MESAVERDE	7,249	9,226			7,249 9,226	0.36	183	Open <input checked="" type="checkbox"/>	Squeezed <input type="checkbox"/>
(C)								Open <input type="checkbox"/>	Squeezed <input type="checkbox"/>
(D)								Open <input type="checkbox"/>	Squeezed <input type="checkbox"/>

**28. ACID, FRACTURE, TREATMENT, CEMENT SQUEEZE, ETC.**

DEPTH INTERVAL	AMOUNT AND TYPE OF MATERIAL
6768 - 9226	PUMP 11,861 BBLS SLICK H2O & 466,438 LBS 30/50 SAND

29. ENCLOSED ATTACHMENTS: <input type="checkbox"/> ELECTRICAL/MECHANICAL LOGS <input type="checkbox"/> GEOLOGIC REPORT <input type="checkbox"/> DST REPORT <input checked="" type="checkbox"/> DIRECTIONAL SURVEY <input type="checkbox"/> SUNDRY NOTICE FOR PLUGGING AND CEMENT VERIFICATION <input type="checkbox"/> CORE ANALYSIS <input type="checkbox"/> OTHER: _____	30. WELL STATUS: <div style="font-size: 2em; font-weight: bold; text-align: center;">PROD</div>
--	--

**RECEIVED**

SEP 27 2010

## 31. INITIAL PRODUCTION

## INTERVAL A (As shown in item #26)

DATE FIRST PRODUCED: 8/18/2010		TEST DATE: 8/22/2010		HOURS TESTED: 24		TEST PRODUCTION RATES: →		OIL – BBL: 0		GAS – MCF: 2,289		WATER – BBL: 360		PROD. METHOD: FLOWING	
CHOKE SIZE: 20/64	TBG. PRESS. 2,000	CSG. PRESS. 2,950	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →		OIL – BBL: 0		GAS – MCF: 2,289		WATER – BBL: 360		INTERVAL STATUS: PROD	

## INTERVAL B (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

## INTERVAL C (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

## INTERVAL D (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

## 32. DISPOSITION OF GAS (Sold, Used for Fuel, Vented, Etc.)

## 33. SUMMARY OF POROUS ZONES (include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

## 34. FORMATION (Log) MARKERS:

Formation	Top (MD)	Bottom (MD)	Descriptions, Contents, etc.	Name	Top (Measured Depth)
GREEN RIVER	1,266				
BIRD'S NEST	1,525				
MAHOGANY	1,993				
WASATCH	4,566	7,233			
MESAVERDE	7,233	9,421	TD		

## 35. ADDITIONAL REMARKS (include plugging procedure)

ATTACHED IS THE CHRONOLOGICAL WELL HISTORY AND FINAL SURVEY.

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.

NAME (PLEASE PRINT) ANDREW LYTLE

TITLE REGULATORY ANALYST

SIGNATURE 

DATE 9/23/2010

This report must be submitted within 30 days of

- completing or plugging a new well
- reentering a previously plugged and abandoned well
- drilling horizontal laterals from an existing well bore
- significantly deepening an existing well bore below the previous bottom-hole depth
- recompleting to a different producing formation
- drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests

\* ITEM 20: Show the number of completions if production is measured separately from two or more formations.

\*\* ITEM 24: Cement Top – Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

Send to: Utah Division of Oil, Gas and Mining  
1594 West North Temple, Suite 1210  
Box 145801  
Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940

**US ROCKIES REGION**  
**Operation Summary Report**

Well: NBU 922-31J2S    PURPLE			Spud Conductor: 10/7/2009				Spud Date: 10/16/2009			
Project: UTAH-UINTAH				Site: NBU 922-31K PAD				Rig Name No: ENSIGN 146/146, PROPETRO/		
Event: DRILLING				Start Date: 9/28/2009				End Date: 12/6/2009		
Active Datum: RKB @4,855.01ft (above Mean Sea Level)				UWI: NE/SW/0/9/S/22/E/31/0/0/26/PM/S/2,611.00/E/0/1,837.00/0/0						
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation		
10/16/2009	0:00 - 2:00	2.00	MIRU	01	B	P		DRESS CONDUCTOR, INSTALL AIR BOWL AND BOWIE LINE, INSTALL AIR COMPRESSOR AND AIR BOOSTER, RIG UP PUMPS, BUILD DITCH.P/U AIR HAMMER.		
	2:00 - 4:00	2.00	DRLSUR	02	A	P		AIR SPUD 10/16/2009 02:00. AIR HAMMER 44'-180'. NO CROSS COMMUNICATION W/ OTHER WELLS ON PAD.		
	4:00 - 6:00	2.00	DRLSUR	06	A	P		LD AIR HAMMER AND P/U HUNTING 2.12 DEG. BENT HOUSE MOTOR M/U DP 507 BIT W/ 2ND RUN. P/U DIRECTIONAL TOOLS AND SCRIBE.		
	6:00 - 0:00	18.00	DRLSUR	02	D	P		DRILL SLIDE 180'- 1640' (1460', 81'/HR) WOB 12-20K ROT 45, DH RPM 104, GPM 650, ON/OFF PSI 1600/1450, UP/DOWN/ROT 65/60/52. DRAG 5K.		
10/17/2009	0:00 - 11:30	11.50	DRLSUR	02	D	P		DRILL SLIDE 1640'-2230' (590',51'/HR) TD 10/17/2009 11:30 WOB 12-15K ROT 45, DH RPM 104, GPM 650, ON/OFF PSI 1650/1450, UP/DOWN/ROT 68/62/56. DRAG 6K. FULL CIRC THROUGH OUT JOB.		
	11:30 - 12:30	1.00	CSG	05	F	P		CIRC AND CONDITION HOLE, CLEAN HOLE W/ POLY SWEEPS. FULL CIRC THROUGHOUT.		
	12:30 - 15:00	2.50	CSG	06	D	P		HOLD SAFETY MEETING. LDDs, LAY DOWN DIRECTIONAL TOOLS. MOVE FLOAT.		
	15:00 - 19:00	4.00	CSG	12	C	P		RUN 51 JTS OF 9-5/8" 40#, J-55, LTC CSG. LAND CSG 2197' KB, (TVD 2123') BAFFLE PLATE RAN IN TOP OF FIRST JT. LANDED @ 2154' KB. CSG ID OF 8.835, BURST 3750. FILL PIPE 500' AND 1500'. RUN 200' OF 1" DOWN BACK SIDE.		
	19:00 - 19:30	0.50	RDMO	01	A	P		RIG DOWN RIG AND MOVE RIG OUT OF WAY FOR CEMENTERS. MOVE RIG BACK ONTO NBU 922-F3S. RELEASE RIG 10/17/2009 19:30.		
	19:30 - 0:00	4.50	CSG	12	E	P		RIG UP CEMENTERS.,HOLD SAFETY MEETING.RIG UP CEMENTERS, INSPECT TRUCK FOR VISABLE PROBLEMS. HOLD SAFETY MEETING W PROPETRO CEMENTERS, START FLUSH 140 BBLS OF H2O, PUMP 20 BBLS OF GEL WATER, PUMP 220SX (150 BBLS) OF 11# 3.82 YD 23 GAL/SK HI FILL LEAD CEMENT. CIRC THROUGH OUT. PUMP 200 SX (41 BBLS) OF 15.8#, 1.15 YD, 5 GAL/SK PREMIUM TAIL 2% CALC. DROP PLUG ON FLY, DISPLACE W/ 159.6 BBLS OF H2O, LIFT PRESSURE 400, BUMP PLUG 1000 PSI, CHECK FLOAT. FLOAT HELD.20 BBLS OF LEAD CEMENT TO PIT. CEMENT FELL. PUMP SAME TAIL CEMENT (100 SX) 20 BBLS DOWN 1" DISPLACE OUT LEAD CEMENT W/ 15.8# 4% CALC2 TAIL CEMENT. CEMENT FELL. WAIT 2 HRS PUMP 100 SX OF 15.8# 4% CALC2 TAIL CEMENT DOWN BACK SIDE. 2 BBLS OF CEMENT TO SURFACE AND STAYED. RIG DOWN AND FLUSH CEMENTERS.		
11/23/2009	21:00 - 0:00	3.00	RDMO	01	E	P		SKID RIG 60' TO NBU 922-31J2S, R/DN BACKYARD - PREPARE TO MOVE UP BACKYARD RDRT		
11/24/2009	0:00 - 9:00	9.00	RDMO	01	E	P				
	9:00 - 14:00	5.00	MIRU	01	A	P		MOVE BACKYARD UP 30' - TRUCKS OFF LOCATION @ 14:00 HRS - ( WESTROC 2 R/UP TRUCKS)		
	14:00 - 18:00	4.00	MIRU	01	B	P		RURT		



**US ROCKIES REGION**  
**Operation Summary Report**

Well: NBU 922-31J2S	PURPLE	Spud Conductor: 10/7/2009	Spud Date: 10/16/2009
Project: UTAH-UINTAH	Site: NBU 922-31K PAD		Rig Name No: ENSIGN 146/146, PROPETRO/
Event: DRILLING	Start Date: 9/28/2009	End Date: 12/6/2009	
Active Datum: RKB @4,855.01ft (above Mean Sea Level)		UWI: NE/SW/0/9/S/22/E/31/0/0/26/PM/S/2,611.00/E/0/1,837.00/0/0	

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
11/25/2009	18:00 - 20:30	2.50	MAINT	08	B	P		INSTALL BLOCK GUIDES
	20:30 - 22:30	2.00	MAINT	09	A	P		SLIP & CUT DRILL LINE
	22:30 - 23:30	1.00	DRLPRO	14	A	P		N/UP BOPE
	23:30 - 0:00	0.50	DRLPRO	15	A	P		TEST BOPE - RAMS, CHOKE, CHOKE LINE, HCR, MANUALS, FLOOR VALVES, MANUAL IBOP 250 LOW 5000 HIGH, ANNULAR 250 LOW 2500 HIGH, CASING 1500
	0:00 - 5:00	5.00	DRLPRO	15	A	P		TEST BOPE - RAMS, CHOKE, CHOKE LINE, HCR, MANUALS, FLOOR VALVES, MANUAL IBOP 250 LOW 5000 HIGH, ANNULAR 250 LOW 2500 HIGH, CASING 1500 (FLANGE BETWEEN MUD CROSS & WEATHERFORD ADAPTER LEAKING)
	5:00 - 6:00	1.00	DRLPRO	08	A	Z		DRAWWORKS BRAKES WILL NOT RELEASE - MAIN AIR COMPRESSOR DOWN - AIR FREEZING
	6:00 - 7:30	1.50	DRLPRO	06	A	P		P/UP MM & BIT #1, P/UP DIRECTIONAL TOOLS, SCRIBE & ORIENT - RIH
	7:30 - 8:30	1.00	DRLPRO	06	A	P		TRIP 5 STDs IN HOLE - IT WAS NOTICED THAT IRON ROUGHNECK WAS NOT MAKING UP ALL THE WAY.
	8:30 - 11:00	2.50	DRLPRO	06	A	Z		TRIP OUT CHECK CONNECTIONS 3 THREE WERE LOOSE - CLEANED & INSPECTED IRON ROUGHNECK TORQUED UP - TRIP IN HOLE - INSTALLED CORROSION RING, ROTATING RUBBER - TAG CMT. @ 2199 FT.
	11:00 - 12:30	1.50	DRLPRO	02	F	P		DRILL CMT. FLOAT, SHOE & RAT HOLE - SHOE DEPTH 2208 FT.
	12:30 - 17:00	4.50	DRLPRO	02	C	P		DRILL & SLIDE F/ 2240 TO 2740 - 500 FT. 111 FPH, WOB 18, RPM 45, MMRPM 102, GPM 486, MW 8.5 VIS 26, SLIDES - 2328-2336 2373-2381 2419-2431 2464-2472 2509-2517 2555-2565 2600-2608 2645-2653 2691-2699
	17:00 - 17:30	0.50	DRLPRO	07	A	P		RIG SERVICE
	17:30 - 0:00	6.50	DRLPRO	02	C	P		DRILL & SLIDE F/ 2740 TO 3310 - 570 FT. 87.7 FPH, WOB 18, RPM 45, MMRPM 102, GPM 486, MW 8.5 VIS 26, SLIDES 2736-2746 2781-2793 2827-2837 2872-2880 2917-2925 2963-2970 3008-3014 3053-3058 3144-3153 3189-3195 3235-3242 3280-3290
11/26/2009	0:00 - 13:30	13.50	DRLPRO	02	C	P		DRILL & SLIDE F/ 3310 TO 4457 - 1147 FT. 85 FPH, WOB 18, RPM 45, MMRPM 102, GPM 486, MW 8.5, VIS 26 - SLIDES 3325-3337,3370-3381,3461-3469,3506-3513,3597-3605,3642-3649,3688-3695,3733-3743,3778-3793,3824-3839,3869-3879,3914-3929,3959-3969,4005-4015,4050-4060,4095-4110,4141-4153,4186-4204,4231-4243,4277-4289,4367-4382,4412-4427
	13:30 - 14:00	0.50	DRLPRO	07	A	P		RIG SERVICE
	14:00 - 14:30	0.50	DRLPRO	08	A	Z		CHANGED FUEL FILTERS IN #1 GEN
	14:30 - 0:00	9.50	DRLPRO	02	C	P		DRILL & SLIDE F/ 4457 TO 5315 - 858 FT. 90.3 FPH, WOB 18, RPM 45, MMRPM 102, GPM 486, MW 8.5 VIS 27 - SLIDES 4457-4472,4503-4518,4548-4560,4593-4603,4639-4649,4729-4744,4820-4830,5002-5010,5092-5100
	0:00 - 13:30	13.50	DRLPRO	02	C	P		DRILL & SLIDE F/ 5315 TO 6273 - 958 FT. 71 FPH., WOB 18, RPM 45, MMRPM 102, GPM 486, MW 8.8 VIS 36 - LOST RETURNS @ 5599 FT. MUDDUP & BROUGHT LCM % TO 4, BYPASS SHAKERS - SLIDES 5364-5373,5546-5553,5818-5830,5999-6011,6090-6102,6271-6286
11/27/2009	13:30 - 14:00	0.50	DRLPRO	07	A	P		RIG SERVICE

**US ROCKIES REGION**  
**Operation Summary Report**

Well: NBU 922-31J2S	PURPLE	Spud Conductor: 10/7/2009	Spud Date: 10/16/2009
Project: UTAH-UINTAH	Site: NBU 922-31K PAD	Rig Name No: ENSIGN 146/146, PROPETRO/	
Event: DRILLING	Start Date: 9/28/2009	End Date: 12/6/2009	
Active Datum: RKB @4,855.01ft (above Mean Sea Level)		UWI: NE/SW/0/9/S/22/E/31/0/0/26/PM/S/2,611.00/E/0/1,837.00/0/0	

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
11/28/2009	14:00 - 0:00	10.00	DRLPRO	02	C	P		DRILL & SLIDE F/ 6273 TO 6692 - 419 421 FPH, WOB 18, RPM 55, MMRPM 102, GPM 486, MW9.3 VIS 43 - SLIDES 6634-6646
	0:00 - 16:30	16.50	DRLPRO	02	C	P		DRILL & SLIDE F/ 6692 TO 7360 - 668 FT. 40 FPH, WOB 19, RPM 50, MMRPM 102, GPM 486, MW 9.7, VIS 45 - SLIDES 6815-6823 7178-7193 7268-7282 RIG SERVICE
	16:30 - 17:00	0.50	DRLPRO	07	A	P		
	17:00 - 0:00	7.00	DRLPRO	02	C	P		DRILL & SLIDE F/ 7360 TO 7591 - 231 FT. 33 FPH, WOB 20, RPM 45, MMRPM 102, GPM 486, MW 9.9 VIS 46
11/29/2009	0:00 - 2:30	2.50	DRLPRO	02	C	P		DRILL & SLIDE F/ 7591 TO 7645 - 54 FT. 21.6 FPH, WOB 21, RPM 50, MMRPM 102, GPM 486, CIRC. MIX UP A PILL
	2:30 - 3:00	0.50	DRLPRO	05	C	P		
	3:00 - 13:00	10.00	DRLPRO	06	A	P		PUMP 15 STDS OUT, PUMP PILL STRAGHT PULL OUT, PULL ROTATING HEAD, L/D MUD MOTOR & BIT - MOTOR LOCKED UP, BIT GRADE 1/3 P/U NEW BIT & MUD MOTOR SCRIBE, RIH - BREAK CIRC. @ 4000 FT. WASH & REAM 100 FT. FAN NEW BIT TO BTM.
	13:00 - 21:30	8.50	DRLPRO	06	A	P		DRILL F/ 7645 TO 7738 - 93 FT. 46.5 FPH, WOB 18, RPM 60, MMRPM 77, GPM 486
11/30/2009	21:30 - 23:30	2.00	DRLPRO	02	C	P		RIG SERVICE
	23:30 - 0:00	0.50	DRLPRO	07	A	P		
	0:00 - 8:00	8.00	DRLPRO	02	C	P		DRILL F/ 7738 TO 8270 - WOB 18, RPM 60, MMRPM 77, GPM 486, MW 10.4, VIS 43
	8:00 - 8:30	0.50	DRLPRO	08	B	Z		WORK ON MUD PUMPS - SUCTIONS PLUGGED
	8:30 - 15:00	6.50	DRLPRO	02	C	P		DRILL F/ 8270 TO 8635 - WOB 18, RPM 60, MMRPM 77, GPM 486, MW 11, VIS 46
	15:00 - 15:30	0.50	DRLPRO	07	A	P		RIG SERVICE
	15:30 - 22:00	6.50	DRLPRO	02	C	P		DRILL F/ 8635 TO 8780 - WOB 18, RPM 60, MMRPM 77, GPM 486, MW 11.6, VIS 46 - LOST RETURNS - 150 BBLS. - SLIDE F/ 8692-8722
	22:00 - 22:30	0.50	DRLPRO	05	A	X		CIRC. @ 60 SPM - TRANSFER MUD FOR UPRIGHT
12/1/2009	22:30 - 0:00	1.50	DRLPRO	02	C	P		DRILL F/ 8780 TO 8831 - WOB 18, RPM 60, MMRPM 77, GPM 486, MW 12.2 VIS 46
	0:00 - 0:00	24.00	DRLPRO	02	C	P		DRILL F/ 8831 TO 9360 - 529 FT. 22 FPH, WOB 21, RPM 60, MMRPM 77, GPM 486, MW 12.2, VIS 43
	0:00 - 4:30	4.50	DRLPRO	02	C	P		DRILL F/ 9360 TO 9421 61 FT. 13.5 FPH, WOB 17, RPM 45, MMRPM 77, GPM 486, MW 12.2, VIS 44 - LOST 800 TOTAL BBLS.
	4:30 - 6:00	1.50	DRLPRO	05	C	P		CIRC. BTMS UP - FLOW CHECK, WELL WAS FLOWING
12/2/2009	6:00 - 11:00	5.00	DRLPRO	05	A	P		CIRC. BRING MUD WT. UP TO 12.8
	11:00 - 12:00	1.00	DRLPRO	06	E	P		FLOW CHECK SMALL FLOW - WIPER TRIP TO 7500 FT.
	12:00 - 12:30	0.50	DRLPRO	08	B	Z		RETORQUE TOPDRIVE
	12:30 - 16:30	4.00	DRLPRO	06	E	P		WIPERTRIP TO 7500 FT.OBSERVED WELL DURING TRIP - RIH
12/3/2009	16:30 - 19:30	3.00	DRLPRO	05	B	P		CIRC. RAISE WT. TO 13.2
	19:30 - 0:00	4.50	DRLPRO	06	B	P		FLOW CHECK WELL NO FLOW - TRIP OUT FOR WIRELINE LOGS
	0:00 - 6:00	6.00	DRLPRO	06	B	P		T.O.H L/D DIRECTIONAL TOOLS, MOTOR, & BIT - WELL IS STATIC
	6:00 - 12:30	6.50	DRLPRO	11	D	P		HOLD SAFETY MEEETING W/ WEATHERFORD WIRELINE & RIG UP TO RUN OPEN HOLE LOGS - LOGGERS TD 9424 FT.
	12:30 - 16:30	4.00	DRLPRO	06	D	P		P/U BIT SUB & BIT RIH TO 4000 FT. BREAK CIRC.
	16:30 - 17:00	0.50	DRLPRO	05	A	P		CIRC. DISPLACE MUD
	17:00 - 19:30	2.50	DRLPRO	06	D	P		TRIP IN TO 7000 FT. - FILL PIPE, LOST RETURNS - 150 BBLS.

**US ROCKIES REGION**  
**Operation Summary Report**

Well: NBU 922-31J2S	PURPLE	Spud Conductor: 10/7/2009	Spud Date: 10/16/2009
Project: UTAH-UINTAH	Site: NBU 922-31K PAD		Rig Name No: ENSIGN 146/146, PROPETRO/
Event: DRILLING	Start Date: 9/28/2009	End Date: 12/6/2009	
Active Datum: RKB @4,855.01ft (above Mean Sea Level)		UWI: NE/SW/0/9/S/22/E/31/0/0/26/PM/S/2,611.00/E/0/1,837.00/0/0	

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
12/4/2009	19:30 - 0:00	4.50	DRLPRO	22	G	X		TRANSFER PREMIX INTO ACTIVE 10.4 MW, 39 VIS, INCREASE TO 12.2, 44+ 25-30% LCM
	0:00 - 1:00	1.00	DRLPRO	06	K	X		PULL 10 STDS TO 6400 FT.
	1:00 - 1:30	0.50	DRLPRO	05	G	X		PUMP WITH NO RETURNS - 25% LCM
	1:30 - 2:30	1.00	DRLPRO	06	K	X		PULL 10 STDS. TO 5300 FT.
	2:30 - 5:00	2.50	DRLPRO	05	G	X		BUILD VOL. & MIX LCM CONTENT TO 30% VIS 40 MW 10.1 - GOT RETURNS - DISPLACE HEAVY MUD FROM HOLE.
	5:00 - 10:30	5.50	DRLPRO	06	A	P		STAGE IN HOLE CIRC. EVERY 5 STDS. & CIRC. BTMS UP EVERY 10 STDS.
	10:30 - 11:00	0.50	DRLPRO	03	E	P		WASH & REAM 100 FT. TO BTM.
	11:00 - 14:30	3.50	DRLPRO	05	A	P		CIRC. GAS FROM WELL 15 FT. FLARE & GET MUD EQUALIZED - MW 11.9 VIS 44 LCM 28%
	14:30 - 15:00	0.50	DRLPRO	23	B	P		FLOW CHECK WELL - STOPPED FLOWING AFTER 15 MINS
	15:00 - 17:00	2.00	DRLPRO	05	C	P		CIRC. OBSERVE BTMS. UP AFTER FLOW CHECK 5 FT. FLARE - RAISE MW TO 12.2
12/5/2009	17:00 - 23:00	6.00	DRLPRO	06	D	P		L.D.D.P - PUMPED 1 STD OFF BTM. STRAIGHT PULLED FROM THERE
	23:00 - 23:30	0.50	DRLPRO	08	A	Z		REPAIR PIPE SKATE
	23:30 - 0:00	0.50	DRLPRO	06	D	P		L.D.D.P
	0:00 - 1:00	1.00	DRLPRO	06	D	P		L.D.D.P
	1:00 - 2:00	1.00	DRLPRO	08	B	Z		BREAK TIGHT CONNECTION
	2:00 - 3:00	1.00	DRLPRO	06	D	P		L.D.D.P
	3:00 - 4:00	1.00	DRLPRO	08	B	Z		BREAK TIGHT CONNECTION
	4:00 - 5:00	1.00	DRLPRO	06	D	P		L.D.D.P
	5:00 - 5:30	0.50	DRLPRO	08	B	Z		BREAK TIGHT CONNECTION
	5:30 - 8:00	2.50	DRLPRO	06	D	P		L.D.D.P & BHA
12/6/2009	8:00 - 18:00	10.00	DRLPRO	12	C	P		HOLD SAFETY MEETING W/ FRANKS CASING, RIG UP & RUN 224 JTS. 4 1/2, 11.6# I-80, BTC CASING, LAND CASING IN HEAD, SHOE SET @ 9408 FT. MD, 9170 FT. TVD
	18:00 - 18:30	0.50	DRLPRO	05	D	P		CIRC. THROUGH CASING - TOOK 30 BBL. KICK, SHUT IN CASING PSI 211
	18:30 - 19:30	1.00	DRLPRO	08	C	Z		THAW OUT CHOKE LINE
	19:30 - 21:00	1.50	DRLPRO	22	C	X		CIRC. KICK FROM WELL @ 60 SPM,
	21:00 - 0:00	3.00	DRLPRO	12	E	P		HELD SAFETY MEETING W/ HALLIBURTON - RIG UP EQUIPMENT, TEST LINES 8000 PSI, & PUMP 35 BBL. SPACER, LEAD W/ 196 BBLs. 675 SKS. 13.2 1.63 YEILD 8.3 GPS, TAIL W/ 286 BBLs. 1275 SKS. 50/50 POZ @ 14.3, 1.26 YEILD 5.41 GPS, DISPLACE W/ 144.5 BBLs. WATER, BUMPED PLUG, FLOATS HELD 1.5 BBL. BACK TO TRUCK, FINAL LIFT PSI 2600, 30 BBLs. TO PIT
	0:00 - 1:00	1.00	DRLPRO	12	B	P		RIG DOWN HALLIBURTON
	1:00 - 1:30	0.50	DRLPRO	24	A	P		SET PACK OFF ASSEMBLY
	1:30 - 6:00	4.50	DRLPRO	14	A	P		NIPPLE DOWN BOP, CLEAN MUD TANKS, RELEASE RIG @ 06:00 HRS. 12/6/2009

## US ROCKIES REGION

## Operation Summary Report

Well: NBU 922-31J2S		PURPLE		Spud Conductor: 10/7/2009			Spud Date: 10/16/2009			
Project: UTAH-UINTAH				Site: NBU 922-31K PAD				Rig Name No: LEED 733/733		
Event: COMPLETION				Start Date: 8/6/2010			End Date: 8/17/2010			
Active Datum: RKB @4,855.01ft (above Mean Sea Level)				UWI: NE/SW/0/9/S/22/E/31/0/0/26/PM/S/2,611.00/E/0/1,837.00/0/0						
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation		
8/9/2010	7:00 - 7:15	0.25	COMP	48		P		HSM. WL SAFETY & FRAC SAFETY.		

US ROCKIES REGION  
Operation Summary Report

Well: NBU 922-31J2S	PURPLE	Spud Conductor: 10/7/2009	Spud Date: 10/16/2009
Project: UTAH-UINTAH	Site: NBU 922-31K PAD		Rig Name No: LEED 733/733
Event: COMPLETION	Start Date: 8/6/2010		End Date: 8/17/2010
Active Datum: RKB @4,855.01ft (above Mean Sea Level)		UWI: NE/SW/0/9/S/22/E/31/0/0/26/PM/S/2,611.00/E/0/1,837.00/0/0	

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
	7:15 - 18:00	10.75	COMP	36	B	P		<p>OPEN WELL 0#</p> <p>PERF STG 1)PU 3 1/8 EXP GUN, 23 GM, .36 HOLE SIZE. 120 DEG PHASING. RIH PERF F/ 9043'-44', 3 SPF, 3 HOLES.</p> <p>9105'-06', 3 SPF, 3 HOLES.</p> <p>9180'-82', 3 SPF, 6 HOLES.</p> <p>9198'-99', 3 SPF, 3 HOLES.</p> <p>9209'-10', 3 SPF, 3 HOLES.</p> <p>9224'-26', 3 SPF, 6 HOLES. 24 HOLES.</p> <p>POOH. X-OVER FOR HALLIBURTON FRAC CREW.</p> <p>FRAC STG 1)WHP 0 PSI, BRK 4239 PSI @ 4.3 BPM. ISIP 2754 PSI, FG .74.</p> <p>PUMP 100 BBLs @ 49.3 BPM @ 5430 PSI = 100% HOLES OPEN.</p> <p>ISIP 2904 PSI, FG .76, NPI 150 PSI.</p> <p>MP 6793 PSI, MR 53.6 BPM, AP 5332 PSI, AR 49.6 BPM,</p> <p>PMP 1557 BBLs SW &amp; 55,124 LBS OF 30/50 SND &amp; 5,000 LBS OF 20/40 SLC SND. TOTAL PROP 60,124 LBS, SWI, X-OVER FOR WL.</p> <p>PERF STG 2)PU 4 1/2 8K HAL CBP &amp; 3 1/8 EXP GUN, 23 GM, .36 HOLE SIZE. 120 DEG PHASING. RIH SET CBP @ 8974' P/U PERF F/ 8791'-93', 3 SPF, 6 HOLES.</p> <p>8821'-22', 3 SPF, 3 HOLES.</p> <p>8890'-92', 3 SPF, 6 HOLES.</p> <p>8942'-44', 3 SPF, 6 HOLES. 21 HOLES.</p> <p>POOH, X-OVER FOR FRAC CREW.</p> <p>FRAC STG 2)WHP 1640 PSI, BRK 3590 PSI @ 4.9 BPM. ISIP 2598 PSI, FG .73.</p> <p>PUMP 100 BBLs @ 50.1 BPM @ 5444 PSI = 100% HOLES OPEN.</p> <p>ISIP 2888 PSI, FG .77, NPI 290 PSI.</p> <p>MP 5673 PSI, MR 50.2 BPM, AP 5102 PSI, AR 50 BPM,</p> <p>PMP 890 BBLs SW &amp; 28,648 LBS OF 30/50 SND &amp; 5,000 LBS OF 20/40 SLC SND. TOTAL PROP 33,648 LBS, SWI, X-OVER FOR WL.</p> <p>PERF STG 3)PU 4 1/2 8K HAL CBP &amp; 3 1/8 EXP GUN, 23 GM, .36 HOLE SIZE. 120 DEG PHASING. RIH SET CBP @ 8726' P/U PERF F/ 8561'-63', 3 SPF, 6 HOLES.</p> <p>8580'-81', 3 SPF, 3 HOLES.</p> <p>8605'-07', 3 SPF, 6 HOLES.</p> <p>8668'-70', 3 SPF, 6 HOLES.</p> <p>8695'-96', 3 SPF, 3 HOLES. 24 HOLES.</p> <p>POOH, X-OVER FOR FRAC CREW.</p> <p>FRAC STG 3)WHP 1229 PSI, BRK 4428 PSI @ 5.2 BPM. ISIP 2800 PSI, FG .77.</p> <p>PUMP 100 BBLs @ 41.6 BPM @ 5794 PSI = 71% HOLES OPEN.</p> <p>ISIP 2561 PSI, FG .74, NPI 395 PSI.</p> <p>MP 6661 PSI, MR 51.4 BPM, AP 5265 PSI, AR 49.8 BPM,</p> <p>PMP 1590 BBLs SW &amp; 60,667 LBS OF 30/50 SND &amp; 5,000 LBS OF 20/40 SLC SND. TOTAL PROP 65,669 LBS, SWI, X-OVER FOR WL.</p> <p>PERF STG 4)PU 4 1/2 8K HAL CBP &amp; 3 1/8 EXP GUN, 23 GM, .36 HOLE SIZE. 120 DEG PHASING.</p>

US ROCKIES REGION  
**Operation Summary Report**

Well: NBU 922-31J2S	PURPLE	Spud Conductor: 10/7/2009	Spud Date: 10/16/2009
Project: UTAH-UINTAH	Site: NBU 922-31K PAD		Rig Name No: LEED 733/733
Event: COMPLETION	Start Date: 8/6/2010		End Date: 8/17/2010
Active Datum: RKB @4,855.01ft (above Mean Sea Level)		UWI: NE/SW/0/9/S/22/E/31/0/0/26/PM/S/2,611.00/E/0/1,837.00/0/0	

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
								<p>RIH SET CBP @ 8533' P/U PERF F/ 8362'-64', 3 SPF, 6 HOLES. 8426'-28', 3 SPF, 6 HOLES. 8470'-71', 3 SPF, 3 HOLES. 8501'-03', 3 SPF, 6 HOLES. 21 HOLES. POOH, X-OVER FOR FRAC CREW.</p> <p>FRAC STG 4)WHP 2032 PSI, BRK 4428 PSI @ 5.2 BPM. ISIP 2800 PSI, FG .77. PUMP 100 BBLs @ 41.6 BPM @ 5794 PSI = 81% HOLES OPEN. ISIP 2362 PSI, FG .72, NPI 438 PSI. MP 7010 PSI, MR 50.1 BPM, AP 5615 PSI, AR 46.8 BPM, PMP 716 BBLs SW &amp; 25,856 LBS OF 30/50 SND &amp; 5,000 LBS OF 20/40 SLC SND. TOTAL PROP 30,856 LBS, SWI, X-OVER FOR WL.</p> <p>PERF STG 5)PU 4 1/2 8K HAL CBP &amp; 3 1/8 EXP GUN, 23 GM, .36 HOLE SIZE. 120 DEG PHASING. RIH SET CBP @ 8327' P/U PERF F/ 8059'-60', 3 SPF, 3 HOLES. 8079'-80', 3 SPF, 3 HOLES. 8109'-10', 3 SPF, 3 HOLES. 8174'-75', 3 SPF, 3 HOLES. 8197'-98', 3 SPF, 3 HOLES. 8221'-22', 3 SPF, 3 HOLES. 8264'-65', 3 SPF, 3 HOLES. 8296'-97', 3 SPF, 3 HOLES. 24 HOLES. POOH, SWIFN.</p>



**US ROCKIES REGION**  
**Operation Summary Report**

Well: NBU 922-31J2S	PURPLE	Spud Conductor: 10/7/2009	Spud Date: 10/16/2009
Project: UTAH-UINTAH	Site: NBU 922-31K PAD		Rig Name No: LEED 733/733
Event: COMPLETION	Start Date: 8/6/2010		End Date: 8/17/2010
Active Datum: RKB @4,855.01ft (above Mean Sea Level)		UWI: NE/SW/0/9/S/22/E/31/0/0/26/PM/S/2,611.00/E/0/1,837.00/0/0	

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
8/10/2010	8:00 - 18:00	10.00	COMP	36	B	P		<p>FRAC STG 5)WHP 1588 PSI, BRK 2532 PSI @ 5.0 BPM. ISIP 2256 PSI, FG .72. PUMP 100 BBLS @ 49.6 BPM @ 4758 PSI = 96% HOLES OPEN. ISIP 2413 PSI, FG .74, NPI 157 PSI. MP 6240 PSI, MR 50.4 BPM, AP 4577 PSI, AR 49.6 BPM, PMP 777 BBLS SW &amp; 23,599 LBS OF 30/50 SND &amp; 5,000 LBS OF 20/40 SLC SND. TOTAL PROP 28,,599 LBS, SWI, X-OVER FOR WL.</p> <p>PERF STG 6)PU 4 1/2 8K HAL CBP &amp; 3 1/8 EXP GUN, 23 GM, .36 HOLE SIZE. 120 DEG PHASING. RIH SET CBP @ 7997' P/U PERF F/ 7747'-48', 3 SPF, 3 HOLES. 7796'-98', 3 SPF, 6 HOLES. 7864'-67', 3 SPF, 9 HOLES. 7965'-67', 3 SPF, 6 HOLES. 24 HOLES. POOH, X-OVER FOR FRAC CREW.</p> <p>FRAC STG 6)COULD NOT START THIS STG UNTIL MAKE REPAIRS T/ PUMP 84. ( PONY ROD BRK.) DOWN FOR 39 MIN. WHP 1085 PSI, BRK 2883 PSI @ 5.4 BPM. ISIP 2189 PSI, FG .72. PUMP 100 BBLS @ 48.7 BPM @ 4500 PSI = 100% HOLES OPEN. ISIP 0000 PSI, FG .00, NPI 000 PSI. MP 0000 PSI, MR 00 BPM, AP 0000 PSI, AR 00.0 BPM, PMP 758 BBLS SW &amp; 36,952 LBS OF 30/50 SND &amp; 5,000 LBS OF 20/40 SLC SND. TOTAL PROP 41,952 LBS,</p> <p>PERF STG 7) PU 4 1/2 8K HAL CBP &amp; 3 1/8 EXP GUN, 23 GM, .36 HOLE SIZE. 120 DEG PHASING. RIH SET CBP @ 7665' P/U PERF F/ 7456'-59', 3 SPF, 9 HOLES. 7631'-35', 3 SPF, 12 HOLES. 21 HOLES. POOH, X-OVER FOR FRAC CREW.</p> <p>FRAC STG 7)WHP 675 PSI, BRK 2670 PSI @ 5.1 BPM. ISIP 1941 PSI, FG .70. PUMP 100 BBLS @ 50.1 BPM @ 4480 PSI = 100% HOLES OPEN. ISIP 2167 PSI, FG .73, NPI 226 PSI. MP 4706 PSI, MR 50.2 BPM, AP 4325 PSI, AR 50 BPM, PMP 965 BBLS SW &amp; 32,655 LBS OF 30/50 SND &amp; 5,000 LBS OF 20/40 SLC SND. TOTAL PROP 37,655 LBS, SWI, X-OVER FOR WL.</p> <p>PERF STG 8)PU 4 1/2 8K HAL CBP &amp; 3 1/8 EXP GUN, 23 GM, .36 HOLE SIZE. 120 DEG PHASING. RIH SET CBP @ 7412' P/U PERF F/ 7249'-52', 3 SPF, 9 HOLES. 7301'-03', 3 SPF, 6 HOLES. 7379'-82', 3 SPF, 9 HOLES. 24 HOLES. POOH, SWIFN.</p>

US ROCKIES REGION  
Operation Summary Report

Well: NBU 922-31J2S PURPLE		Spud Conductor: 10/7/2009		Spud Date: 10/16/2009				
Project: UTAH-UINTAH		Site: NBU 922-31K PAD		Rig Name No: LEED 733/733				
Event: COMPLETION		Start Date: 8/6/2010		End Date: 8/17/2010				
Active Datum: RKB @4,855.01ft (above Mean Sea Level)		UWI: NE/SW/0/9/S/22/E/31/0/0/26/PM/S/2,611.00/E/0/1,837.00/0/0						
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
8/11/2010	7:30 - 18:00	10.50	COMP	36	B	P		FRAC STG 8)WHP 1320 PSI, BRK 2335 PSI @ 5.0 BPM. ISIP 1990 PSI, FG .71. PUMP 100 BBLS @ 50.4 BPM @ 4356 PSI = 100% HOLES OPEN. ISIP 2985 PSI, FG .85, NPI 995 PSI. MP 6676 PSI, MR 54.3 BPM, AP 4540 PSI, AR 51.1 BPM, PMP 3972 BBLS SW & 137,655 LBS OF 30/50 SND & 5,000 LBS OF 20/40 SLC SND. TOTAL PROP 142,028 LBS, SWI, X-OVER FOR WL. ((( DID NOT GET ANY SLC SAND IN THIS STG. )))  PERF STG 9)PU 4 1/2 8K HAL CBP & 3 1/8 EXP GUN, 23 GM, .36 HOLESIZE. 120 DEG PHASING. RIH SET CBP @ 6920' P/U PERF F/ 6768'-72', 3 SPF, 12 HOLES. 6887'-90', 3 SPF, 9 HOLES. 21 HOLES. POOH. X-OVER FOR FRAC CREW.  FRAC STG 9)WHP 142 PSI, BRK 1925 PSI @ 5.0 BPM. ISIP 1788 PSI, FG .70. PUMP 100 BBLS @ 49 BPM @ 4640 PSI = 95% HOLES OPEN. ISIP 1954 PSI, FG .73, NPI 166 PSI. MP 4989 PSI, MR 50.2 BPM, AP 4471 PSI, AR 49.8 BPM, PMP 636 BBLS SW & 20,907 LBS OF 30/50 SND & 5,000 LBS OF 20/40 SLC SND. TOTAL PROP 25,907 LBS, SWI, X-OVER FOR WL.  PU 4 1/2 8K HAL CBP. RIH SET KILL PLUG @ 6920'. POOH. SWI. DONE FRACING THIS WELL.  TOTAL SAND 466,436# TOTAL FLUID 11,861 BBLS. JSA- RUSU. NU BOP. PU TBG ROAD RIG IN. SPOT AND RUSU. SPOT EQUIP. ND WH. NU BOP. RU FLOOR AND TBG EQUIP. MU 3-7/8" BIT, POBS, 1.87" XN NIPPLE AND RIH AS MEAS AND PU 212 JTS 2-3/8" L-80 TBG. TAG AT 6509'. RU DRLG EQUIP. FILL TBG AND P-TEST TO 3000#. GOOD. EST CIRC AND D/O PLUGS. #1- C/O 6' SAND TO CBP AT 6718'. D/O IN 15 MIN. 0# INC. RIH. #2- C/O 18' SAND TO CBP AT 6920'. D/O IN 15 MIN. 200# INC. RIH. #3- C/O 30' SAND TO CBP AT 7412'. D/O IN 12 MIN. 100# INC. RIH. #4- C/O 24' SAND TO CBP AT 7665'. D/O IN 23 MIN. 300# INC. RIH. #5- C/O 30' SAND TO CBP AT 7997'. D/O IN 11 MIN. 100# INC.
8/16/2010	6:30 - 6:45	0.25	COMP	48		P		
	6:45 - 9:00	2.25	COMP	30	A	P		
	9:00 - 13:30	4.50	COMP	31	I	P		
	13:30 - 18:30	5.00	COMP	44	C	P		
8/17/2010	6:30 - 6:45	0.25	COMP	48		P		CIRC CLEAN W/ 253-JTS IN. EOT AT 8018'. SDFN. JSA- PU TBG. D/O PLUGS. ND/NU.

US ROCKIES REGION  
Operation Summary Report

Well: NBU 922-31J2S	PURPLE	Spud Conductor: 10/7/2009	Spud Date: 10/16/2009
Project: UTAH-UINTAH	Site: NBU 922-31K PAD	Rig Name No: LEED 733/733	
Event: COMPLETION	Start Date: 8/6/2010	End Date: 8/17/2010	
Active Datum: RKB @4,855.01ft (above Mean Sea Level)	UWI: NE/SW/0/9/S/22/E/31/0/0/26/PM/S/2,611.00/E/0/1,837.00/0/0		

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
	6:45 - 13:30	6.75	COMP	44	C	P		<p>SITP 0, SICP 1750. OPEN CSG TO PIT. PU TBG TO TAG. PU PWR SWIVEL. EST CIRC AND CONT D/O PLUGS.</p> <p>#6- C/O 35' SAND TO CBP AT 8327'. D/O IN 3 MIN. 100# INC. RIH.</p> <p>#7- C/O 28' SAND TO CBP AT 8533'. D/O IN 8 MIN. 0# INC. RIH.</p> <p>#8- C/O 25' SAND TO CBP AT 8726'. D/O IN 10 MIN. 100# INC. RIH.</p> <p>#9- C/O 28' SAND TO CBP AT 8974'. D/O IN 10 MIN. 0# INC. RIH.</p> <p>PBTD- C/O 78' SAND TO PBTD AT 9346' (120' RATHOLE) W/ 295-JTS IN.</p> <p>CIRC CLEAN RD PWR SWIVEL. POOH AS LD 88-JTS TBG. PU 7" 5K HANGER. LUB IN AND LAND 207-JTS W/ EOT AT 6575.33'. RD FLOOR. ND BOP. NU WH. PMP OFF BIT AT 2800 PSI. SHUT WELL IN FOR 30 MIN. TURN OVER TO FBC. RDSU AND MOVE OVER.</p> <p>TBG DETAIL KB 15.00 314-JTS DELIVERED 7" 5K HANGER 1.00 107-JTS RETURNED 207-JTS L-80 6557.13 1.87" XN (FE POBS) 2.20 EOT 6575.33</p> <p>LOAD 11,861 BBL / RCVR 3474 BBL / LTR 8387 BBL</p>
8/18/2010	7:00 -			33	A			<p>7 AM FLBK REPORT: CP 2800#, TP 2200#, 20/64" CK, 48 BWPH, HEAVY SAND, LIGHT GAS TTL BBLS RECOVERED: 7483 BBLS LEFT TO RECOVER: 4378</p>
	11:50 -		PROD	50				<p>WELL TURNED TO SALES @ 1150 HR ON 8/18/2010 - 958 MCFD, 1200 BWPD, CP 2800#, FTP 1950#, CK 20/64"</p>
8/19/2010	7:00 -			33	A			<p>7 AM FLBK REPORT: CP 2950#, TP 2000#, 20/64" CK, 40 BWPH, med SAND, 2263 GAS TTL BBLS RECOVERED: 5588 BBLS LEFT TO RECOVER: 7089</p>
8/20/2010	7:00 -			33	A			<p>7 AM FLBK REPORT: CP 2750#, TP 1900#, 20/64" CK, 38 BWPH, MED SAND, 2256 GAS TTL BBLS RECOVERED: 6536 BBLS LEFT TO RECOVER: 6141</p>
8/21/2010	7:00 -			33	A			<p>7 AM FLBK REPORT: CP 2600#, TP 1800#, 20/64" CK, 34 BWPH, MED SAND, - GAS TTL BBLS RECOVERED: 7408 BBLS LEFT TO RECOVER: 5269</p>
8/22/2010	7:00 -			33	A			<p>7 AM FLBK REPORT: CP 2750#, TP 1750#, 20/64" CK, 28 BWPH, LIGHT SAND, - GAS TTL BBLS RECOVERED: 8140 BBLS LEFT TO RECOVER: 4537</p>
	7:00 -							<p>WELL IP'D ON 8/22/10 - 2289 MCFD, 0 BOPD, 360 BWPD, CP 2950#, FTP 2000#, CK 20/64", LP 123#, 24 HRS</p>





WELL DETAILS: NBU 922-31J2S								
+N/-S	+E/-W	Northing	Ground Level: 4840.00	Easting	Latitude	Longitude	Slot	
0.00	0.00	14526851.04		2064787.06	39° 59' 32.320 N	109° 29' 5.669 W		

WELLBORE TARGET DETAILS (LAT/LONG)							
Name	TVD	+N/-S	+E/-W	Latitude	Longitude	Shape	
PBHL	9170.00	55.77	1613.9339° 59'	32.870 109° 28'	44.929 W	Circle (Radius: 25.00)	

SECTION DETAILS										
MD	Inc	Azi	TVD	+N/-S	+E/-W	DLeg	TFace	VSec	Target	
2185.00	17.44	85.95	2112.48	20.32	495.91	0.00	0.00	496.32		
2297.00	17.44	85.95	2219.33	22.69	529.39	0.00	0.00	529.86		
2331.91	17.51	88.26	2252.63	23.22	539.86	2.00	85.43	540.34		
5462.43	17.51	88.26	5238.11	51.75	1481.26	0.00	0.00	1482.17		
6337.88	0.00	0.00	6100.00	55.77	1613.93	2.00	180.00	1614.89		
9407.88	0.00	0.00	9170.00	55.77	1613.93	0.00	0.00	1614.89	PBHL_NBU 922-31J2S(2611 FSL, 1837 FEL)25' TGT RAD	

KB ELEV: PROD RIG KB @ 4854.00ft (ENSIGN 146)  
 GRD ELEV: 4840.00



FORMATION TOP DETAILS			
TVDPath	MDPath	Formation	
4374.00	4556.34	WASATCH	
6955.00	7192.88	DKCYN	
7932.00	8169.88	MESAUVERDE	

CASING DETAILS			
TVD	MD	Name	Size
2123.93	2197.00	9 5/8"	9.62



# **ANADARKO PETROLEUM CORP.**

UINTAH COUNTY, UTAH (nad 27)

NBU 922-31K PAD

NBU 922-31J2S

NBU 922-31J2S

Survey: Survey #1

## **Standard Survey Report**

02 December, 2009



Company: ANADARKO PETROLEUM CORP.  
Project: UINTAH COUNTY, UTAH (nad 27)  
Site: NBU 922-31K PAD  
Well: NBU 922-31J2S  
Wellbore: NBU 922-31J2S  
Design: NBU 922-31J2S

Local Co-ordinate Reference: Well NBU 922-31J2S  
TVD Reference: PROD RIG KB @ 4854.00ft (ENSIGN 146)  
MD Reference: PROD RIG KB @ 4854.00ft (ENSIGN 146)  
North Reference: True  
Survey Calculation Method: Minimum Curvature  
Database: EDM 2003.21 Single User Db

Project	UINTAH COUNTY, UTAH (nad 27),		
Map System:	Universal Transverse Mercator (US Survey Fee	System Datum:	Mean Sea Level
Geo Datum:	NAD 1927 (NADCON CONUS)		
Map Zone:	Zone 12N (114 W to 108 W)		

Site	NBU 922-31K PAD, SECTION 31 T9S R22E			
Site Position:		Northing:	14,526,925.45 ft	Latitude: 39° 59' 33.050 N
From:	Lat/Long	Easting:	2,064,816.91 ft	Longitude: 109° 29' 5.269 W
Position Uncertainty:	0.00 ft	Slot Radius:	in	Grid Convergence: 0.97 °

Well	NBU 922-31J2S			
Well Position	+N/-S	0.00 ft	Northing:	14,526,851.04 ft
	+E/-W	0.00 ft	Easting:	2,064,787.06 ft
Position Uncertainty	0.00 ft	Wellhead Elevation:	ft	Ground Level: 4,840.00 ft

Wellbore	NBU 922-31J2S				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	BGGM2009	11/17/2009	11.30	65.92	52,495

Design	NBU 922-31J2S				
Audit Notes:					
Version:	1.0	Phase:	ACTUAL	Tie On Depth:	0.00
Vertical Section:	Depth From (TVD) (ft)	+N/-S (ft)	+E/-W (ft)	Direction (°)	
	0.00	0.00	0.00	87.66	

Survey Program Date 12/2/2009

From (ft)	To (ft)	Survey (Wellbore)	Tool Name	Description
155.00	9,421.00	Survey #1 (NBU 922-31J2S)	MWD	MWD - Standard

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
155.00	0.32	341.73	155.00	0.41	-0.14	-0.12	0.21	0.21	0.00
185.00	0.27	314.72	185.00	0.54	-0.21	-0.19	0.49	-0.17	-90.03
215.00	0.41	347.51	215.00	0.69	-0.29	-0.26	0.78	0.47	109.30
245.00	0.46	9.11	245.00	0.92	-0.29	-0.25	0.57	0.17	72.00
275.00	1.00	68.45	275.00	1.13	-0.03	0.02	2.87	1.80	197.80
305.00	1.81	75.32	304.99	1.35	0.67	0.73	2.75	2.70	22.90
335.00	2.63	76.82	334.96	1.63	1.80	1.87	2.74	2.73	5.00
365.00	3.56	79.32	364.92	1.96	3.39	3.47	3.13	3.10	8.33
395.00	4.25	81.20	394.85	2.30	5.40	5.49	2.34	2.30	6.27
425.00	5.13	83.32	424.75	2.63	7.83	7.93	2.99	2.93	7.07
455.00	6.13	81.95	454.60	3.01	10.75	10.87	3.36	3.33	-4.57
480.00	7.00	81.32	479.44	3.42	13.58	13.71	3.49	3.48	-2.52



Company: ANADARKO PETROLEUM CORP.  
Project: UINTAH COUNTY, UTAH (nad 27)  
Site: NBU 922-31K PAD  
Well: NBU 922-31J2S  
Wellbore: NBU 922-31J2S  
Design: NBU 922-31J2S

Local Co-ordinate Reference: Well NBU 922-31J2S  
TVD Reference: PROD RIG KB @ 4854.00ft (ENSIGN 146)  
MD Reference: PROD RIG KB @ 4854.00ft (ENSIGN 146)  
North Reference: True  
Survey Calculation Method: Minimum Curvature  
Database: EDM 2003.21 Single User Db

Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
510.00	8.00	82.82	509.18	3.96	17.46	17.60	3.40	3.33	5.00
535.00	8.75	83.95	533.92	4.38	21.07	21.24	3.07	3.00	4.52
565.00	9.44	85.20	563.54	4.82	25.80	25.97	2.39	2.30	4.17
595.00	10.38	85.19	593.09	5.26	30.94	31.13	3.13	3.13	-0.03
625.00	11.19	85.82	622.56	5.69	36.54	36.74	2.73	2.70	2.10
655.00	11.88	87.69	651.95	6.03	42.53	42.74	2.62	2.30	6.23
685.00	12.63	88.82	681.27	6.22	48.89	49.10	2.62	2.50	3.77
715.00	13.31	90.07	710.50	6.29	55.62	55.83	2.45	2.27	4.17
745.00	14.13	90.57	739.65	6.25	62.74	62.94	2.76	2.73	1.67
775.00	14.88	90.82	768.69	6.15	70.25	70.44	2.51	2.50	0.83
835.00	16.31	91.45	826.48	5.83	86.38	86.54	2.40	2.38	1.05
925.00	17.13	91.70	912.68	5.12	112.26	112.37	0.91	0.91	0.28
1,015.00	17.38	91.57	998.63	4.36	138.94	139.01	0.28	0.28	-0.14
1,105.00	18.06	88.82	1,084.36	4.28	166.33	166.37	1.20	0.76	-3.06
1,195.00	18.31	87.70	1,169.86	5.13	194.40	194.45	0.48	0.28	-1.24
1,285.00	18.31	87.57	1,255.31	6.30	222.65	222.72	0.05	0.00	-0.14
1,375.00	19.06	86.57	1,340.56	7.78	251.45	251.55	0.91	0.83	-1.11
1,465.00	19.56	86.45	1,425.50	9.59	281.15	281.31	0.56	0.56	-0.13
1,555.00	18.81	87.32	1,510.50	11.20	310.68	310.88	0.89	-0.83	0.97
1,645.00	18.00	87.95	1,595.89	12.37	339.07	339.30	0.93	-0.90	0.70
1,735.00	18.63	87.07	1,681.34	13.61	367.33	367.58	0.76	0.70	-0.98
1,825.00	16.56	89.20	1,767.12	14.52	394.51	394.78	2.41	-2.30	2.37
1,915.00	16.00	87.95	1,853.51	15.14	419.73	420.00	0.73	-0.62	-1.39
2,005.00	16.13	86.57	1,940.00	16.34	444.61	444.91	0.45	0.14	-1.53
2,095.00	16.44	84.85	2,026.39	18.23	469.77	470.13	0.64	0.34	-1.91
2,185.00	17.44	85.95	2,112.48	20.32	495.91	496.33	1.17	1.11	1.22
2,278.00	15.94	86.30	2,201.56	22.13	522.56	523.03	1.62	-1.61	0.38
2,323.00	15.53	84.25	2,244.88	23.13	534.72	535.22	1.53	-0.91	-4.56
2,369.00	15.31	85.30	2,289.22	24.25	546.90	547.43	0.77	-0.48	2.28
2,414.00	15.75	85.93	2,332.58	25.17	558.91	559.47	1.05	0.98	1.40
2,459.00	16.38	87.68	2,375.82	25.86	571.34	571.92	1.77	1.40	3.89
2,505.00	16.31	88.43	2,419.96	26.30	584.28	584.87	0.48	-0.15	1.63
2,550.00	16.50	88.68	2,463.13	26.62	596.99	597.57	0.45	0.42	0.56
2,595.00	17.00	88.18	2,506.22	26.97	609.95	610.54	1.16	1.11	-1.11
2,641.00	17.31	87.80	2,550.17	27.45	623.51	624.11	0.72	0.67	-0.83
2,686.00	16.75	88.55	2,593.20	27.87	636.68	637.29	1.34	-1.24	1.67
2,731.00	16.31	88.80	2,636.34	28.17	649.48	650.09	0.99	-0.98	0.56
2,777.00	16.88	88.93	2,680.42	28.43	662.62	663.22	1.24	1.24	0.28
2,822.00	17.56	88.80	2,723.41	28.69	675.94	676.54	1.51	1.51	-0.29
2,867.00	18.56	88.18	2,766.19	29.06	689.88	690.49	2.26	2.22	-1.38
2,913.00	18.94	89.05	2,809.75	29.42	704.66	705.28	1.03	0.83	1.89
2,958.00	19.25	88.18	2,852.27	29.77	719.38	719.99	0.94	0.69	-1.93
3,003.00	19.81	88.05	2,894.68	30.27	734.41	735.04	1.25	1.24	-0.29
3,049.00	20.44	88.05	2,937.87	30.81	750.23	750.86	1.37	1.37	0.00
3,094.00	19.69	87.30	2,980.14	31.43	765.66	766.30	1.76	-1.67	-1.67
3,139.00	19.38	87.30	3,022.55	32.14	780.69	781.35	0.69	-0.69	0.00
3,185.00	19.44	87.30	3,065.94	32.86	795.96	796.64	0.13	0.13	0.00
3,230.00	18.73	87.01	3,108.46	33.59	810.65	811.35	1.59	-1.58	-0.64
3,275.00	17.38	87.18	3,151.25	34.30	824.58	825.29	3.00	-3.00	0.38
3,320.00	17.31	87.68	3,194.20	34.90	837.98	838.71	0.37	-0.16	1.11
3,366.00	19.00	90.43	3,237.91	35.12	852.31	853.03	4.12	3.67	5.98
3,411.00	19.69	91.68	3,280.37	34.84	867.21	867.91	1.79	1.53	2.78
3,456.00	19.13	90.93	3,322.81	34.50	882.16	882.84	1.36	-1.24	-1.67
3,502.00	19.81	89.93	3,366.18	34.39	897.50	898.15	1.65	1.48	-2.17

Company: ANADARKO PETROLEUM CORP.  
Project: UINTAH COUNTY, UTAH (nad 27)  
Site: NBU 922-31K PAD  
Well: NBU 922-31J2S  
Wellbore: NBU 922-31J2S  
Design: NBU 922-31J2S

Local Co-ordinate Reference: Well NBU 922-31J2S  
TVD Reference: PROD RIG KB @ 4854.00ft (ENSIGN 146)  
MD Reference: PROD RIG KB @ 4854.00ft (ENSIGN 146)  
North Reference: True  
Survey Calculation Method: Minimum Curvature  
Database: EDM 2003.21 Single User Db

Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
3,547.00	18.88	89.80	3,408.64	34.42	912.40	913.05	2.07	-2.07	-0.29
3,592.00	18.31	88.55	3,451.29	34.63	926.75	927.39	1.55	-1.27	-2.78
3,638.00	18.44	88.05	3,494.94	35.06	941.24	941.89	0.44	0.28	-1.09
3,683.00	17.75	87.43	3,537.72	35.61	955.21	955.87	1.59	-1.53	-1.38
3,728.00	16.94	86.80	3,580.67	36.28	968.61	969.28	1.85	-1.80	-1.40
3,774.00	16.38	86.05	3,624.74	37.10	981.77	982.47	1.30	-1.22	-1.63
3,819.00	17.38	86.80	3,667.80	37.92	994.81	995.53	2.27	2.22	1.67
3,864.00	17.38	86.68	3,710.75	38.68	1,008.23	1,008.97	0.08	0.00	-0.27
3,909.00	17.75	86.05	3,753.65	39.54	1,021.78	1,022.55	0.92	0.82	-1.40
3,955.00	18.25	87.30	3,797.40	40.36	1,035.97	1,036.76	1.37	1.09	2.72
4,000.00	18.19	87.30	3,840.14	41.03	1,050.03	1,050.83	0.13	-0.13	0.00
4,045.00	17.38	87.68	3,882.99	41.63	1,063.76	1,064.57	1.82	-1.80	0.84
4,091.00	16.63	88.30	3,926.98	42.10	1,077.20	1,078.02	1.68	-1.63	1.35
4,136.00	15.88	88.18	3,970.18	42.49	1,089.79	1,090.62	1.67	-1.67	-0.27
4,181.00	16.13	88.05	4,013.44	42.90	1,102.19	1,103.03	0.56	0.56	-0.29
4,227.00	17.19	89.05	4,057.50	43.23	1,115.38	1,116.21	2.39	2.30	2.17
4,272.00	18.19	88.93	4,100.38	43.47	1,129.05	1,129.88	2.22	2.22	-0.27
4,317.00	18.13	88.43	4,143.13	43.79	1,143.07	1,143.91	0.37	-0.13	-1.11
4,362.00	17.13	87.93	4,186.02	44.22	1,156.69	1,157.53	2.25	-2.22	-1.11
4,407.00	16.13	89.55	4,229.14	44.51	1,169.57	1,170.41	2.45	-2.22	3.60
4,453.00	16.00	87.80	4,273.34	44.81	1,182.29	1,183.13	1.09	-0.28	-3.80
4,498.00	16.69	87.18	4,316.52	45.36	1,194.94	1,195.80	1.58	1.53	-1.38
4,543.00	17.50	87.43	4,359.53	45.98	1,208.16	1,209.03	1.81	1.80	0.56
4,589.00	18.50	86.30	4,403.28	46.76	1,222.35	1,223.24	2.30	2.17	-2.46
4,679.00	17.88	86.30	4,488.78	48.58	1,250.38	1,251.33	0.69	-0.69	0.00
4,770.00	19.20	89.56	4,575.06	49.59	1,279.29	1,280.25	1.84	1.45	3.58
4,861.00	19.50	87.18	4,660.92	50.46	1,309.42	1,310.39	0.93	0.33	-2.62
4,952.00	18.50	87.93	4,746.96	51.72	1,339.02	1,340.02	1.13	-1.10	0.82
5,042.00	18.06	87.68	4,832.42	52.81	1,367.23	1,368.25	0.50	-0.49	-0.28
5,133.00	18.31	88.43	4,918.88	53.77	1,395.61	1,396.65	0.38	0.27	0.82
5,224.00	17.63	88.30	5,005.44	54.57	1,423.68	1,424.72	0.75	-0.75	-0.14
5,314.00	16.50	89.05	5,091.47	55.18	1,450.08	1,451.12	1.28	-1.26	0.83
5,405.00	15.19	84.43	5,179.02	56.56	1,474.87	1,475.95	2.00	-1.44	-5.08
5,496.00	14.19	85.18	5,267.04	58.65	1,497.85	1,499.00	1.12	-1.10	0.82
5,586.00	12.56	85.68	5,354.60	60.31	1,518.60	1,519.80	1.82	-1.81	0.56
5,677.00	11.69	87.05	5,443.57	61.53	1,537.67	1,538.91	1.01	-0.96	1.51
5,768.00	10.88	85.68	5,532.81	62.66	1,555.45	1,556.71	0.94	-0.89	-1.51
5,858.00	8.31	85.80	5,621.54	63.77	1,570.40	1,571.70	2.86	-2.86	0.13
5,949.00	7.50	87.30	5,711.67	64.53	1,582.90	1,584.21	0.92	-0.89	1.65
6,040.00	5.44	79.93	5,802.09	65.57	1,593.08	1,594.42	2.44	-2.26	-8.10
6,130.00	3.81	80.43	5,891.80	66.81	1,600.23	1,601.62	1.81	-1.81	0.56
6,221.00	3.50	82.93	5,982.61	67.66	1,605.96	1,607.39	0.38	-0.34	2.75
6,312.00	0.81	98.30	6,073.54	67.90	1,609.36	1,610.79	3.00	-2.96	16.89
6,402.00	0.81	113.18	6,163.53	67.56	1,610.57	1,611.99	0.23	0.00	16.53
6,493.00	0.87	125.58	6,254.52	66.91	1,611.72	1,613.11	0.21	0.07	13.63
6,584.00	1.00	126.05	6,345.51	66.04	1,612.93	1,614.28	0.14	0.14	0.52
6,674.00	0.50	351.68	6,435.50	65.96	1,613.51	1,614.85	1.55	-0.56	-149.30
6,765.00	0.38	339.18	6,526.50	66.64	1,613.34	1,614.72	0.17	-0.13	-13.74
6,856.00	1.06	349.30	6,617.49	67.75	1,613.08	1,614.50	0.76	0.75	11.12
6,946.00	0.88	356.43	6,707.48	69.26	1,612.88	1,614.36	0.24	-0.20	7.92
7,037.00	0.56	34.68	6,798.47	70.32	1,613.09	1,614.62	0.62	-0.35	42.03
7,128.00	0.63	81.68	6,889.47	70.76	1,613.84	1,615.38	0.53	0.08	51.65
7,218.00	0.69	289.05	6,979.47	71.01	1,613.82	1,615.37	1.43	0.07	-169.59
7,309.00	1.56	329.55	7,070.45	72.25	1,612.67	1,614.28	1.24	0.96	44.51

Company: ANADARKO PETROLEUM CORP.  
Project: Uintah County, Utah (nad 27)  
Site: NBU 922-31K PAD  
Well: NBU 922-31J2S  
Wellbore: NBU 922-31J2S  
Design: NBU 922-31J2S

Local Co-ordinate Reference: Well NBU 922-31J2S  
TVD Reference: PROD RIG KB @ 4854.00ft (ENSIGN 146)  
MD Reference: PROD RIG KB @ 4854.00ft (ENSIGN 146)  
North Reference: True  
Survey Calculation Method: Minimum Curvature  
Database: EDM 2003.21 Single User Db

# Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
7,400.00	1.31	340.93	7,161.42	74.30	1,611.70	1,613.39	0.42	-0.27	12.51
7,491.00	1.25	335.68	7,252.40	76.19	1,610.95	1,612.72	0.14	-0.07	-5.77
7,581.00	1.06	341.05	7,342.38	77.87	1,610.28	1,612.12	0.24	-0.21	5.97
7,669.00	0.64	347.32	7,430.37	79.12	1,609.91	1,611.80	0.49	-0.48	7.12
7,760.00	0.44	346.80	7,521.37	79.96	1,609.72	1,611.64	0.22	-0.22	-0.57
7,851.00	0.19	37.05	7,612.36	80.42	1,609.73	1,611.67	0.39	-0.27	55.22
7,942.00	0.38	105.43	7,703.36	80.46	1,610.11	1,612.05	0.39	0.21	75.14
8,032.00	0.44	136.68	7,793.36	80.13	1,610.63	1,612.56	0.25	0.07	34.72
8,123.00	0.75	117.93	7,884.36	79.60	1,611.40	1,613.31	0.40	0.34	-20.60
8,214.00	0.81	118.18	7,975.35	79.01	1,612.49	1,614.37	0.07	0.07	0.27
8,304.00	1.06	110.18	8,065.34	78.42	1,613.83	1,615.69	0.31	0.28	-8.89
8,395.00	1.25	123.18	8,156.32	77.59	1,615.46	1,617.28	0.35	0.21	14.29
8,486.00	1.63	120.93	8,247.29	76.38	1,617.40	1,619.17	0.42	0.42	-2.47
8,576.00	2.31	125.05	8,337.24	74.68	1,619.98	1,621.68	0.77	0.76	4.58
8,667.00	2.25	127.30	8,428.16	72.55	1,622.90	1,624.51	0.12	-0.07	2.47
8,787.00	2.19	157.80	8,548.08	69.00	1,625.64	1,627.10	0.97	-0.05	25.42
8,848.00	1.81	152.18	8,609.04	67.07	1,626.53	1,627.91	0.70	-0.62	-9.21
8,939.00	2.00	151.18	8,699.99	64.40	1,627.97	1,629.24	0.21	0.21	-1.10
9,029.00	1.94	145.68	8,789.94	61.77	1,629.58	1,630.75	0.22	-0.07	-6.11
9,120.00	2.00	153.93	8,880.88	59.07	1,631.15	1,632.20	0.32	0.07	9.07
9,211.00	2.06	146.93	8,971.83	56.27	1,632.74	1,633.68	0.28	0.07	-7.69
9,301.00	2.50	148.68	9,061.75	53.24	1,634.64	1,635.45	0.49	0.49	1.94
9,365.00	2.50	140.93	9,125.69	50.97	1,636.25	1,636.96	0.53	0.00	-12.11
EXT. TD									
9,421.00	2.50	140.93	9,181.64	49.07	1,637.79	1,638.43	0.00	0.00	0.00

## Survey Annotations

Measured Depth (ft)	Vertical Depth (ft)	Local Coordinates +N/-S (ft)	+E/-W (ft)	Comment
9,421.00	9,181.64	49.07	1,637.79	EXT. TD

Checked By: \_\_\_\_\_ Approved By: \_\_\_\_\_ Date: \_\_\_\_\_



# **ANADARKO PETROLEUM CORP.**

UINTAH COUNTY, UTAH (nad 27)

NBU 922-31K PAD

NBU 922-31J2S

NBU 922-31J2S

Survey: Survey #1

## **Survey Report - Geographic**

02 December, 2009



Company:	ANADARKO PETROLEUM CORP.	Local Co-ordinate Reference:	Well NBU 922-31J2S
Project:	UINTAH COUNTY, UTAH (nad 27)	TVD Reference:	PROD RIG KB @ 4854.00ft (ENSIGN 146)
Site:	NBU 922-31K PAD	MD Reference:	PROD RIG KB @ 4854.00ft (ENSIGN 146)
Well:	NBU 922-31J2S	North Reference:	True
Wellbore:	NBU 922-31J2S	Survey Calculation Method:	Minimum Curvature
Design:	NBU 922-31J2S	Database:	EDM 2003.21 Single User Db

Project	UINTAH COUNTY, UTAH (nad 27),		
Map System:	Universal Transverse Mercator (US Survey Fee	System Datum:	Mean Sea Level
Geo Datum:	NAD 1927 (NADCON CONUS)		
Map Zone:	Zone 12N (114 W to 108 W)		

Site	NBU 922-31K PAD, SECTION 31 T9S R22E				
Site Position:		Northing:	14,526,925.45 ft	Latitude:	39° 59' 33.050 N
From:	Lat/Long	Easting:	2,064,816.91 ft	Longitude:	109° 29' 5.269 W
Position Uncertainty:	0.00 ft	Slot Radius:	in	Grid Convergence:	0.97 °

Well	NBU 922-31J2S					
Well Position	+N/-S	0.00 ft	Northing:	14,526,851.04 ft	Latitude:	39° 59' 32.320 N
	+E/-W	0.00 ft	Easting:	2,064,787.06 ft	Longitude:	109° 29' 5.669 W
Position Uncertainty	0.00 ft		Wellhead Elevation:	ft	Ground Level:	4,840.00 ft

Wellbore	NBU 922-31J2S				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	BGGM2009	11/17/2009	11.30	65.92	52,495

Design	NBU 922-31J2S				
Audit Notes:					
Version:	1.0	Phase:	ACTUAL	Tie On Depth:	0.00
Vertical Section:	Depth From (TVD) (ft)	+N/-S (ft)	+E/-W (ft)	Direction (°)	
	0.00	0.00	0.00	87.66	

Survey Program	Date 12/2/2009				
From (ft)	To (ft)	Survey (Wellbore)	Tool Name	Description	
155.00	9,421.00	Survey #1 (NBU 922-31J2S)	MWD	MWD - Standard	

Company: ANADARKO PETROLEUM CORP.  
Project: UINTAH COUNTY, UTAH (nad 27)  
Site: NBU 922-31K PAD  
Well: NBU 922-31J2S  
Wellbore: NBU 922-31J2S  
Design: NBU 922-31J2S

Local Co-ordinate Reference: Well NBU 922-31J2S  
TVD Reference: PROD RIG KB @ 4854.00ft (ENSIGN 146)  
MD Reference: PROD RIG KB @ 4854.00ft (ENSIGN 146)  
North Reference: True  
Survey Calculation Method: Minimum Curvature  
Database: EDM 2003.21 Single User Db

# Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (ft)	Map Easting (ft)	Latitude	Longitude
0.00	0.00	0.00	0.00	0.00	0.00	14,526,851.04	2,064,787.06	39° 59' 32.320 N	109° 29' 5.669 W
155.00	0.32	341.73	155.00	0.41	-0.14	14,526,851.45	2,064,786.92	39° 59' 32.324 N	109° 29' 5.671 W
185.00	0.27	314.72	185.00	0.54	-0.21	14,526,851.58	2,064,786.84	39° 59' 32.325 N	109° 29' 5.672 W
215.00	0.41	347.51	215.00	0.69	-0.29	14,526,851.73	2,064,786.76	39° 59' 32.326 N	109° 29' 5.672 W
245.00	0.46	9.11	245.00	0.92	-0.29	14,526,851.96	2,064,786.76	39° 59' 32.329 N	109° 29' 5.673 W
275.00	1.00	68.45	275.00	1.13	-0.03	14,526,852.17	2,064,787.01	39° 59' 32.331 N	109° 29' 5.669 W
305.00	1.81	75.32	304.99	1.35	0.67	14,526,852.40	2,064,787.71	39° 59' 32.333 N	109° 29' 5.660 W
335.00	2.63	76.82	334.96	1.63	1.80	14,526,852.70	2,064,788.84	39° 59' 32.336 N	109° 29' 5.646 W
365.00	3.56	79.32	364.92	1.96	3.39	14,526,853.06	2,064,790.42	39° 59' 32.339 N	109° 29' 5.625 W
395.00	4.25	81.20	394.85	2.30	5.40	14,526,853.43	2,064,792.42	39° 59' 32.342 N	109° 29' 5.599 W
425.00	5.13	83.32	424.75	2.63	7.83	14,526,853.80	2,064,794.85	39° 59' 32.346 N	109° 29' 5.568 W
455.00	6.13	81.95	454.60	3.01	10.75	14,526,854.23	2,064,797.76	39° 59' 32.349 N	109° 29' 5.531 W
480.00	7.00	81.32	479.44	3.42	13.58	14,526,854.69	2,064,800.58	39° 59' 32.353 N	109° 29' 5.494 W
510.00	8.00	82.82	509.18	3.96	17.46	14,526,855.30	2,064,804.45	39° 59' 32.359 N	109° 29' 5.444 W
535.00	8.75	83.95	533.92	4.38	21.07	14,526,855.78	2,064,808.06	39° 59' 32.363 N	109° 29' 5.398 W
565.00	9.44	85.20	563.54	4.82	25.80	14,526,856.30	2,064,812.77	39° 59' 32.367 N	109° 29' 5.337 W
595.00	10.38	85.19	593.09	5.26	30.94	14,526,856.82	2,064,817.91	39° 59' 32.372 N	109° 29' 5.271 W
625.00	11.19	85.82	622.56	5.69	36.54	14,526,857.36	2,064,823.50	39° 59' 32.376 N	109° 29' 5.199 W
655.00	11.88	87.69	651.95	6.03	42.53	14,526,857.80	2,064,829.48	39° 59' 32.379 N	109° 29' 5.122 W
685.00	12.63	88.82	681.27	6.22	48.89	14,526,858.10	2,064,835.84	39° 59' 32.381 N	109° 29' 5.041 W
715.00	13.31	90.07	710.50	6.29	55.62	14,526,858.27	2,064,842.57	39° 59' 32.382 N	109° 29' 4.954 W
745.00	14.13	90.57	739.65	6.25	62.74	14,526,858.35	2,064,849.68	39° 59' 32.381 N	109° 29' 4.863 W
775.00	14.88	90.82	768.69	6.15	70.25	14,526,858.39	2,064,857.20	39° 59' 32.380 N	109° 29' 4.766 W
835.00	16.31	91.45	826.48	5.83	86.38	14,526,858.34	2,064,873.33	39° 59' 32.377 N	109° 29' 4.559 W
925.00	17.13	91.70	912.68	5.12	112.26	14,526,858.07	2,064,899.22	39° 59' 32.370 N	109° 29' 4.226 W
1,015.00	17.38	91.57	998.63	4.36	138.94	14,526,857.76	2,064,925.91	39° 59' 32.363 N	109° 29' 3.883 W
1,105.00	18.06	88.82	1,084.36	4.28	166.33	14,526,858.14	2,064,953.29	39° 59' 32.362 N	109° 29' 3.531 W
1,195.00	18.31	87.70	1,169.86	5.13	194.40	14,526,859.48	2,064,981.35	39° 59' 32.370 N	109° 29' 3.171 W
1,285.00	18.31	87.57	1,255.31	6.30	222.65	14,526,861.12	2,065,009.58	39° 59' 32.382 N	109° 29' 2.808 W
1,375.00	19.06	86.57	1,340.56	7.78	251.45	14,526,863.09	2,065,038.34	39° 59' 32.396 N	109° 29' 2.438 W
1,465.00	19.56	86.45	1,425.50	9.59	281.15	14,526,865.41	2,065,068.01	39° 59' 32.414 N	109° 29' 2.056 W
1,555.00	18.81	87.32	1,510.50	11.20	310.68	14,526,867.52	2,065,097.51	39° 59' 32.430 N	109° 29' 1.676 W
1,645.00	18.00	87.95	1,595.89	12.37	339.07	14,526,869.18	2,065,125.88	39° 59' 32.442 N	109° 29' 1.312 W
1,735.00	18.63	87.07	1,681.34	13.61	367.33	14,526,870.89	2,065,154.10	39° 59' 32.454 N	109° 29' 0.948 W
1,825.00	16.56	89.20	1,767.12	14.52	394.51	14,526,872.27	2,065,181.27	39° 59' 32.463 N	109° 29' 0.599 W
1,915.00	16.00	87.95	1,853.51	15.14	419.73	14,526,873.32	2,065,206.48	39° 59' 32.469 N	109° 29' 0.275 W
2,005.00	16.13	86.57	1,940.00	16.34	444.61	14,526,874.93	2,065,231.33	39° 59' 32.481 N	109° 28' 59.955 W
2,095.00	16.44	84.85	2,026.39	18.23	469.77	14,526,877.25	2,065,256.46	39° 59' 32.500 N	109° 28' 59.632 W
2,185.00	17.44	85.95	2,112.48	20.32	495.91	14,526,879.79	2,065,282.55	39° 59' 32.520 N	109° 28' 59.296 W
2,278.00	15.94	86.30	2,201.56	22.13	522.56	14,526,882.05	2,065,309.17	39° 59' 32.538 N	109° 28' 58.954 W
2,323.00	15.53	84.25	2,244.88	23.13	534.72	14,526,883.26	2,065,321.31	39° 59' 32.548 N	109° 28' 58.797 W
2,369.00	15.31	85.30	2,289.22	24.25	546.90	14,526,884.58	2,065,333.47	39° 59' 32.559 N	109° 28' 58.641 W
2,414.00	15.75	85.93	2,332.58	25.17	558.91	14,526,885.71	2,065,345.46	39° 59' 32.568 N	109° 28' 58.487 W
2,459.00	16.38	87.68	2,375.82	25.86	571.34	14,526,886.61	2,065,357.88	39° 59' 32.575 N	109° 28' 58.327 W
2,505.00	16.31	88.43	2,419.96	26.30	584.28	14,526,887.27	2,065,370.81	39° 59' 32.579 N	109° 28' 58.161 W
2,550.00	16.50	88.68	2,463.13	26.62	596.99	14,526,887.80	2,065,383.51	39° 59' 32.583 N	109° 28' 57.997 W
2,595.00	17.00	88.18	2,506.22	26.97	609.95	14,526,888.38	2,065,396.46	39° 59' 32.586 N	109° 28' 57.831 W
2,641.00	17.31	87.80	2,550.17	27.45	623.51	14,526,889.09	2,065,410.01	39° 59' 32.591 N	109° 28' 57.656 W
2,686.00	16.75	88.55	2,593.20	27.87	636.68	14,526,889.73	2,065,423.18	39° 59' 32.595 N	109° 28' 57.487 W
2,731.00	16.31	88.80	2,636.34	28.17	649.48	14,526,890.25	2,065,435.97	39° 59' 32.598 N	109° 28' 57.323 W
2,777.00	16.88	88.93	2,680.42	28.43	662.62	14,526,890.73	2,065,449.10	39° 59' 32.601 N	109° 28' 57.154 W
2,822.00	17.56	88.80	2,723.41	28.69	675.94	14,526,891.22	2,065,462.41	39° 59' 32.603 N	109° 28' 56.983 W
2,867.00	18.56	88.18	2,766.19	29.06	689.88	14,526,891.83	2,065,476.35	39° 59' 32.607 N	109° 28' 56.804 W
2,913.00	18.94	89.05	2,809.75	29.42	704.66	14,526,892.43	2,065,491.12	39° 59' 32.610 N	109° 28' 56.614 W
2,958.00	19.25	88.18	2,852.27	29.77	719.38	14,526,893.04	2,065,505.83	39° 59' 32.614 N	109° 28' 56.425 W



Company: ANADARKO PETROLEUM CORP.  
Project: UTAH COUNTY, UTAH (nad 27)  
Site: NBU 922-31K PAD  
Well: NBU 922-31J2S  
Wellbore: NBU 922-31J2S  
Design: NBU 922-31J2S

Local Co-ordinate Reference: Well NBU 922-31J2S  
TVD Reference: PROD RIG KB @ 4854.00ft (ENSIGN 146)  
MD Reference: PROD RIG KB @ 4854.00ft (ENSIGN 146)  
North Reference: True  
Survey Calculation Method: Minimum Curvature  
Database: EDM 2003.21 Single User Db

Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (ft)	Map Easting (ft)	Latitude	Longitude
3,003.00	19.81	88.05	2,894.68	30.27	734.41	14,526,893.79	2,065,520.85	39° 59' 32.619 N	109° 28' 56.231 W
3,049.00	20.44	88.05	2,937.87	30.81	750.23	14,526,894.60	2,065,536.66	39° 59' 32.624 N	109° 28' 56.028 W
3,094.00	19.69	87.30	2,980.14	31.43	765.66	14,526,895.48	2,065,552.07	39° 59' 32.630 N	109° 28' 55.830 W
3,139.00	19.38	87.30	3,022.55	32.14	780.69	14,526,896.45	2,065,567.09	39° 59' 32.637 N	109° 28' 55.637 W
3,185.00	19.44	87.30	3,065.94	32.86	795.96	14,526,897.43	2,065,582.34	39° 59' 32.644 N	109° 28' 55.440 W
3,230.00	18.73	87.01	3,108.46	33.59	810.65	14,526,898.41	2,065,597.02	39° 59' 32.652 N	109° 28' 55.252 W
3,275.00	17.38	87.18	3,151.25	34.30	824.58	14,526,899.35	2,065,610.94	39° 59' 32.659 N	109° 28' 55.073 W
3,320.00	17.31	87.68	3,194.20	34.90	837.98	14,526,900.18	2,065,624.33	39° 59' 32.664 N	109° 28' 54.900 W
3,366.00	19.00	90.43	3,237.91	35.12	852.31	14,526,900.65	2,065,638.65	39° 59' 32.667 N	109° 28' 54.716 W
3,411.00	19.69	91.68	3,280.37	34.84	867.21	14,526,900.62	2,065,653.56	39° 59' 32.664 N	109° 28' 54.525 W
3,456.00	19.13	90.93	3,322.81	34.50	882.16	14,526,900.53	2,065,668.51	39° 59' 32.660 N	109° 28' 54.333 W
3,502.00	19.81	89.93	3,366.18	34.39	897.50	14,526,900.68	2,065,683.84	39° 59' 32.659 N	109° 28' 54.136 W
3,547.00	18.88	89.80	3,408.64	34.42	912.40	14,526,900.97	2,065,698.74	39° 59' 32.660 N	109° 28' 53.944 W
3,592.00	18.31	88.55	3,451.29	34.63	926.75	14,526,901.42	2,065,713.09	39° 59' 32.662 N	109° 28' 53.760 W
3,638.00	18.44	88.05	3,494.94	35.06	941.24	14,526,902.09	2,065,727.57	39° 59' 32.666 N	109° 28' 53.573 W
3,683.00	17.75	87.43	3,537.72	35.61	955.21	14,526,902.88	2,065,741.52	39° 59' 32.671 N	109° 28' 53.394 W
3,728.00	16.94	86.80	3,580.67	36.28	968.61	14,526,903.78	2,065,754.91	39° 59' 32.678 N	109° 28' 53.222 W
3,774.00	16.38	86.05	3,624.74	37.10	981.77	14,526,904.83	2,065,768.06	39° 59' 32.686 N	109° 28' 53.053 W
3,819.00	17.38	86.80	3,667.80	37.92	994.81	14,526,905.86	2,065,781.08	39° 59' 32.694 N	109° 28' 52.885 W
3,864.00	17.38	86.68	3,710.75	38.68	1,008.23	14,526,906.85	2,065,794.49	39° 59' 32.702 N	109° 28' 52.713 W
3,909.00	17.75	86.05	3,753.65	39.54	1,021.78	14,526,907.95	2,065,808.02	39° 59' 32.710 N	109° 28' 52.539 W
3,955.00	18.25	87.30	3,797.40	40.36	1,035.97	14,526,909.01	2,065,822.20	39° 59' 32.718 N	109° 28' 52.356 W
4,000.00	18.19	87.30	3,840.14	41.03	1,050.03	14,526,909.91	2,065,836.24	39° 59' 32.725 N	109° 28' 52.176 W
4,045.00	17.38	87.68	3,882.99	41.63	1,063.76	14,526,910.75	2,065,849.96	39° 59' 32.731 N	109° 28' 51.999 W
4,091.00	16.63	88.30	3,926.98	42.10	1,077.20	14,526,911.45	2,065,863.39	39° 59' 32.736 N	109° 28' 51.826 W
4,136.00	15.88	88.18	3,970.18	42.49	1,089.79	14,526,912.05	2,065,875.97	39° 59' 32.739 N	109° 28' 51.665 W
4,181.00	16.13	88.05	4,013.44	42.90	1,102.19	14,526,912.67	2,065,888.36	39° 59' 32.743 N	109° 28' 51.505 W
4,227.00	17.19	89.05	4,057.50	43.23	1,115.38	14,526,913.22	2,065,901.54	39° 59' 32.747 N	109° 28' 51.336 W
4,272.00	18.19	88.93	4,100.38	43.47	1,129.05	14,526,913.70	2,065,915.21	39° 59' 32.749 N	109° 28' 51.160 W
4,317.00	18.13	88.43	4,143.13	43.79	1,143.07	14,526,914.26	2,065,929.22	39° 59' 32.752 N	109° 28' 50.980 W
4,362.00	17.13	87.93	4,186.02	44.22	1,156.69	14,526,914.92	2,065,942.83	39° 59' 32.756 N	109° 28' 50.805 W
4,407.00	16.13	89.55	4,229.14	44.51	1,169.57	14,526,915.43	2,065,955.70	39° 59' 32.759 N	109° 28' 50.639 W
4,453.00	16.00	87.80	4,273.34	44.81	1,182.29	14,526,915.94	2,065,968.42	39° 59' 32.762 N	109° 28' 50.476 W
4,498.00	16.69	87.18	4,316.52	45.36	1,194.94	14,526,916.71	2,065,981.06	39° 59' 32.768 N	109° 28' 50.313 W
4,543.00	17.50	87.43	4,359.53	45.98	1,208.16	14,526,917.55	2,065,994.26	39° 59' 32.774 N	109° 28' 50.144 W
4,589.00	18.50	86.30	4,403.28	46.76	1,222.35	14,526,918.58	2,066,008.44	39° 59' 32.782 N	109° 28' 49.961 W
4,679.00	17.88	86.30	4,488.78	48.58	1,250.38	14,526,920.87	2,066,036.44	39° 59' 32.799 N	109° 28' 49.601 W
4,770.00	19.20	89.56	4,575.06	49.59	1,279.29	14,526,922.37	2,066,065.32	39° 59' 32.809 N	109° 28' 49.229 W
4,861.00	19.50	87.18	4,660.92	50.46	1,309.42	14,526,923.75	2,066,095.44	39° 59' 32.818 N	109° 28' 48.842 W
4,952.00	18.50	87.93	4,746.96	51.72	1,339.02	14,526,925.52	2,066,125.01	39° 59' 32.831 N	109° 28' 48.462 W
5,042.00	18.06	87.68	4,832.42	52.81	1,367.23	14,526,927.08	2,066,153.19	39° 59' 32.841 N	109° 28' 48.099 W
5,133.00	18.31	88.43	4,918.88	53.77	1,395.61	14,526,928.52	2,066,181.56	39° 59' 32.851 N	109° 28' 47.735 W
5,224.00	17.63	88.30	5,005.44	54.57	1,423.68	14,526,929.80	2,066,209.60	39° 59' 32.859 N	109° 28' 47.374 W
5,314.00	16.50	89.05	5,091.47	55.18	1,450.08	14,526,930.87	2,066,235.99	39° 59' 32.865 N	109° 28' 47.035 W
5,405.00	15.19	84.43	5,179.02	56.56	1,474.87	14,526,932.66	2,066,260.75	39° 59' 32.878 N	109° 28' 46.716 W
5,496.00	14.19	85.18	5,267.04	58.65	1,497.85	14,526,935.14	2,066,283.69	39° 59' 32.899 N	109° 28' 46.421 W
5,586.00	12.56	85.68	5,354.60	60.31	1,518.60	14,526,937.16	2,066,304.41	39° 59' 32.915 N	109° 28' 46.154 W
5,677.00	11.69	87.05	5,443.57	61.53	1,537.67	14,526,938.70	2,066,323.46	39° 59' 32.927 N	109° 28' 45.909 W
5,768.00	10.88	85.68	5,532.81	62.66	1,555.45	14,526,940.13	2,066,341.21	39° 59' 32.938 N	109° 28' 45.681 W
5,858.00	8.31	85.80	5,621.54	63.77	1,570.40	14,526,941.50	2,066,356.15	39° 59' 32.949 N	109° 28' 45.489 W
5,949.00	7.50	87.30	5,711.67	64.53	1,582.90	14,526,942.47	2,066,368.63	39° 59' 32.957 N	109° 28' 45.328 W
6,040.00	5.44	79.93	5,802.09	65.57	1,593.08	14,526,943.68	2,066,378.79	39° 59' 32.967 N	109° 28' 45.197 W
6,130.00	3.81	80.43	5,891.80	66.81	1,600.23	14,526,945.04	2,066,385.92	39° 59' 32.979 N	109° 28' 45.105 W
6,221.00	3.50	82.93	5,982.61	67.66	1,605.96	14,526,945.98	2,066,391.64	39° 59' 32.988 N	109° 28' 45.032 W
6,312.00	0.81	98.30	6,073.54	67.90	1,609.36	14,526,946.29	2,066,395.03	39° 59' 32.990 N	109° 28' 44.988 W

Company: ANADARKO PETROLEUM CORP.  
Project: UINTAH COUNTY, UTAH (nad 27)  
Site: NBU 922-31K PAD  
Well: NBU 922-31J2S  
Wellbore: NBU 922-31J2S  
Design: NBU 922-31J2S

Local Co-ordinate Reference: Well NBU 922-31J2S  
TVD Reference: PROD RIG KB @ 4854.00ft (ENSIGN 146)  
MD Reference: PROD RIG KB @ 4854.00ft (ENSIGN 146)  
North Reference: True  
Survey Calculation Method: Minimum Curvature  
Database: EDM 2003.21 Single User Db

Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Map Northing (ft)	Map Easting (ft)	Latitude	Longitude
6,402.00	0.81	113.18	6,163.53	67.56	1,610.57	14,526,945.97	2,066,396.25	39° 59' 32.987 N	109° 28' 44.972 W
6,493.00	0.87	125.58	6,254.52	66.91	1,611.72	14,526,945.33	2,066,397.41	39° 59' 32.980 N	109° 28' 44.958 W
6,584.00	1.00	126.05	6,345.51	66.04	1,612.93	14,526,944.49	2,066,398.63	39° 59' 32.972 N	109° 28' 44.942 W
6,674.00	0.50	351.68	6,435.50	65.96	1,613.51	14,526,944.42	2,066,399.21	39° 59' 32.971 N	109° 28' 44.935 W
6,765.00	0.38	339.18	6,526.50	66.64	1,613.34	14,526,945.09	2,066,399.03	39° 59' 32.978 N	109° 28' 44.937 W
6,856.00	1.06	349.30	6,617.49	67.75	1,613.08	14,526,946.20	2,066,398.75	39° 59' 32.989 N	109° 28' 44.940 W
6,946.00	0.88	356.43	6,707.48	69.26	1,612.88	14,526,947.70	2,066,398.53	39° 59' 33.004 N	109° 28' 44.943 W
7,037.00	0.56	34.68	6,798.47	70.32	1,613.09	14,526,948.77	2,066,398.72	39° 59' 33.014 N	109° 28' 44.940 W
7,128.00	0.63	81.68	6,889.47	70.76	1,613.84	14,526,949.22	2,066,399.46	39° 59' 33.018 N	109° 28' 44.930 W
7,218.00	0.69	289.05	6,979.47	71.01	1,613.82	14,526,949.47	2,066,399.43	39° 59' 33.021 N	109° 28' 44.931 W
7,309.00	1.56	329.55	7,070.45	72.25	1,612.67	14,526,950.69	2,066,398.27	39° 59' 33.033 N	109° 28' 44.945 W
7,400.00	1.31	340.93	7,161.42	74.30	1,611.70	14,526,952.73	2,066,397.26	39° 59' 33.054 N	109° 28' 44.958 W
7,491.00	1.25	335.68	7,252.40	76.19	1,610.95	14,526,954.60	2,066,396.48	39° 59' 33.072 N	109° 28' 44.967 W
7,581.00	1.06	341.05	7,342.38	77.87	1,610.28	14,526,956.27	2,066,395.78	39° 59' 33.089 N	109° 28' 44.976 W
7,669.00	0.64	347.32	7,430.37	79.12	1,609.91	14,526,957.52	2,066,395.39	39° 59' 33.101 N	109° 28' 44.981 W
7,760.00	0.44	346.80	7,521.37	79.96	1,609.72	14,526,958.35	2,066,395.18	39° 59' 33.109 N	109° 28' 44.983 W
7,851.00	0.19	37.05	7,612.36	80.42	1,609.73	14,526,958.81	2,066,395.19	39° 59' 33.114 N	109° 28' 44.983 W
7,942.00	0.38	105.43	7,703.36	80.46	1,610.11	14,526,958.86	2,066,395.57	39° 59' 33.114 N	109° 28' 44.978 W
8,032.00	0.44	136.68	7,793.36	80.13	1,610.63	14,526,958.53	2,066,396.10	39° 59' 33.111 N	109° 28' 44.972 W
8,123.00	0.75	117.93	7,884.36	79.60	1,611.40	14,526,958.01	2,066,396.87	39° 59' 33.106 N	109° 28' 44.962 W
8,214.00	0.81	118.18	7,975.35	79.01	1,612.49	14,526,957.45	2,066,397.97	39° 59' 33.100 N	109° 28' 44.948 W
8,304.00	1.06	110.18	8,065.34	78.42	1,613.83	14,526,956.89	2,066,399.33	39° 59' 33.094 N	109° 28' 44.930 W
8,395.00	1.25	123.18	8,156.32	77.59	1,615.46	14,526,956.08	2,066,400.96	39° 59' 33.086 N	109° 28' 44.910 W
8,486.00	1.63	120.93	8,247.29	76.38	1,617.40	14,526,954.90	2,066,402.92	39° 59' 33.074 N	109° 28' 44.885 W
8,576.00	2.31	125.05	8,337.24	74.68	1,619.98	14,526,953.25	2,066,405.53	39° 59' 33.057 N	109° 28' 44.851 W
8,667.00	2.25	127.30	8,428.16	72.55	1,622.90	14,526,951.16	2,066,408.49	39° 59' 33.036 N	109° 28' 44.814 W
8,787.00	2.19	157.80	8,548.08	69.00	1,625.64	14,526,947.66	2,066,411.29	39° 59' 33.001 N	109° 28' 44.779 W
8,848.00	1.81	152.18	8,609.04	67.07	1,626.53	14,526,945.74	2,066,412.21	39° 59' 32.982 N	109° 28' 44.767 W
8,939.00	2.00	151.18	8,699.99	64.40	1,627.97	14,526,943.11	2,066,413.70	39° 59' 32.956 N	109° 28' 44.749 W
9,029.00	1.94	145.68	8,789.94	61.77	1,629.58	14,526,940.50	2,066,415.36	39° 59' 32.930 N	109° 28' 44.728 W
9,120.00	2.00	153.93	8,880.88	59.07	1,631.15	14,526,937.83	2,066,416.97	39° 59' 32.903 N	109° 28' 44.708 W
9,211.00	2.06	146.93	8,971.83	56.27	1,632.74	14,526,935.06	2,066,418.61	39° 59' 32.875 N	109° 28' 44.687 W
9,301.00	2.50	148.68	9,061.75	53.24	1,634.64	14,526,932.06	2,066,420.56	39° 59' 32.845 N	109° 28' 44.663 W
9,365.00	2.50	140.93	9,125.69	50.97	1,636.25	14,526,929.81	2,066,422.20	39° 59' 32.823 N	109° 28' 44.642 W
EXT. TD									
9,421.00	2.50	140.93	9,181.64	49.07	1,637.79	14,526,927.94	2,066,423.78	39° 59' 32.804 N	109° 28' 44.623 W

Survey Annotations

Measured Depth (ft)	Vertical Depth (ft)	Local Coordinates +N/-S (ft)	+E/-W (ft)	Comment
9,421.00	9,181.64	49.07	1,637.79	EXT. TD

Checked By: \_\_\_\_\_ Approved By: \_\_\_\_\_ Date: \_\_\_\_\_

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> UO 1207A
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> KERR-MCGEE OIL & GAS ONSHORE, L.P.		<b>7. UNIT or CA AGREEMENT NAME:</b> NATURAL BUTTES
<b>3. ADDRESS OF OPERATOR:</b> P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		<b>8. WELL NAME and NUMBER:</b> NBU 922-31J2S
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 2552 FSL 1420 FWL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NESW Section: 31 Township: 09.0S Range: 22.0E Meridian: S		<b>9. API NUMBER:</b> 43047504170000
<b>PHONE NUMBER:</b> 720 929-6515 Ext		<b>9. FIELD and POOL or WILDCAT:</b> NATURAL BUTTES
<b>COUNTY:</b> UTAH		<b>STATE:</b> UTAH


11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start: 3/8/2011  <input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:  <input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:  <input type="checkbox"/> <b>DRILLING REPORT</b> Report Date:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input checked="" type="checkbox"/> <b>CASING REPAIR</b> <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <span style="border: 1px solid black; display: inline-block; width: 100px; height: 15px; vertical-align: middle;"></span>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.  
 The operator request approval to conduct wellhead/casing repair operations on the subject well location. Please find the attached procedures for the proposed repair work for the subject well location.

Approved by the  
Utah Division of  
Oil, Gas and Mining

Date: 03/09/2011

By: 

<b>NAME (PLEASE PRINT)</b> Gina Becker	<b>PHONE NUMBER</b> 720 929-6086	<b>TITLE</b> Regulatory Analyst II
<b>SIGNATURE</b> N/A		<b>DATE</b> 3/8/2011

**WORKORDER #:** 88119395

3/1/11

**Name:** NBU 922-31J2S - 922-31K PAD  
**Surface Location:** NESW SEC.31, T9S, R22E  
Uintah County, UT

**API:** 4304750417      **LEASE#:** UO 1207 A

**ELEVATIONS:** 4840' GL      4859' KB

**TOTAL DEPTH:** 9421'      **PBTD:** 9389'

**SURFACE CASING:** 9 5/8", 36# J-55 @ 2206'

**PRODUCTION CASING:** 4 1/2", 11.6#, I-80 @ 9408'  
TOC @ 1552' per CBL

**PERFORATIONS:** Wasatch 6768' - 6890'  
Mesaverde 7249' - 9226'

Tubular/Borehole	Drift inches	Collapse psi	Burst psi	Capacities		
				Gal./ft.	Cuft/ft.	Bbl./ft.
2.375" 4.7# J-55 tbg.	1.901	8100	7700	0.1624	0.02173	0.00387
4.5" 11.6# I-80	3.875	6350	7780	0.6528	0.0872	0.01554
9.625" 36# J-55	8.921	2020	3520	3.247	0.434	0.0773
<b>Annular Capacities</b>						
2.375" tbg. X 4 1/2" 11.6# csg				0.4227	0.0565	0.01006

**GEOLOGICAL TOPS:**

1266' Green River  
1525' Bird's Nest  
1993' Mahogany  
4566' Wasatch  
7233' Mesaverde

## **NBU 922-31J2S – WELLHEAD REPLACEMENT PROCEDURE**

### **PREP-WORK PRIOR TO MIRU:**

1. Dig out down to the 2" surface casing valve or to the valve on the riser off the surface casing.
2. Install a tee with 2 valves, with a pressure gauge and sensor on one valve.
3. Open casing valve and record pressures.
4. Install nipple and steel hose on the other valve, the relief valve,. Do not use hammer unions. No impact equipment or tools to be used for any of this installation. Extend hose and hard piping to a downwind location at least 100' from the wellhead. Consider installing a manifold so that vent area could be in two locations approx. 90 degrees apart from the wellhead.
5. Open the relief valve and blow well down to the atmosphere.
6. Make a determination of amount of gas flow, either by installation of a choke nipple, bucket test or other.
7. Shut well in. Observe for rate of build-up by utilizing sensor data. Do not build-up for more than 24 hours. Vent gas through the vent line and leave open to the atmosphere.

### **WORKOVER PROCEDURE:**

1. MIRU workover rig.
2. Kill well with 10# brine / KCL (dictated by well pressure ).
3. Remove tree, install double BOP with blind and 2 3/8" pipe rams, with accumulator closing unit and manual back-ups. Function test BOP system.
4. POOH w/ tubing laying down extra tubing.
5. Rig up wireline service. RIH and set CBP @ ~6718. Dump bail 4 sx cement on top of plug. POOH and RD wireline service. TIH w/ tubing and seating nipple. Land tubing ±60' above cement. RDMO.
6. Monitor well pressures. If surface casing is dead. MIRU. ND WH and NU BOP. POOH w/ tubing.
7. Depending on conditions at wellsite, continue with either CUT/PATCH Procedure or BACK-OFF Procedure.

### **CUT/PATCH PROCEDURE:**

1. PU internal casing cutters and RIH. Cut casing at +/- 30' from surface.
2. POOH, LD cutters and casing.
3. PU 7 3/8" overshoot with 4 1/2" right hand standard wicker grapple, 1 - 4 3/4" drill collar with 3 1/2" IF threads, pup joint, manual bumper sub, and crossovers. If casing cut is deeper than ±30' utilize >7000 ft-lb torque pipe as needed. Pull a minimum of 10,000# to keep grapple engaged if cement top is high (<~900'). If cement top is low (>~900'), more weight will be required to put casing in neutral. Torque casing string to ±7000 ft-lbs, count number of turns to make-up, and document in the daily report. Ensure that tongs are safely anchored to rig and that all personnel are at a safe working distance from the tongs during torque-up and torque release. After initial make-up, place pipe torque to neutral and mark pipe. Place ±7000 ft-lbs on casing a second time, count turns, then return pipe torque to neutral and count turns. Repeat if torque-up turns do not equal torque release turns. Once torque-in equals torque-out, release overshoot, POOH, and lay down.
4. TIH w/ skirted mill and dress off the fish top for approximately 1/2 hour. TOOH.
5. PU & RIH w/ 4 1/2" 10k external casing patch on 4 1/2" P-110 casing. Ensure that sliding sleeve assembly shifts ±3' and casing tags no-go portion of patch. NOTE: Shear pins will shear at 3500 to 4500 lbs.
6. Latch fish, PU to 100,000# tension. RU B&C. Cycle pressure test to 7,000# / 9,000# psi.
7. Install slips. Land casing w/ 80,000# tension.
8. Cut-off and dress 4 1/2" casing stub.
9. NUWH. PU 3 7/8" bit, POBS and RIH. D/O cement and plug ~6668'. Clean out to PBTD (9389').
10. POOH, land tbg and pump off POBS.
11. NUWH, RDMO. Turn well over to production ops.

### **BACK-OFF PROCEDURE:**

1. PU internal casing cutters and RIH. Cut casing at +/- 6' from surface.
2. POOH, LD cutters and casing.
3. PU 4 1/2" overshoot. RIH, latch fish. Pick string weight to neutral.
4. MIRU casing crew and wireline services. RIH and shoot string shot at casing collar @ ± 46'.
5. Back-off casing, POOH.



6. PU new casing joint with buttress threads and entry guide and RIH. Tag casing top. Thread into casing and torque up to  $\pm 7000$  ft-lbs, count number of additional turns to make-up, and document in the daily report. Ensure that tongs are safely anchored to rig and that all personnel are at a safe working distance from the tongs during torque-up and torque release. After initial make-up, place pipe torque to neutral and mark pipe. Place  $\pm 7000$  ft-lbs on casing a second time, count turns, then return pipe torque to neutral and count turns. Repeat if torque-up turns do not equal torque release turns. Once torque-in equals torque-out go to step 7.
7. PU 100,000# tension string weight. RU B&C. Cycle pressure test to 7,000# / 9,000# psi.
8. Install slips. Land casing w/ 80,000# tension.
9. Cut-off and dress 4 1/2" casing stub.
10. NUWH. PU 3 7/8" bit, POBS and RIH. D/O cement and plug ~6668'. Clean out to PBTD (9389').
11. POOH, land tbg and pump off POBS.
12. NUWH, RDMO. Turn well over to production ops.



---


## **Logan High Pressure Casing Patches Assembly Procedure**

All parts should be thoroughly greased before being assembled.


1. Install all four Logan Type "L" Packers in the spaces provided in the Casing Patch Bowl. Refer to diagram provided for proper installation.
2. Install Packer Protector from the Basket Grapple end of the Bowl. The beveled end of the Packer Protector goes in first. Carefully push the Packer Protector through the four Type "L" Packers.
3. Align Shear Pin Holes in Packer Protector so that the holes have just passed into the counter bore at the Top Sub end, refer to diagram. The Packer Protector is provided with four Shear Pin Holes. Use only two holes, 180 degrees apart and install the pins.
4. Screw the Basket Grapple in from the lower end of the Bowl, using left-hand rotation. The Tang Slot in the Basket Grapple must land in line with the slot in the Bowl.
5. Insert the Basket Grapple Control into the end of the Bowl. Align Tang on the Basket Grapple Control with the Tang Slot of the Bowl and Basket Grapple. This secures the Bowl and the Basket Grapple together.
6. Install the Cutlipped Guide into the lower end of the Bowl.
7. Install O-Rings on the two five-foot long Extensions. Screw the first Extension into the top end of the Bowl. Screw the second Extension into the top end of the first Extension.
8. Install O-Ring on Top Sub. Screw Top Sub into top end of second Extension.

Follow recommended Make-Up Torque as provided in chart.

510L-005-001 4-1/2" LOGAN HP CASING PATCH



**STRENGTH DATA FOR LOGAN 5.88" OD "L" TYPE CSG PATCH  
4-1/2 CASING, 10K PSI MAX WP 125K YIELD MAT'L  
LOGAN ASSEMBLY NO. 510L-005 -000**



COLLAPSE PRESSURE:  
11,222 PSI @ 0 TENSILE  
8,634 PSI @ 220K TENSILE

Tensile Strength @ Yield:  
Tensile Strength w/ 0 Int. Press.= 472,791lbs.  
Tensile Strength w/ 10K Int. Press.= 313,748lbs.

DATA BY SLS 11/16/2009

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> UO 1207A
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> KERR-MCGEE OIL & GAS ONSHORE, L.P.		<b>7. UNIT or CA AGREEMENT NAME:</b> NATURAL BUTTES
<b>3. ADDRESS OF OPERATOR:</b> P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		<b>8. WELL NAME and NUMBER:</b> NBU 922-31J2S
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 2552 FSL 1420 FWL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NESW Section: 31 Township: 09.0S Range: 22.0E Meridian: S		<b>9. API NUMBER:</b> 43047504170000
<b>11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</b>		<b>9. FIELD and POOL or WILDCAT:</b> NATURAL BUTTES
<b>11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</b>		
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 5/9/2011	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION	
<input type="checkbox"/> DRILLING REPORT Report Date:	OTHER: <input type="text" value="Wellhead Repair"/>	
<b>12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.</b>  The operator has concluded wellhead/casing repairs on the subject well location. Please see the attached chronological history for details of the operations.		
<b>Accepted by the          Utah Division of          Oil, Gas and Mining          FOR RECORD ONLY</b>		
<b>NAME (PLEASE PRINT)</b> Gina Becker		<b>PHONE NUMBER</b> 720 929-6086
<b>SIGNATURE</b> N/A		<b>TITLE</b> Regulatory Analyst II
<b>DATE</b> 5/9/2011		

## US ROCKIES REGION

### Operation Summary Report

Well: NBU 922-31J2S      PURPLE			Spud Conductor: 10/7/2009			Spud Date: 10/16/2009		
Project: UTAH-UINTAH				Site: NBU 922-31K PAD				Rig Name No: MILES-GRAY 1/1
Event: WELL WORK EXPENSE				Start Date: 3/18/2011				End Date:
Active Datum: RKB @4,855.00ft (above Mean Sea Leve				UWI: NE/SW/0/9/S/22/E/31/0/0/26/PM/S/2,611.00/E/0/1,837.00/0/0				
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
4/8/2011	7:00 - 7:15	0.25	WO/REP	48		P		JSA-SAFETY MEETING, TRIP TBG
	7:15 - 8:30	1.25	WO/REP	30	A	P		MIRU, PUMP 40 BBLS WTR DN TBG AND 60 BBLS DN CSG, N/D WH, N/U BOPS, R/U TBG EQUIP,
	8:30 - 11:30	3.00	WO/REP	31	I	P		TOOH W/ 2 3/8" L-80 TBG, TALLY TBG OUT, 261 JTS,
	11:30 - 13:25	1.92	WO/REP	34	I	P		R/U CUTTER WIRELINE, RIH W GAUGE RING TO 6750', RIH W/ BAKER 10K CBP, SET CBP @ 6718', RIH DUMP BAIL 4 SACKS CEMENT ON TOP OF CBP, R/D WIRELINE, PREPARE TO REPAIR WELL HEAD ON MONDAY, SDFWE
4/11/2011	7:00 - 7:30	0.50	WO/REP	48		P		JSA-SAFETY MEETING W/ WEATHERFORD, FRANKS CSG TONGS, CUTTER WIRELINE AND RIG CREW
	7:30 - 12:00	4.50	WO/REP	52	G	P		NO PRESSURE ON WELL, N/D BOPS AND TBG SPOOL, PACK OFF ON CSG HEAD WOULD NOT MOVE, R/U POWER SWIVEL, RIH W/ INSIDE CUTTER, CUT 4 1/2" CSG OFF 10' BELOW SURFACE, P/O LAYED DN, R/U POWER SWIVEL AND CSG TONGS, P/U OVERSHOT, RIH LATACH ON TO CSG, MADE SURE CSG TIGHT TO 2500#, RIH W/ WIRELINE STRING SHOT, SHOT STRING SHOT @ 134', FORTH COLLAR DN, BACK CSG OFF @ 134', R/D WIRELINE, P/O LAY 3 JTS CSG DN W/ CUT COLLARS OFF, P/U RIH W/ 1 JT 4 1/2" CSG W/ SKIRTED PIN, 2 JTS BUTTRESS CSG AND 1 12' SUB, SCREWED INTO 4 1/2" CSG @ 134', WORK CSG W/ WORKING TORQUE DN, 4 EXTRA TURN IN CSG TO GET 7000# TORQUE, R/D CSG TONGS
	12:00 - 13:00	1.00	WO/REP	33	C	P		R/U B & C QUICK TEST TO 4 1/2" CSG, PRESSURE TEST CSG W/ LOW TEST 1000# FOR 15 MIN, OK, HIGH TEST @ 3500# FOR 30 MIN W/ BLEED DN 27# IN 30 MIN, OK, R/D TESTER
	13:00 - 15:30	2.50	WO/REP	30		P		SET WEATHERFOFD C-22 SLIPS W/ 90,000# SET, CUT CSG STUB OFF, N/U NEW CSG HEAD AND TBG SPOOL, N/U BOPS, R/U TBG EQUIP.
	15:30 - 18:00	2.50	WO/REP	31	I	P		P/U 3 7/8" BIT & POBS, TIH W/ 2 3/8" TBG W/ BROACH TBG IN, TAG @ 6670', LAY DN 4 JTS, SWI SDFN,
4/12/2011	7:00 - 7:15	0.25	WO/REP	48		P		JSA-SAFETY MEETING, DRILL OUT W/ N2/ FOAM UNIT



**US ROCKIES REGION**  
**Operation Summary Report**

Well: NBU 922-31J2S    PURPLE			Spud Conductor: 10/7/2009			Spud Date: 10/16/2009			
Project: UTAH-UINTAH			Site: NBU 922-31K PAD				Rig Name No: MILES-GRAY 1/1		
Event: WELL WORK EXPENSE			Start Date: 3/18/2011				End Date:		
Active Datum: RKB @4,855.00ft (above Mean Sea Leve			UWI: NE/SW/0/9/S/22/E/31/0/0/26/PM/S/2,611.00/E/0/1,837.00/0/0						
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation	
	7:15   - 13:00	5.75	WO/REP	44	C	P		NO PRESSURE ON WELL, PRESSURE TEST BOPS TO 3000#, OK, R/U POWER SWIVEL AND N2 FOAM UNIT, ESTB CIRC DN TBG OUT CSG, TAG CEMENT @ 6670', DRILL OUT CEMENT TO 6718', DRILL OUT CBP @ 6718', NO PRESSURE INCREASE. CIRC WELL CLEAN, TIH TAG PBTD @ 9320', P/O LAY DN 33 JTS TBG ON TRAILER, LAND TBG W/ HANGER W/ 261 JTS 2 3/8" L-80 TBG, EOT @ 8286.45', N/D BOPS N/U WH, PUMP BIT OFF @ 1800#, SHUT WELL IN, SICP = 1100#, SITP = ZERC PRESSURE, R/D SERVICE UNIT, MOVE TO NEXT WELL, TURN WELL OVER TO CONSTRUCTION FOR SALE LINE HOOK UP,	
								40 BBLS WTR LTR	
								KB	

## DIVISION OF OIL, GAS AND MINING

### **SPUDDING INFORMATION**

Name of Company: KERR-McGEE OIL & GAS ONSHORE, L.P.

Well Name: NBU 922-31J2S

Api No: 43-047-50417 Lease Type: STATE

Section 31 Township 09S Range 22E County UINTAH

Drilling Contractor PETE MARTIN DRILLING RIG # BUCKET

### **SPUDDED:**

Date 10/07/2009

Time 2:00 PM

How

**Drilling will Commence:**

Reported by KENNY

Telephone # (435) 828-1691

Date 10/07/2009 Signed CHD

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 6

**ENTITY ACTION FORM**

Operator: KERR McGEE OIL & GAS ONSHORE LP Operator Account Number: N 2995  
Address: P.O. Box 173779  
city DENVER  
state CO zip 80217 Phone Number: (720) 929-6100

**Well 1**

API Number	Well Name		QQ	Sec	Twp	Rng	County
4304750417	NBU 922-31J2S		NESW	31	9S	22E	UINTAH
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
<u>B</u>	99999	<u>2900</u>	10/7/2009			<u>10/13/09</u>	
<b>Comments:</b> MIRU PETE MARTIN BUCKET RIG. <u>WSTMVD</u> SPUD WELL LOCATION ON 10/07/2009 AT 13:30 HRS. <u>BHL = NWSE</u>							

**Well 2**

API Number	Well Name		QQ	Sec	Twp	Rng	County
4304750415	NBU 922-31F2S		NESW	31	9S	22E	UINTAH
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
<u>B</u>	99999	<u>2900</u>	10/7/2009			<u>10/13/09</u>	
<b>Comments:</b> MIRU PETE MARTIN BUCKET RIG. <u>WSTMVD</u> SPUD WELL LOCATION ON 10/07/2009 AT 16:00 HRS. <u>BHL = SENW</u>							

**Well 3**

API Number	Well Name		QQ	Sec	Twp	Rng	County
4304750419	NBU 922-31F3S		NESW	31	9S	22E	UINTAH
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
<u>B</u>	99999	<u>2900</u>	10/8/2009			<u>10/13/09</u>	
<b>Comments:</b> MIRU PETE MARTIN BUCKET RIG. <u>WSTMVD</u> SPUD WELL LOCATION ON 10/08/2009 AT 09:00 HRS. <u>BHL = SENW</u>							

**ACTION CODES:**

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

ANDY LYTLE

Name (Please Print)

Signature

REGULATORY ANALYST

Title

10/8/2009

Date

**RECEIVED**

**OCT 08 2009**